

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT

SECRETARY

March 5, 2003

Addendum No. 1

RE:

Contract ID: C200683

Work Order No. 8.2603502 F. A. No. STP-0916 (6) Davidson County (U-3122) Peace Street at Norfolk Southern

Peace Street at Norfolk Southern Railway Crossing in Thomasville.

March 18, 2003 Letting

To Whom It May Concern:

Reference is made to the proposal furnished to you on the above mentioned project.

On Page No. 1, the liquidated damages amount shown in the project special provision entitled "Contract Time and Liquidated Damages" has been revised. Please void Page No. 1 in your proposal and staple the revised Page No. 1 thereto.

On Page No. 47, a paragraph was added to the utility construction provisions, subsection "Utility Locations shown on the plans." Please void Page No. 47 in your proposal and staple the revised Page No. 47 thereto.

Sincerely

R. A. Garris, P.E. Contract Officer

RAG/jag/pa (Attachments)

cc:

Mr. J. D. Goins, P.E.

Mr. Aydren Flowers

Mr. S. D. DeWitt, P.E.

Mr. Ron Davenport, Jr., P.E

Mr. S. P. Ivey, P.E.

Ms. Kim Canady

Ms. D. M. Barbour, P.E.

Ms. Yang Steelman

Mr. J. V. Barbour, P.E.

Project File (2)

Mr. Mark Staley (2)

WEBSITE: WWW.DOH.DOT.STATE.NC.US

LOCATION:

PROJECT SPECIAL PROVISIONS

General

7-1-95

SP1G01

CONTRACT TIME AND LIQUIDATED DAMAGES:

7-1-95

The date of availability for this contract is June 15, 2003.

The completion date for this contract is October 15, 2004.

When observation periods are required by the special provisions, they are not a part of the work to be completed by the completion date and/or intermediate contract times stated in the contract. Should an observation period extend beyond the final completion date, the acceptable completion of the observation period shall be a part of the work covered by the performance and payment bonds.

The liquidated damages for this contract are Two Thousand Dollars (\$2,000.00) per calendar day.

SP1G10

SAFETY INDEX RATING:

6-18-02

Revise the 2002 Standard Specifications as follows:

Page 1-10, Article 102-2

Before the last paragraph on this page, add the following paragraph:

"All subcontractors performing work for the Department shall have received a passing grade on the Safety Index Rating form, in accordance with Article 102-2, prior to beginning work. Subcontractors can request the Safety Index Rating form from the State Contractual Services Engineer."

SP1G14

MAJOR CONTRACT ITEMS:

2-1-02

The following listed items are the major contract items for this contract (See Articles 101-54 and 104-5 of the Standard Specifications):

SP1G28

Item No. Description

10-0106000000-M-230 Borrow Excavation
180-8147000000-M-420 Reinforced Concrete Deck Slab

Kevised 3-5-03

47

Project: U-3122 County: Davidson

monts, on other attackments

Any cracked, damaged, or defective pipe, fittings, valves, hydrants, or other attachments discovered as a result of the pressure test, shall be removed and replaced with sound material. The tests shall be repeated until test results are satisfactory.

After the pressure test is complete, the Contractor shall make a leakage test. Such leakage test shall last at least 2 hours at a pressure of 1.38 MPa.

The pressure test and leakage test may be performed concurrently.

All valves on the lines being sterilized shall be opened and closed several times during the chlorinating period. The pipeline shall then be flushed with clean water until the residual chlorine is reduced to less than 1.0 ppm or at the same level as in the existing water mains. Samples of water shall be taken at representative points along the pipeline by the Contractor in approved containers and submitted to a certified testing laboratory for bacterial and chlorine content. Test results shall be provided to the City of Thomasville as soon as they are made available to the Contractor.

Utility Locations Shown on the Plans:

The locations, sizes, and type material of the existing utilities shown on the plans are from the best available information. The Contractor will be responsible for determining the exact location, size, and type material of the existing facilities necessary for the construction of the proposed utilities and to avoid damage to existing facilities.

 $\overline{\text{MOTE}}$: The Contractor will not be allowed to perform the utility work on the 150mm or 400mm water line, or the two 300mm force main sewer lines located inside the NCRR right-of-way until July 1, 2003 unless specifically directed otherwise in writing by the Engineer.

Services will be checked for leaks, cracked, broken, or missing pipe, deformed pipe and grade.

Upon notification from the utility owner(s) advising that the line has passed final inspection, the Engineer shall complete the Engineer's Certification and send to the Division of Environmental Management with a copy to the City of Thomasville. The utility owner shall then issue an acceptance letter for the line.

COMPENSATION:

No direct payment will be made for utility construction work required by the preceding provisions, which are general requirements applying to utility construction, and all of the requirements stated will be considered incidental work, paid for at the contract unit prices of the various utility items included in the contract.