



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

March 6, 2003

Addendum No. 1

RE: Contract ID: C200559
Work Order No. 8.1403905
F. A. No. HPSTP-55 (28)
Wake County (R-2906A)
NC-55 From North of US-64
To North of SR-1726.

March 18, 2003 Letting

To Whom It May Concern:

Reference is made to the plans and proposal furnished to you on the above mentioned project.

The following revision has been made to the roadway plans:

On the drainage summary sheet numbers 3-F, 3-G and 3-O the thickness of the 48" welded steel pipe has been revised to 0.500". Please void sheet No.'s 3-F, 3-G and 3-O in your plans and staple the revised sheets thereto.

The following revisions have been to the proposal form:

On Page 3 and 3-A, two more delay in entries have been added. Please void Page 3 in your proposal form and staple the revised Page 3 thereto. Please staple the additional Page 3-A behind Page 3 in your proposal form.

The Table of Contents has been revised to reflect the above revisions.

On Page 3 of 17 of the Item Sheets, Line No. 42-0980000000-E-SP "48" Welded Steel Pipe 0.109" Thick, Grade B, Installed by Boring and Jacking" has been revised. Please draw a single line thru 0.109 "and insert 0.500" and initial same in ink. (Sample Attached)

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACTS & PROPOSALS
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4124
FAX: 919-250-4127


WEBSITE: WWW.DOH.DOT.STATE.NC.US

LOCATION:
CENTURY CENTER COMPLEX
BUILDING B - ENTRANCE B15
1020 BIRCH RIDGE DRIVE
RALEIGH NC

On Page 12 of 17 of the Item Sheets, Line No. 202-584000000-E-1540 "24" Steel Encasement Pipe, 2.250 "Thick, By Open Cut" has been revised. Please draw a single line thru 2.250" and insert 0.250" and initial same in ink. (Sample Attached)

The Expedite file has been updated to reflect this revision. Please download the Expedite addendum file and follow the instructions for applying the addendum. Bid Express will not accept your bid unless all addendums have been applied.

Sincerely,



R. A. Garris, P.E.
Contract Officer

RAG/rdk/pa
(Attachments)

cc: Mr. J. D. Goins, P.E.
Mr. S. D. DeWitt, P.E.
Mr. J. G. Nance, P.E.
Ms. D. M. Barbour, P.E.
Mr. J. V. Barbour, P.E.
Mr. J. A. Bennett, P.E.
Mr. Mark Staley (2)

Mr. Aydren Flowers
Mr. Ron Davenport, Jr., P.E.
Ms. Kim Canady
Ms. Yang Steelman
Project File (2)

Revised 3-6-03

PROJECT: 8.1403905
WAKE COUNTY

TABLE OF CONTENTS

COVER SHEET	
PROPOSAL SHEETS	
PROJECT SPECIAL PROVISIONS (GREEN SHEETS)	PAGE NO.
Contract Time and Liquidated Damages.....	1
Intermediate Contract Time (s).....	1 - 3
Safety Index Rating.....	3
Delay in Right of Entry.....	3 - 3-A
Notice to Bidders.....	3-A - 4
Major Contract Items.....	4
Specialty Items.....	4
Fuel Price Adjustment.....	5
Execution of Signature Sheets and Debarment Certification.....	5
Submission of Bids.....	5 - 6
Schedule of Estimated Completion Progress.....	6
On-Line Electronic Bidding.....	6 - 7
Disadvantaged Business Enterprise.....	7 - 16
Retainage and Prompt Payment.....	16 - 17
Certification for Federal-Aid Contracts.....	17 - 18
Contractor's License Requirements.....	18
Domestic Steel and Iron Products.....	18 - 19
U.S. Department of Transportation Hotline.....	19
Submission of Records - Federal-Aid Projects.....	19
Subsurface Information.....	19
Payments for Materials – Portable Concrete Barrier.....	19 - 20
Payments for Materials – Removable Pavement Marking Material.....	20
Borrow Criteria.....	20
Plant Pest Quarantines.....	20 - 21
Cooperation Between Contractors.....	21
Training Requirements.....	21
Safety Vests.....	21
Roadway.....	22 - 63
Utility Construction.....	64 - 72
Utility Conflicts.....	73 - 74
Erosion Control.....	75 - 82
Signals and Traffic Management Systems.....	83 - 109
Project Special Provisions Culverts.....	110 - 125
Permits (WHITE SHEETS).....	126 - 239

The date of availability for this intermediate contract time will be the date the Contractor elects to begin the work.

The completion date for this intermediate contract time will be the date which is 21 consecutive calendar days after and including the date the Contractor begins the work.

The liquidated damages are Five Hundred Dollars (\$500.00) per day.

SAFETY INDEX RATING:

6-18-02

Revise the 2002 Standard Specifications as follows:

Page 1-10, Article 102-2

Before the last paragraph on this page, add the following paragraph:

"All subcontractors performing work for the Department shall have received a passing grade on the Safety Index Rating form, in accordance with Article 102-2, prior to beginning work. Subcontractors can request the Safety Index Rating form from the State Contractual Services Engineer."

SP1G14

DELAY IN RIGHT OF ENTRY:

7-1-95

The Contractor will not be allowed right of entry to the parcels listed below before November 1, 2003 unless otherwise permitted by the Engineer.

SP1G22

<u>Parcel No.</u>	<u>Property Owner</u>
56	Mastec North America

NOTE: This delay is only for part of Parcel No. 56. The area needed to be delayed is from Station 256+50 to 259+00 RT of Line -L-.

DELAY IN RIGHT OF ENTRY:

7-1-95

The Contractor will not be allowed right of entry to the parcels listed below before June 2, 2003 unless otherwise permitted by the Engineer.

SP1G22

<u>Parcel No.</u>	<u>Property Owner</u>
6	M.P., NC, LP
7	Michael J. Holland
26	Shell Oil Company
51	Brook Arbor Company, LLC
63	Dorothy Cooke
65	Paul W. Phillips Estate

201 & 203
206
210
215
221

Betty Hockaday
Herman Edwards
Warren Hill
Terry Slate
Heartland Durham/Cary Ltd.

DELAY IN RIGHT OF ENTRY:

7-1-95

The Contractor will not be allowed right of entry to the parcels listed below before July 1, 2003 unless otherwise permitted by the Engineer.

SP1G22

Parcel No.

Property Owner

8
50

Gregory Keith Roberts
James Wade Russell

NOTICE TO BIDDERS:

7-1-95

Project 8.1403904 Wake, Durham Counties from North Proposed I 540 to SR 1121 (Cornwallis Road) in Durham

Project 8.1403905 Wake County NC 55 from North of US 64 to North of SR 1726

On the above projects, the following Proposal Forms are available.

- | | | |
|------------------------------|---|-------------------|
| Proposal Form No. 1 | - | Project 8.1403904 |
| Proposal Form No. 2 | - | Project 8.1403905 |
| Combined Proposal Form No. 3 | | Project 8.1403904 |
| | | Project 8.1403905 |

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	244 LF		
0037	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	36 LF		
0038	0732000000-E	310	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	8 LF		
0039	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	47 EA		
0040	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	5 EA		
0041	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	10 EA		
0042	0980000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (48", 0.409") <i>0,500" Pak</i>	660 LF		
0043	0986000000-E	SP	GENERIC PIPE ITEM POLYMER LINE DRAIN	192 LF		
0044	0992000000-E	SP	GENERIC PIPE ITEM 48" X 24" RC PIPE TAPERED INLET, CLASS III	1 EA		
0045	0992000000-E	SP	GENERIC PIPE ITEM 54" X 30" RC PIPE TAPERED INLET, CLASS III	2 EA		
0046	0995000000-E	340	PIPE REMOVAL	4,111 LF		
0047	0996000000-N	350	PIPE CLEAN-OUT	9 EA		
0048	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0049	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	1,000 LB		
0050	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	26,587 SY		
0051	1066000000-E	501	LIME FOR LIME TREATED SOIL	275 TON		
0052	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0195	5750000000-E	1520	*** DI FORCE MAIN SEWER PIPE, PC ***** (14", 350)	118	LF	
0196	5750000000-E	1520	*** DI FORCE MAIN SEWER PIPE, PC ***** (16", 250)	58	LF	
0197	5756000000-E	1520	DUCTILE IRON SEWER PIPE FIT- TINGS, ***** (350# WP)	2,440	LB	
0198	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2	EA	
0199	5804000000-E	1530	FILL OR REMOVE ABANDONED 12" PIPE, ***** (DI WATER)	326	LF	
0200	5816000000-N	1530	BREAK DOWN, PLUG, & FILL ABAN- DONED UTILITY MANHOLE	1	EA	
0201	5822000000-N	1530	BREAK DOWN & REBUILD EXISTING MANHOLE	3	EA	
0202	5840000000-E	1540	*** STEEL ENCASMENT PIPE, ***** THICK, BY OPEN CUT (24", 2-250 THICK) <i>0.250" Rok</i>	42	LF	
0203	5882000000-N	SP	GENERIC UTILITY ITEM 2" COMBINATION AIR RELEASE VALVE & MANHOLE	1	EA	
0204	5882000000-N	SP	GENERIC UTILITY ITEM 24" SPLIT RING RETAINER GLANDS	3	EA	
0205	5882000000-N	SP	GENERIC UTILITY ITEM BLOWOFF ASSEMBLY	1	EA	
0206	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXT COMBINATION AIR RELEASE VALVE	1	EA	
0207	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE EXISTING BLOWOFF	1	EA	
0208	5882000000-N	SP	GENERIC UTILITY ITEM WATER METER ASSEMBLY	1	EA	
0209	6000000000-E	1605	TEMPORARY SILT FENCE	12,745	LF	