



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

September 9, 2002

Addendum No. 1

RE: State Project: 6.241004R, Etc.
Duplin County
NC-111 From NC-11 to Wayne
County Line, 3 Sections of NC-903
And 12 Sections of Secondary Roads.

SEPTEMBER 17, 2002 Letting

To Whom It May Concern:

Reference is made to the proposal form recently furnished to you on the above project.

The following revision has been made to the proposal form:

The item sheets do not include the pay items for guardrail or type 350 Anchor Units as shown on Sheet no. 8 of 11 of the sketch maps.

Page no. 18 has been revised to include the project special provision entitled "Guardrail Anchor Units Type 350". Please void page no. 18 in your proposal form and staple the revised page no. 18 thereto.

Page no. 18-A has been added to include the project special provision for "Steel Beam Guardrail". Please staple page no. 18-A to the revised page no. 18 in your proposal form.

The Table of Contents has been revised to reflect the above revisions.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, P.E.
Contract Officer

RAG/rdk/pa
(Attachments)

cc: Mr. J. D. Goins, P.E.
Mr. S. D. DeWitt, P.E.
Mr. H. A. Pope, P.E.
Ms. D. M. Barbour, P.E.
Mr. J. V. Barbour, P.E.
Mr. Mark Staley (2)
Mr. Ayden Flowers
Mr. R. E. Davenport, Jr., P.E.
Mr. J. A. Bennett, P.E.
Ms. Kim Canady
Ms. Yang Steelman
Project File (2)

Project: 6.241004R
Duplin County

TABLE OF CONTENTS

COVER SHEET
PROPOSAL SHEETS
PROJECT SPECIAL PROVISIONS (GREEN SHEETS) PAGE NO.

Notice to Bidders.....	1
Contract Time and Liquidated Damages.....	2
Prosecution of Work.....	2
Safety Index Rating.....	2
Railroad Grade Crossing.....	3
Major Contract Items.....	3
Specialty Items.....	3
Posted Weight Limits.....	3
Notes to Contractor.....	4 - 5
Execution of Signature Sheets and Debarment Certification.....	5
Schedule of Estimated Completion Progress.....	5 - 6
On-Line Electronic Bidding.....	6 - 7
Minority and Women Business.....	7 - 15
Retainage and Prompt Payment.....	16
Partial Payments.....	16
Domestic Steel Products.....	16 - 17
Plant Pest Quarantines.....	17 - 18
Safety Vests and Guardrail Anchor Units, Type 350.....	18
Steel Beam Guardrail.....	18 - A
Roadway.....	19 - 38
Erosion Control.....	39 - 40
Traffic Control.....	41 - 47
Sketch Map.....	

STANDARD SPECIAL PROVISIONS (YELLOW SHEETS)

Availability of Funds.....	1
Seed Quality Requirements.....	2 - 4
Errata.....	5 - 6
Minimum Wages.....	7

PROPOSAL FORM ITEM SHEETS, ETC.

- Item Sheets
- Award Limits
- Signature

Project 6.241004R, etc.

Duplin County

9. Any other products, articles, or means of conveyance, of any character, if determined by an inspector to present a hazard of spreading witchweed, imported fire ant or other noxious weeds.

RG84

SAFETY VESTS:

6-19-01

All Contractors' personnel, all subcontractors and their personnel, and any material suppliers and their personnel must wear an OSHA approved reflective vest or outer garment at all times while on the project.

RG87

GUARDRAIL ANCHOR UNITS, TYPE 350:

12-15-98

DESCRIPTION:

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the Standard Specifications, and at locations shown in the plans.

MATERIALS:

The Contractor may, at his option, furnish any one of the guardrail anchor units.

Guardrail anchor unit (ET-2000) as manufactured by:

TRINITY INDUSTRIES, INC.
2525 N. STEMMONS FREEWAY
DALLAS, TEXAS 75207
TELEPHONE: 1-800-644-7976

The guardrail anchor unit (SKT 350) as manufactured by:

ROAD SYSTEMS, INC.
3616 OLD HOWARD COUNTY AIRPORT
BIG SPRING, TEXAS 79720
TELEPHONE : (915) 263-2435

CONSTRUCTION:

Perform installation in accordance with the details in the plans and details and assembling instructions furnished by the Manufacturer.

Guardrail end delineation is required on all approach and trailing end guardrail buffer end sections for both temporary and permanent. Guardrail end delineation consists of yellow reflective sheeting applied to the entire buffer end section of the guardrail in accordance with Section 1088-3 of the Standard Specifications and is incidental to the cost of the guardrail anchor unit.

No direct payment will be made for the above described work, as such work shall be included in the contract unit price per ton for "Asphalt Concrete Surface Course, Type S9.5A".

Project 6.241004R, etc.

Duplin County

STEEL BEAM GUARDRAIL:

Furnish and install Steel Beam Guardrail in accordance with Section 862 of the Standard Specifications.

No direct payment will be made for "Steel Beam Guardrail" as such work shall be included in the contract unit price per ton for "Asphalt Concrete Surface Course, Type S9.5A".