



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

August 15, 2002

Addendum No. 1

RE: State Project: 6.549008T, 6.569006T, 6.569007T
Lee-Moore Counties (R-210C, R-210A, R-210B)
US-1 From South of SR-1853 and SR-2175,
North of Lakeview to SR-1180 South of Sanford.

SEPTEMBER 17, 2002 Letting

To Whom It May Concern:

Reference is made to the cross-section plans and proposal recently furnished to you on the above project.

The following revision has been made to the proposal form:

On page no. 23 the project special provision entitled "Survey Line Coordinate Data" has been added. Please void page no. 23 in your proposal and staple the revised page no. 23 thereto.

The following corrections are being made to the Roadway Cross-Section plans.

The following sheets were inadvertently omitted from the plans:

From R-210B, X-44A, X-44B, X-45, X-45A, X-45B and X-46.

From R-210C, X-17 thru X-27.

Please staple these sheets in the appropriate locations within your plans.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, P.E.
Contract Officer

RAG/jag/pa
(Attachments)

cc: Mr. J. D. Goins, P.E.
Mr. S. D. DeWitt, P.E.
Mr. W. F. Rosser, P.E.
Ms. D. M. Barbour, P.E.
Mr. J. V. Barbour, P.E.
Mr. Mark Staley (2)
Mr. Aydren Flowers
Mr. R. E. Davenport, Jr., P.E.
Ms. Kim Canady
Ms. Yang-Ju Lin
Project File (2)

PROJECT SPECIAL PROVISIONS

Roadway

7-1-95
SP1R01**SURVEY LINE COORDINATE DATA:**

A printout of the survey line coordinate data for this project is available without charge upon request.

CLEARING AND GRUBBING:

9-17-02

Perform clearing on this project to the limits established by Method "III" shown on Standard No. 200.03 of the Roadway Standards. SP2R01

The 2002 Standard Specifications shall be revised as follows:

Page 2-3, Article 200-5

Delete the first sentence of this article and insert the following:

The property owner will have no right to use or reserve for his use any timber on the project. All timber cut during the clearing operations is to become the property of the Contractor, and shall be either removed from the project by him, or else shall be satisfactorily disposed of as hereinafter provided.

BUILDING REMOVAL:

01-01-02

Remove the buildings and appurtenances listed below in accordance with Section 215 of the Standard Specifications and the following provisions:

Prior to removal of any building, comply with the notification requirements of Title 40 Code of Federal Regulations, Part 61, Subpart M, which are applicable to asbestos. Give notification to the North Carolina Department of Health and Human Services, Division of Epidemiology, Asbestos Hazard Management Branch and/or the appropriate county agency when enforcement of the Federal Regulation is performed by the county. Submit a copy of the notification to the Engineer prior to the building removal.

The Department has performed asbestos assessments for building items identified below. Copies of this report may be obtained through the Division Right-of-Way Agent. When asbestos is discovered after the opening of bids for the project, the cost of asbestos removal and disposal will be paid for in accordance with Article 104-7 of the Standard Specifications. Perform removal and disposal of asbestos in accordance with the requirements of Title 40 Code of Federal Regulations.

When a building has had or will have asbestos removed and the Contractor elects to remove the building such that it becomes a public area, the Contractor is responsible for any additional costs incurred including final air monitoring.