



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

September 9, 2002

Addendum No. 1

RE: State Project: 6.201008R, 6.241004R, Etc.
Lenoir-Duplin Counties
US-70 From Wayne County to
Southwest Creek Bridge, NC-111 From
NC-11 to Wayne County, 3 Sections of
NC-903 and 12 Sections of Secondary Roads.

SEPTEMBER 17, 2002 Letting

To Whom It May Concern:

Reference is made to the proposal form recently furnished to you on the above project.

The following revision has been made to the proposal form:

The item sheets do not include the pay items for guardrail or type 350 Anchor Units as shown on Sheet no. 8 of 11 of the sketch maps for Duplin County.

Page no. 18-A has been added to include the project special provision entitled "Guardrail Anchor Units Type 350" and "Steel Beam Guardrail". Please staple page no. 18-A to page 18 in your proposal form.

The Table of Contents has been revised to reflect the above revisions.

Sincerely,

R. A. Garris, P.E.
Contract Officer

RAG/rdk/pa
(Attachments)

cc: Mr. J. D. Goins, P.E.
Mr. S. D. DeWitt, P.E.
Mr. H. A. Pope, P.E.
Ms. D. M. Barbour, P.E.
Mr. J. V. Barbour, P.E.
Mr. Mark Staley (2)
Mr. Aydren Flowers
Mr. R. E. Davenport, Jr., P.E.
Mr. J. A. Bennett, P.E.
Ms. Kim Canady
Ms. Yang Steelman
Project File (2)

Revised 9/9/02

PROJECT: 6.201008R, ETC.
LENOIR / DUPLIN COUNTIES

TABLE OF CONTENTS

COVER SHEET

PROPOSAL SHEETS

PROJECT SPECIAL PROVISIONS (GREEN SHEETS)

PAGE NO.

Notice to Bidders.....	1
Contract Time and Liquidated Damages.....	2
Intermediate Contract Time (s).....	2 - 3
Prosecution of Work.....	3
Safety Index Rating.....	3
Railroad Grade Crossing.....	4
Major Contract Items.....	4
Specialty Items.....	4
Cooperation Between Contractors for Lenoir County.....	4 - 5
Posted Weight Limits for Duplin County.....	5
Execution of Signature Sheets and Debarment Certification.....	5
Schedule of Estimated Completion Progress.....	5 - 6
On-Line Electronic Bidding.....	6 - 7
Minority and Women Business.....	7 - 15
Retainage and Prompt Payment.....	15-16
Partial Payments.....	16
Submission of Bids - Alternates.....	16
Domestic Steel Products.....	17
Plant Pest Quarantines.....	17 - 18
Safety Vests.....	18
Guardrail Anchor Units, Type 350 and Steel Beam Guardrail.....	18 - A
Roadway.....	19 - 65
Erosion Control.....	66 - 69
Traffic Control.....	70 - 82
Sketch Map.....	

STANDARD SPECIAL PROVISIONS (YELLOW SHEETS)

Availability of Funds.....	1
Seed Quality Requirements.....	2 - 4
Errata.....	5 - 6
Minimum Wages.....	7

PROPOSAL FORM ITEM SHEETS, ETC.

Item Sheets
Award Limits
Signature

Project 6.201008R & 6.241004R, etc.

Lenoir & Duplin Counties

GUARDRAIL ANCHOR UNITS, TYPE 350:

12-15-98

DESCRIPTION:

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the Standard Specifications, and at locations shown in the plans.

MATERIALS:

The Contractor may, at his option, furnish any one of the guardrail anchor units.

Guardrail anchor unit (ET-2000) as manufactured by:

TRINITY INDUSTRIES, INC.
2525 N. STEMMONS FREEWAY
DALLAS, TEXAS 75207
TELEPHONE: 1-800-644-7976

The guardrail anchor unit (SKT 350) as manufactured by:

ROAD SYSTEMS, INC.
3616 OLD HOWARD COUNTY AIRPORT
BIG SPRING, TEXAS 79720
TELEPHONE : (915) 263-2435

CONSTRUCTION:

Perform installation in accordance with the details in the plans and details and assembling instructions furnished by the Manufacturer.

Guardrail end delineation is required on all approach and trailing end guardrail buffer end sections for both temporary and permanent. Guardrail end delineation consists of yellow reflective sheeting applied to the entire buffer end section of the guardrail in accordance with Section 1088-3 of the Standard Specifications and is incidental to the cost of the guardrail anchor unit.

No direct payment will be made for the above described work, as such work shall be included in the contract unit price per ton for "Asphalt Concrete Surface Course, Type S9.5A".

STEEL BEAM GUARDRAIL:

Furnish and install Steel Beam Guardrail in accordance with Section 862 of the Standard Specifications.

No direct payment will be made for "Steel Beam Guardrail" as such work shall be included in the contract unit price per ton for "Asphalt Concrete Surface Course, Type S9.5A".