




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

November 17, 2009

Notice To: Prospective Bidders and Materials Suppliers

From: R. A. Garris, PE 
State Contract Officer

Subject: Revised Drainage Pipe Standard Details and Pipe Alternates/Drainage
Summary Revisions

Beginning with the October 2009 letting, the standard installation details for drainage pipe are revised and will be included in the two series sheets within the plans. In addition, Section 300 of the 2006 Standard Specifications has been revised and is included in the proposals as a project special provision. The major revisions are summarized as follows:

- Method A and Method B installation types are no longer referenced.
- There are separate details for flexible and rigid pipes.
- No direct payment will be made for select backfill and bedding material and it is considered incidental to the pipe.
- Line item payment is provided for foundation conditioning material and foundation conditioning fabric when required.
- For Reinforced Concrete Pipes, which require fill heights greater than 40', there is a special provision titled "Reinforced Concrete Pipe Design." This provision requires the contractor to submit a site specific pipe design for review and approval.

Beginning with the January 2010 letting, in addition to the revised drainage pipe installation details, a new Project Special Provision to expand the use of alternate drainage pipe materials was developed. This provision titled "Drainage Pipe" will be included in designated projects. Sections 310 and 1032 of the Standard Specifications have been modified to reflect the new requirements for Drainage Pipe selection. The revisions are summarized below:

- Modifications to the Drainage Summary and Estimate Plan Sheets have been made and the summary will have columns for ___" Drainage Pipe and/or ___" Side Drain Pipe.
- The associated pay items will also be designated ___" Drainage Pipe and ___" Side Drain Pipe. The use of the "Drainage Pipe" item will be limited to Regional and Sub-Regional tier facilities as determined by NCDOT. Statewide Tier facilities will not use the "Drainage Pipe" item, but will use the "Side Drain Pipe" pay item as defined in the revised Article 310-4 of the Specifications. Where allowed by the plans and contract document, contractors will be allowed to bid these items without specifying the material type at bid time. This will eliminate the need for multiple alternate bid items.

If you have questions regarding this revision please contact Joel Howerton at 919-250-4128 or jhowerton@ncdot.gov.

MAILING ADDRESS:

NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119

WEBSITE: WWW.NCDOT.ORG

LOCATION:

CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC 27610



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

September 22, 2009

Notice To: Prospective Bidders and Material Suppliers

From: R.A. Garris, PE 
State Contract Officer

Subject: Counting of Material Costs for Meeting DBE, MBE or WBE Advertised Goals

The Department has received many questions regarding the use of DBE, MBE or WBE firms in a supplier role to count as participation on a contract to meet the advertised goal(s). Typically, DBEs, MBEs and WBEs do not act as suppliers on a contract. There are exceptions however, when a bidder can count expenditures with DBEs, MBEs or WBEs for materials or supplies toward advertised goals as provided by the following:

- 1) If the materials or supplies are obtained from a DBE, MBE or WBE manufacturer, 100 percent of the cost of the materials or supplies counts toward the advertised goal(s).

For purposes of clarification, a "manufacturer" is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.

- 2) If the materials or supplies are purchased from a DBE, MBE or WBE regular dealer, 60 percent of the cost of the materials or supplies counts toward the advertised goal(s).

For purposes of clarification, a "regular dealer" is a firm that own, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are being bought, kept in stock, and regularly sold or leased to the public in the usual course of business.

In addition, to be a regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119

WEBSITE: WWW.NCDOT.ORG

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

A person may be regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis.

Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not regular dealers.

- 3) With respect to materials or supplies purchased from a DBE, MBE or WBE which is neither a manufacturer nor a regular dealer, the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, can be counted toward the advertised goal(s), provided that it is determined by the Department that the fees are reasonable and not excessive as compared with fees customarily allowed for similar services. Any portion of the cost of the materials and supplies themselves will not count toward the advertised goal(s).

If you have any questions, contact Mr. Michael McKoy (mmkoy@ncdot.gov) or Terry Canales (tcanales@ncdot.gov) at 919-733-7174.




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

July 21, 2009

Notice To: Prospective Bidders, Material Suppliers, and Subcontractors

From: R.A. Garris, P.E. 
State Contract Officer

Subject: ***2006 Metric Standard Specifications for Roads and Structures and 2006 Metric Roadway Standard Drawings***

In 1999, the North Carolina Department of Transportation elected to return to the English measurement system when developing project plans as a result of the elimination of the FHWA metric requirement in the 1998 TEA 21 legislation. However, design efforts had already begun on approximately sixty projects utilizing the metric measurement system. Of those, some remained metric and were let under the 2002 Specifications and Standards, and some were re-engineered (converted) to English plans. Currently, there are fourteen projects that will be designed, let and constructed utilizing the 2006 Metric Specifications and Standards. See attached list for project information and tentative let dates.

The Metric Specifications Book is a mirror image of the 2006 (English) Specifications Book, except for the conversion to metric units and dimensions. The 2006 Metric Standard Drawings is a mirror image of the 2006 (English) Standard Drawings, except that Standards 840.25 and 700.01 have been updated to match Details 840D25 and 700D01. The Specifications and Standards are available in .pdf on the Projects Services Website at:
<http://www.ncdot.org/doh/preconstruct/ps/contracts/default.html>

The 2006 Metric Specifications and Standards are being printed within the Department and are available for purchase. Due to the small number of metric projects to be let over the next several years, a limited number will be printed. Therefore we ask that you review the attached list of projects and not order immediately if projects of interest to you are further out in the future. This will allow us to manage the printing demands much more efficiently. The 2006 Metric Standard Specifications for Roads and Structures and the 2006 Metric Roadway Standard Drawings are \$25.00 each plus 6.75% North Carolina sales tax. To request a copy, please contact Rick Montanez at 919-250-4014, or place your order electronically at the following Website:
<http://www.ncdot.org/doh/preconstruct/altern/value/manuals/puborder.html>

If you have any questions, I can be reached at (919) 250-4128.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119
WEBSITE: WWW.NCDOT.ORG

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

UPDATED JULY 17, 2009

TIP#	DIVISION	COUNTY	DESCRIPTION	TENTATIVE LET DATE
R-2814A	5	WAKE	US 401 FROM SR 2044 TO NORTH OF SR 2226	DECEMBER 15, 2009
R-2824	13	BURKE	SR 1546 FROM SR 1545 TO SR 1001	JUNE 15, 2010
R-2414B	1	CAMDEN	US 158/NC 34 FROM NORTH OF SR 1257 TO EAST OF NC 34 IN BELCROSS	DECEMBER 21, 2010
R-2519A	13	YANCEY	US 19 EAST FROM SR 1336 TO NC 80	MAY 17, 2011
R-2413C	7	GUILFORD ROCKINGHAM	NC 68 CONNECTOR -US 220 FROM THE HAW RIVER TO EXISTING NC 68/US 220 INTERSECTION	JANUARY 17, 2012




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

March 24, 2009

NOTICE TO: All Prospective Bidders

FROM: R. A. Garris, P.E. 
State Contract Officer

SUBJECT: Changes to the Implementation Dates for the Work Zone Traffic Control
Qualification and Training Program

As you may know the Department is pursuing a Work Zone Traffic Control Qualification and Training Program for anyone working within the NCDOT right of way. This program is part of our compliance with the FHWA Safety & Mobility Rule (23 CFR 630 subpart j). As a result of feedback from our industry partners (mostly due to the economy and our desire not to implement a timeline that we know some will not be able to meet), the NCDOT has postponed the implementation dates of the program one year. The new implementation dates are as follows:

Flagger Qualifications and Training - July 1, 2010
Installer Qualifications and Training - January 1, 2011
Supervisor Qualifications and Training - July 1, 2011

In the next year, the Department will reconsider the on the job training (OJT) requirement for flaggers as we have gotten strong feedback that most small companies and municipalities will not be able to obtain the present requirement of 40 hours of OJT. We plan to investigate the common practice of other State DOT's and intend for our program to be similar to those OJT requirements. We expect our industry partners to take advantage of this implementation delay by continuing to pursue courses and OJT to meet the requirements of the program by the revised dates.

Please do not misunderstand our implementation delays. The NCDOT fully supports the implementation of the Work Zone Qualifications and Training requirements and is committed to seeing this program come to fruition. Working together with the industry we have already made great progress and look forward to seeing our work zones become even safer for the workers and traveling public.

We will continue to work with our industry partners through our Work Zone Qualification and Training Committee meetings and address all the issues that remain in the coming year. Additional information can be found on our web site at:

<http://www.ncdot.org/doh/preconstruct/wztc/WZTCTrainingProgram/default.html>

If you have questions or want to find out how you can be involved with this committee, contact Stuart Bourne at (919) 250-4159 or sbourne@ncdot.gov

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119
WEBSITE: WWW.NCDOT.ORG

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

**STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
INVITATION TO BID**

ELECTRONIC BIDS (UNLESS OTHERWISE SPECIFIED IN THE PROJECT SPECIAL PROVISION) FOR THE CONSTRUCTION OF THE FOLLOWING PROJECTS WILL BE PUBLICLY READ IN ROOM 156-A/B, THE CONTRACT STANDARDS AND DEVELOPMENT UNIT LARGE CONFERENCE ROOM, LOCATED IN BUILDING B AT 1020 BIRCH RIDGE DRIVE, RALEIGH, N.C. AT **2:00 PM** ON JANUARY 19, 2010. NO ELECTRONIC BIDS WILL BE RECEIVED AFTER 2.00 PM.

1. THE BIDDER SHALL PURCHASE A PROPOSAL FOR EACH PROJECT FOR WHICH HE INTENDS TO SUBMIT A BID IN RESPONSE TO THIS INVITATION TO BID.

2. A BID BOND OR BID DEPOSIT IN THE AMOUNT OF 5% OF THE TOTAL AMOUNT BID WILL BE REQUIRED. THE BIDDER SHALL SUBMIT AN ELECTRONIC BID BOND WITH EACH ELECTRONIC BID SUBMITTAL UNLESS HE ELECTS TO FURNISH A BID DEPOSIT.

3. UPON RECEIPT OF AWARD LETTER, THE SUCCESSFUL BIDDER SHALL FURNISH A PROPERLY EXECUTED EXECUTION OF CONTRACT, NON-COLLUSION AFFIDAVIT AND DEBARMENT CERTIFICATION, AND EXECUTED PAYMENT AND PERFORMANCE BONDS FOR EACH CONTRACT. AFFIDAVIT FORMS AND BOND FORMS ARE AVAILABLE AS PART OF THE CONTRACT EXECUTION FORMS AT THE FOLLOWING WEBSITE
<http://www.ncdot.gov/doh/preconstruct/ps/contracts/letting/debar/debar1.html>.

ALL QUESTIONS RELATED TO PROJECTS DURING THE ADVERTISEMENT PERIOD SHALL BE ADDRESSED TO THE STATE CONTRACT OFFICER AT 919-250-4124.

THE MINIMUM WAGE FOR LABOR WILL BE SHOWN IN THE PROPOSAL FORM FOR FEDERAL AID PROJECTS.

CONTRACTOR'S LICENSE: A GENERAL CONTRACTOR'S LICENSE IS REQUIRED IN ORDER TO SUBMIT A BID ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000.00 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. FOR ADDITIONAL INFORMATION OR TO MAKE APPLICATION FOR A LICENSE, APPLY TO THE EXECUTIVE SECRETARY OF THE CONTRACTOR LICENSING BOARD, P.O. BOX 17187, RALEIGH, NC 27619, (919-571-4183).

PREQUALIFYING TO BID: ALL PROSPECTIVE BIDDERS SHALL BE PREQUALIFIED WITH THE DEPARTMENT OF TRANSPORTATION PRIOR TO SUBMITTING A BID. CONTRACTORS WHO ARE NOT PREQUALIFIED MAY OBTAIN INFORMATION AND FORMS FOR PREQUALIFYING FROM THE CONTRACTUAL SERVICES UNIT, DIVISION OF HIGHWAYS, DEPARTMENT OF TRANSPORTATION, 1509 MAIL SERVICE CENTER, RALEIGH, N. C., . ALL REQUIRED PREQUALIFICATION STATEMENTS AND DOCUMENTS SHALL BE FILED WITH THE CONTRACTUAL SERVICES UNIT AT LEAST FOUR WEEKS PRIOR TO THE DATE OF OPENING BIDS.

THE DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS INVITATION TO BID, MINORITY BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, OR NATIONAL ORIGIN IN COMPENSATION TO THIS AWARD.

PROPOSAL FORMS AT **\$25.00** EACH, PLANS (SMALL SIZE) AT **\$40.00** PER SET, PLANS (LARGE SIZE) AT **\$100.00** PER SET, AND CROSS-SECTIONS AT **\$40.00** PER SET, PLUS SALES TAX FOR N.C. RESIDENTS, MAY BE OBTAINED BY TELEPHONING (919-250-4124), FAXING (919-250-4127), OR WRITING TO: PLANS AND PROPOSALS, CONTRACT STANDARDS AND DEVELOPMENT UNIT, DEPARTMENT OF TRANSPORTATION, 1591 MAIL SERVICE CENTER, RALEIGH, N.C., 27699-1591. THESE CHARGES ARE NOT DEPOSITS AND WILL NOT BE REFUNDED. ALL ORDERS FOR PROPOSAL FORMS, PLANS AND CROSS-SECTIONS DELIVERED IN NORTH CAROLINA ARE SUBJECT TO 7.75% SALES TAX. ORDERS MAILED TO OUT OF STATE CONTRACTORS ARE NOT SUBJECT TO SALES TAX. MAKE ALL CHECKS PAYABLE TO THE "N.C. DEPARTMENT OF TRANSPORTATION".

THE RIGHT IS RESERVED TO REJECT ANY OR ALL BIDS.

**TODAY'S DATE IS DECEMBER 22, 2009.
BY ORDER OF THE DEPARTMENT OF TRANSPORTATION
(THE WORK WILL CONSIST APPROXIMATELY AS SHOWN ON THE FOLLOWING SHEETS)**

(Revised on 16Oct2009)

REVIEW OF PLANS AND PROPOSALS IN DIVISION OFFICE

IN ORDER TO FACILITATE AND ENCOURAGE THE INVOLVEMENT OF MINORITY BUSINESS ENTERPRISES IN THE HIGHWAY CONSTRUCTION PROCESS, IT IS THE POLICY OF THE DEPARTMENT OF TRANSPORTATION, DIVISION OF HIGHWAYS, THAT A SET OF PLANS AND PROPOSAL FOR EACH PROJECT TO BE LET WILL BE MAINTAINED FOR REVIEW BY ANY CONTRACTOR INTERESTED IN BIDDING UPON OR QUOTING WORK IN AN ADVERTISED PROJECT.

THE PROPOSALS AND PLANS WILL BE AVAILABLE FOR REVIEW BEGINNING TWO WEEKS PRIOR TO THE DATE OF BID OPENING IN THE DIVISION OFFICE WHICH WILL ADMINISTER THE CONTRACT. THE DEPARTMENT WILL, UPON REQUEST, MAKE AVAILABLE FROM ITS STAFF A PERSON TO EXPLAIN THE PROPOSED PROJECT AND TO ANSWER GENERAL QUESTIONS RELATING TO THE PROJECT. THE PLANS AND PROPOSALS CAN BE REVIEWED ANY TIME MONDAY THRU FRIDAY, EXCLUDING HOLIDAYS, BETWEEN THE HOURS OF 8:00 A.M. AND 4:30 P.M. IN THE DIVISION OFFICE. IN ORDER TO HAVE A MEMBER OF THE STAFF EXPLAIN THE PROJECT AND/OR ANSWER GENERAL QUESTIONS PERTAINING TO THE PROJECT, PRIOR APPOINTMENTS MUST BE MADE BY CALLING THE APPROPRIATE DIVISION OFFICE.

FOLLOWING ARE THE LOCATIONS AND TELEPHONE NUMBERS OF THE OFFICES IN WHICH THE PLANS AND PROPOSALS WILL BE MADE AVAILABLE, REFERENCE SHOULD BE MADE TO THE SHEETS CONTAINING THE INDIVIDUAL PROJECT QUANTITIES TO DETERMINE WHICH DIVISION OFFICE WILL ADMINISTER THE CONTRACT.

<u>DIV NO.</u>	<u>DIVISION ENGINEER</u>	<u>LOCATION</u>	<u>TOWN</u>	<u>TELEPHONE</u>
00001	Jerry Jennings, PE	113 AIRPORT DRIVE, SUITE 100	EDENTON	(252) 482-7977
00002	C. E. Lassiter, Jr., PE	PO BOX 1587	GREENVILLE	(252) 830-3490
00003	H. Allen Pope, PE	124 DIVISION DRIVE	WILMINGTON	(910) 251-5724
00004	Richard E Greene, Jr., PE	PO BOX 3165	WILSON	(252) 237-6164
00005	J. Wally Bowman, PE	2612 NORTH DUKE STREET	DURHAM	(919) 220-4600
00006	Gregory W Burns, PE	PO BOX 1150	FAYETTEVILLE	(910) 486-1493
00007	James M Mills, PE	PO BOX 14996	GREENSBORO	(336) 334-3192
00008	Tim Johnson, PE	PO BOX 1067	ABERDEEN	(910) 944-2344
00009	S. Pat Ivey, PE	375 SILAS CREEK PARKWAY	WINSTON-SALEM	(336) 703-6500
00010	Barry S Moose, PE	716 WEST MAIN STREET	ALBEMARLE	(704) 982-0101
00011	Michael A Pettyjohn, PE	PO BOX 250	NORTH WILKESBORO	(336) 667-9111
00012	Michael L Holder, PE	PO BOX 47	SHELBY	(704) 480-5400
00013	Jay J Swain, PE	PO BOX 3279	ASHEVILLE	(828) 251-6171
00014	Joel B Setzer, PE	253 WEBSTER ROAD	SYLVA	(828) 586-2141

===== SUMMARY OF PROPOSALS =====

Bid Letting Number L100119

RPN	Contract Id	WBS	County	Length	JobType
001	C202270	33714.3.1	CHOWAN	0.482 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
*002	C202503	45288.3.ST1	DARE, TYRRELL	2.830 MI	BRIDGE PRESERVATION.
*003	C202501	45287.3.ST1	BERTIE	1.106 MI	BRIDGE PRESERVATION.
004	C202510	2CR.10401.10	ETC GREENE, PITT	9.600 MI	WIDENING, RESURFACING, AND SHOULDER RECONSTRUCTION.
005	C202509	2CR.10401.12	ETC GREENE, LENOIR	9.000 MI	WIDENING, RESURFACING AND SHOULDER RECONSTRUCTION.
*006	C202539	36727.3.14	NEW HANOVER	0.000 MI	BRIDGE PRESERVATION.
007	C202491	41154.3.ST2	DUPLIN, PENDER	20.090 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
008	C202073	41867.3.1	NEW HANOVER	6.330 MI	GRADING, DRAINAGE, AND PAVING.
009	C202232	33353.3.1	WAKE	0.286 MI	GRADING, DRAINAGE, PAVING & STRUCTURES.
010	C202277	34365.3.ST1	ETC. WAKE, DURHAM	3.560 MI	WIDENING, GRADING, DRAINAGE, MILLING, PAVING, & STRUCTURE .
011	C202493	45158.3.ST1	DURHAM	9.600 MI	MILLING, RESURFACING & MILLED RUMBLE STRIPS.
012	C202496	45158.3.ST3	ETC. DURHAM	2.900 MI	MILLING & RESURFACING.
013	C202481	45162.3.ST1	ETC. VANCE, WARREN	24.050 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
014	C202505	45163.3.ST2	ETC. WAKE	2.650 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
015	C202538	5CR.10321.13	ETC DURHAM, WAKE	22.960 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
016	C202511	5CR.10911.9	ETC. VANCE, WARREN	30.420 MI	WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
017	C202528	5CR.10921.23	WAKE	7.110 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
018	C202518	5CR.20921.21	WAKE	21.010 MI	WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
019	C202513	5CR.20921.22	WAKE	20.900 MI	WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
020	C202066	34866.3.1	CUMBERLAND	0.791 MI	GRADING, DRAINAGE, PAVING & STRUCTURES.
021	C202088	41822.3.1	HARNETT	0.696 MI	WIDENING, GRADING, DRAINAGE, PAVING, SIGNING, AND SIGNALS.
022	C202267	33562.3.1	ORANGE	0.123 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
023	C201589	38728.3.1	ORANGE	12.120 MI	DIAMOND GRINDING AND CONCRETE PAVEMENT REPAIR.
024	C202372	34896.3.ST1	ORANGE	0.450 MI	WIDENING, GRADING, DRAINAGE, PAVING & SIGNALS.
025	C202537	7.107912	ETC. ROCKINGHAM	44.547 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
026	C202525	7CR.10011.18	ETC ALAMANCE	17.808 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
027	C202540	7CR.10681.16	ETC ORANGE	15.489 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
028	C202495	45121.3.ST2	STOKES	4.805 MI	ULTRATIN HOT MIX.
029	C202484	45164.3.ST2	FORSYTH	4.093 MI	MILLING, MILLED RUMBLE STRIPS & SHOULDER RECONSTRUCTION.
030	C202515	45309.3.ST1	FORSYTH, GUILFORD	0.000 MI	DYNAMIC MESSAGE SIGN REPLACEMENT.

===== SUMMARY OF PROPOSALS =====

Bid Letting Number L100119

RPN	Contract Id	WBS	County	Length	JobType
031	C202529	9CR.10291.7 ETC.	DAVIDSON	45.411 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
032	C202530	9CR.10301.7 ETC.	DAVIE	29.061 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
033	C202526	9CR.10341.7 ETC.	FORSYTH, DAVIDSON	19.478 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
034	C202531	9CR.10801.7 ETC.	ROWAN	30.969 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
035	C202520	9CR.10851.7 ETC.	STOKES, FORSYTH	27.125 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
036	C202519	10CR.10601.30 ET	MECKLENBURG	16.150 MI	WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
037	C202527	10CR.20041.20 ET	ANSON	4.190 MI	DITCHING, RESURFACING & SHOULDER RECONSTRUCTION.
038	C202165	32579.2.3	ASHE	0.245 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
039	C202273	33832.3.1	WILKES	0.055 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
040	C202227	33314.3.1	MADISON	0.024 MI	GRADING, PAVING, & STRUCTURE.
041	C202269	33703.3.1	BUNCOMBE	0.047 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
042	C202483	41860.3.ST1	POLK	9.190 MI	MILLING, RESURFACING, GUARDRAIL & SHOULDER RECONSTRUCTION.
043	C202393	45108.3.ST1	CHEROKEE	8.110 MI	PAVEMENT REHABILITATION, DRAINAGE & GUARDRAIL.
044	C202514	14CR.10451.4 ETC	HENDERSON, POLK	19.710 MI	MILLING, RESURFACING & SHOULDER RECONSTRUCTION.
045	C202508	14CR.10501.4 ETC	JACKSON, TRANSYLVANIA	30.810 MI	WIDENING, MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

*002 C202503 DARE & TYRRELL COUNTIES MANDATORY PRE-BID CONFERENCE ON WEDNESDAY, JANUARY 6, 2010 AT 11:00AM AT THE CHIEF ENGINEER'S CONFERENCE ROOM, 4809 BERYL ROAD, RALEIGH, NC 27606 (919) 733-4362.

*003 C202501 BERTIE COUNTY MANDATORY PRE-BID CONFERENCE ON WEDNESDAY, JANUARY 6, 2010 AT 11:00AM AT THE CHIEF ENGINEER'S CONFERENCE ROOM, 4809 BERYL ROAD, RALEIGH, NC 27606 (919) 733-4362.

*006 C202539 NEW HANOVER COUNTY MANDATORY PRE-BID CONFERENCE ON WEDNESDAY, JANUARY 6, 2010 AT 2:00PM AT THE CHIEF ENGINEER'S CONFERENCE ROOM, 4809 BERYL ROAD, RALEIGH, NC 27606 (919) 733-4362.

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID**L100119 002****CONTRACT ID : C202503 45288.3.ST1****DIV OFFICE EDENTON****LENGTH = 2.830 MI****COUNTY : DARE, TYRRELL****BRIDGE PRESERVATION.****DBE GOAL 0.0% COMPLETION DATE : JUN 30 2011****BRIDGE #7 OVER ALLIGATOR RIVER ON US-64.****STRUCTURE ITEMS**

Lump Sum	LS	MOBILIZATION (STRUCTURES)
500	LB	REINFORCING STEEL (BRIDGE)
Lump Sum	LS	GENERIC STRUCTURE ITEM CLEANING AND PAINTING EXISTING STRUCTURE
Lump Sum	LS	GENERIC STRUCTURE ITEM POLLUTION CONTROL
Lump Sum	LS	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM
153	LF	GENERIC STRUCTURE ITEM CONCRETE PILE JACKET
124	LF	GENERIC STRUCTURE ITEM H-PILE JACKETS
49	LF	GENERIC STRUCTURE ITEM REJACKETS
484.5	CF	GENERIC STRUCTURE ITEM REPAIRS TO CAPS, DIAPHRAGMS, AND UNDER DECK
14.2	CF	GENERIC STRUCTURE ITEM REPAIRS TO PRESTRESSED CONCRETE GIRDERS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 003

CONTRACT ID : C202501 45287.3.ST1

DIV OFFICE EDENTON

LENGTH = 1.106 MI

COUNTY : BERTIE

BRIDGE PRESERVATION.

DBE GOAL 0.0% COMPLETION DATE : MAY 31 2011

BRIDGE OVER ROANOKE, MIDDLE, AND CASHIE RIVERS ON NC-45.

STRUCTURE ITEMS

Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
Lump Sum	LS	MOBILIZATION (STRUCTURES)
588	SF	REINFORCED CONCRETE DECK SLAB
510	SF	GROOVING BRIDGE FLOORS
2	CY	CLASS A CONCRETE (BRIDGE)
500	LB	REINFORCING STEEL (BRIDGE)
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	EVAZOTE JOINT SEALS
Lump Sum	LS	GENERIC STRUCTURE ITEM BRIDGE JACKING
Lump Sum	LS	GENERIC STRUCTURE ITEM CLEANING AND PAINTING EXISTING STRUCTURE
Lump Sum	LS	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE
Lump Sum	LS	GENERIC STRUCTURE ITEM POLLUTION CONTROL
Lump Sum	LS	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM
357	LF	GENERIC STRUCTURE ITEM PILE ENCAPSULATION
256	CF	GENERIC STRUCTURE ITEM CONCRETE REPAIRS TO CAPS, DIAPHRAGMS AND COLUMNS
9	CF	GENERIC STRUCTURE ITEM REPAIRS TO PRESTRESSED CONCRETE GIRDERS
27,000	LB	GENERIC STRUCTURE ITEM STRUCTURAL STEEL REPAIR APPROX. LBS.
744	EA	GENERIC STRUCTURE ITEM CLEAN AND PAINT EXISTING BEARINGS

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 004

CONTRACT ID : C202510 2CR.10401.10

DIV OFFICE GREENVILLE

LENGTH = 9.600 MI

COUNTY : GREENE, PITT

WIDENING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 2.0% WBE 2.0% COMPLETION DATE : AUG 31 2010

2 SECTIONS OF US-258 AND 2 SECTIONS OF US-13.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
364	CY	BORROW EXCAVATION
500	TON	INCIDENTAL STONE BASE
18.2	SMI	SHOULDER RECONSTRUCTION
7,798	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
24,903	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
14,636	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
2,383	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
364	SY	6" CONCRETE DRIVEWAY
4	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
103,296	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
63,360	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
11	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
166,656	LF	PAINT PAVEMENT MARKING LINES (4")
19.2	ACR	SEEDING & MULCHING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 005

CONTRACT ID : C202509 2CR.10401.12

DIV OFFICE GREENVILLE

LENGTH = 9.000 MI

COUNTY : GREENE, LENOIR

WIDENING, RESURFACING AND SHOULDER RECONSTRUCTION.

MBE GOAL 2.0% WBE 2.0% COMPLETION DATE : AUG 31 2010

2 SECTIONS OF US-258.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
360	CY	BORROW EXCAVATION
500	TON	INCIDENTAL STONE BASE
18	SMI	SHOULDER RECONSTRUCTION
7,311	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
23,347	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
13,721	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
2,235	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
182	SY	6" CONCRETE DRIVEWAY
4	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
96,840	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
59,400	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
156,240	LF	PAINT PAVEMENT MARKING LINES (4")
18	ACR	SEEDING & MULCHING

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 006

CONTRACT ID : C202539 36727.3.14

DIV OFFICE WILMINGTON

LENGTH = 0.000 MI

COUNTY : NEW HANOVER

BRIDGE PRESERVATION.

DBE GOAL 0.0% COMPLETION DATE : SEP 30 2010

US-17/74/76 ACROSS THE CAPE FEAR RIVER.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
560	SF	WORK ZONE SIGNS (STATIONARY)
310	SF	WORK ZONE SIGNS (PORTABLE)
26	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
2	EA	FLASHING ARROW PANELS, TYPE C
14	EA	CHANGEABLE MESSAGE SIGN
540	EA	DRUMS
128	LF	BARRICADES (TYPE III)
112	HR	FLAGGER
2	EA	TMIA
448	HR	LAW ENFORCEMENT
100	EA	SKINNY DRUM
Lump Sum	LS	GENERIC STRUCTURE ITEM CLEANING & PAINTING EXISTING STRUCTURE
Lump Sum	LS	GENERIC STRUCTURE ITEM CONTROL HOUSE HVAC SYSTEM
Lump Sum	LS	GENERIC STRUCTURE ITEM GUIDE ROLLER REHABILITATION
Lump Sum	LS	GENERIC STRUCTURE ITEM ROADWAY LIGHTING REHABILITA- TION
Lump Sum	LS	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 007

CONTRACT ID : C202491 41154.3.ST2

DIV OFFICE WILMINGTON

LENGTH = 20.090 MI

COUNTY : DUPLIN, PENDER

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

DBE GOAL 4.0% COMPLETION DATE : NOV 18 2011

I-40 FROM MP 369.41 IN DUPLIN CO TO MP 389.50 IN PENDER CO.

ROADWAY ITEMS				
			200 SY	MATTING FOR EROSION CONTROL
			66.19 ACR	SEEDING & MULCHING
			120 LF	INDUCTIVE LOOP SAWCUT
			400 LF	LEAD-IN CABLE (***** (14-2))
Lump Sum	LS	MOBILIZATION		
17,299	CY	BORROW EXCAVATION		
3,000	TON	INCIDENTAL STONE BASE		
88.24	SMI	SHOULDER RECONSTRUCTION		
62,406	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")		
612,877	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1/2" TO 1-1/4")		
5,908	SY	INCIDENTAL MILLING		
135,804	TON	ASPHALT CONC SURFACE COURSE, TYPE S12.5C		
7,561	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22		
2,006	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22		
1,129	TON	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED		
32,223	TON	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED		
424,302	LF	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)		
1,680	TON	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S12.5C (LEVELING COURSE)		
443	TON	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)		
4,420	TON	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)		
60	TON	GENERIC PAVING ITEM WEDGING EXISTING PAVEMENT		
40	EA	ADDITIONAL GUARDRAIL POSTS		
8	EA	GUARDRAIL ANCHOR UNITS, TYPE 350		
8	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77		
800	LF	REMOVE & RESET EXISTING GUARD- RAIL		
800	LF	GENERIC GUARDRAIL ITEM REPAIR STEEL BEAM GUARDRAIL		
3	EA	FLASHING ARROW PANELS, TYPE C		
4	EA	CHANGEABLE MESSAGE SIGN		
3	EA	TMIA		
199	EA	TEMPORARY RAISED PAVEMENT MARKERS		
60	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)		
39	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)		
31	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)		
954,678	LF	PAINT PAVEMENT MARKING LINES (4")		
9,342	LF	PAINT PAVEMENT MARKING LINES (8")		
60	LF	PAINT PAVEMENT MARKING LINES (24")		
18	EA	PAINT PAVEMENT MARKING CHARAC- TER		
31	EA	PAINT PAVEMENT MARKING SYMBOL		
525,914	LF	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)		
12,142	LF	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)		
51	EA	GENERIC PAVEMENT MARKING ITEM SHOULDER MARKER FOR DRAINS 90 MILS		
5,105	EA	PERMANENT RAISED PAVEMENT MARKERS		
3,307	EA	SNOWPLOWABLE PAVEMENT MARKERS		
4,018	LF	TEMPORARY SILT FENCE		
40,18	ACR	TEMPORARY MULCHING		
1,004.5	LB	SEED FOR TEMPORARY SEEDING		

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 008

CONTRACT ID : C202073 41867.3.1

DIV OFFICE WILMINGTON

LENGTH = 6.330 MI

COUNTY : NEW HANOVER

GRADING, DRAINAGE, AND PAVING.

DBE GOAL 9.0% COMPLETION DATE : JUL 01 2012

US-421 (CAROLINA BEACH RD) FROM GEORGE ANDERSON RD TO SR-1100 (RIVER RD).

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION	4.73	ACR	SEEDING & MULCHING
2,848	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT			
3.76	SMI	GENERIC GRADING ITEM GRADING PER SHOULDER MILE			
522	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS			
23	LF	***** RC PIPE CULVERTS, CLASS IV (15")			
4,454	LF	***** RC PIPE CULVERTS, CLASS IV (18")			
96	LF	***** RC PIPE CULVERTS, CLASS IV (24")			
502	LF	PIPE REMOVAL			
161	TON	INCIDENTAL STONE BASE			
9,087	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B			
4,955	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B			
3,393	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B			
830	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22			
7.3	CY	PIPE COLLARS			
0.13	CY	PIPE PLUGS			
37	EA	MASONRY DRAINAGE STRUCTURES			
3	EA	FRAME WITH TWO GRATES, STD 840.16			
8	EA	FRAME WITH TWO GRATES, STD 840.22			
10	EA	FRAME WITH TWO GRATES, STD 840.29			
6	EA	FRAME WITH COVER, STD 840.54			
4,101.22	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)			
307	SY	GENERIC PAVING ITEM REMOVAL OF CONCRETE ISLAND			
1	EA	ADJUSTMENT OF MANHOLES			
1	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES			
5	EA	GENERIC DRAINAGE ITEM CONVERT EXIST CB TO TRAFFIC BEARING JTN BOX			
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL			
25,717	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)			
8,589	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)			
9,536	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)			
213	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)			
114	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)			
28,428	LF	REMOVAL OF PAVEMENT MARKING LINES (4")			
1,705	LF	REMOVAL OF PAVEMENT MARKING LINES (8")			
184	LF	REMOVAL OF PAVEMENT MARKING LINES (24")			
112	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS			
989	EA	PERMANENT RAISED PAVEMENT MARKERS			
807	EA	SNOWPLOWABLE PAVEMENT MARKERS			
Lump Sum	LS	PORTABLE LIGHTING			
900	LF	TEMPORARY SILT FENCE			
210	TON	STONE FOR EROSION CONTROL, CLASS A			
90	TON	STONE FOR EROSION CONTROL, CLASS B			
180	TON	SEDIMENT CONTROL STONE			
30	LF	WATTLE			

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 009

CONTRACT ID : C202232 33353.3.1

DIV OFFICE DURHAM

LENGTH = 0.286 MI

COUNTY : WAKE

GRADING, DRAINAGE, PAVING & STRUCTURES.

DBE GOAL 11.0% COMPLETION DATE : MAY 01 2011

BRIDGES OVER AUSTIN CREEK & SMITH'S CREEK AND APPROACHES ON SR-2053.

ROADWAY ITEMS				
		78	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
		144	LF	BARRICADES (TYPE III)
		30	MD	FLAGGER
Lump Sum	LS	2,333	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
Lump Sum	LS	3,669	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
		933	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
Lump Sum	LS	142	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
		6	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1	ACR	957	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
400	CY	356	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)
Lump Sum	LS	7,840	LF	PAINT PAVEMENT MARKING LINES (4")
15,900	CY	40	EA	PERMANENT RAISED PAVEMENT MARKERS
275	CY	799	LF	12" WATER LINE
400	CY	2	EA	12" VALVE
400	SY	1	EA	RELOCATE WATER METER
150	TON	1	EA	RELOCATE FIRE HYDRANT
300	SY	745	LF	ABANDON 12" UTILITY PIPE
24	LF	332	LF	24" ENCASUREMENT PIPE
20	LF	166	LF	TRENCHLESS INSTALLATION OF 24" IN SOIL
32	LF	166	LF	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL
2	EA	4,000	LF	TEMPORARY SILT FENCE
44	LF	450	TON	STONE FOR EROSION CONTROL, CLASS A
35	TON	750	TON	STONE FOR EROSION CONTROL, CLASS B
150	TON	350	TON	SEDIMENT CONTROL STONE
195	SY	6	ACR	TEMPORARY MULCHING
1,215	TON	150	LB	SEED FOR TEMPORARY SEEDING
1,180	TON	1.75	TON	FERTILIZER FOR TEMPORARY SEEDING
1,020	TON	800	LF	TEMPORARY SLOPE DRAINS
170	TON	8	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
20	TON	2,000	LF	SAFETY FENCE
23	EA	1,725	CY	SILT EXCAVATION
13	EA	8,500	SY	MATTING FOR EROSION CONTROL
19.7	LF	275	SY	COIR FIBER MAT
4	EA	900	SY	PERMANENT SOIL REINFORCEMENT MAT
5	EA	625	LF	1/4" HARDWARE CLOTH
4	EA	400	LF	WATTLE
820	LF	100	LB	POLYACRYLAMIDE (PAM)
700	SY	1,025	LF	COIR FIBER BAFFLES
2	EA	5	EA	** SKIMMER (1-1/2")
43	SY	10	ACR	SEEDING & MULCHING
4	EA	3	ACR	MOWING
3	EA	50	LB	SEED FOR REPAIR SEEDING
237.5	LF	0.25	TON	FERTILIZER FOR REPAIR SEEDING
5	EA	125	LB	SEED FOR SUPPLEMENTAL SEEDING
5	EA	3.5	TON	FERTILIZER TOPDRESSING
5	EA	10	MHR	SPECIALIZED HAND MOWING
20	TON	12	EA	RESPONSE FOR EROSION CONTROL
20	TON	0.1	ACR	REFORESTATION
1,275	SY			
1	EA			
120	LF			
7	EA			
2	EA			
17	EA			
1	EA			
436	SF			
148	SF			
		20	LF	12" RC PIPE CULVERTS, CLASS III
		716	LF	15" RC PIPE CULVERTS, CLASS III
		48	LF	18" RC PIPE CULVERTS, CLASS III

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

12	LF	24" RC PIPE CULVERTS, CLASS III
12	LF	30" RC PIPE CULVERTS, CLASS III
		*** OR ***
616	LF	15" RC PIPE CULVERTS, CLASS III
20	LF	***" HDPE PIPE CULVERTS (12")
100	LF	***" HDPE PIPE CULVERTS (15")
48	LF	***" HDPE PIPE CULVERTS (18")
12	LF	***" HDPE PIPE CULVERTS (24")
12	LF	***" HDPE PIPE CULVERTS (30")
		*** OR ***
616	LF	15" RC PIPE CULVERTS, CLASS III
20	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (12", 0.064")
100	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")
48	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")
12	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")
12	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.064")

*** END SCHEDULE AA ***

STRUCTURE ITEMS

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+55.20-L-)
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (38+12.60-L-)
80	LF	PILE EXCAVATION IN SOIL
30	LF	PILE EXCAVATION NOT IN SOIL
2,065	CY	UNCLASSIFIED STRUCTURE EXCAVATION
12,160	SF	CONCRETE WEARING SURFACE
14,653	SF	GROOVING BRIDGE FLOORS
113.1	CY	CLASS AA CONCRETE (BRIDGE)
164.6	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (17+55.20-L-)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (38+12.60-L-)
27,714	LB	REINFORCING STEEL (BRIDGE)
3,817	LB	EPOXY COATED REINFORCING STEEL (BRIDGE)
930	LF	HP12X53 STEEL PILES
322.7	LF	THREE BAR METAL RAIL
655	TON	RIP RAP CLASS II (2'-0" THICK)
730	SY	FILTER FABRIC FOR DRAINAGE
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	EVAZOTE JOINT SEALS
2,241	LF	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS
2,629.69	LF	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 010

CONTRACT ID : C202277 34365.3.ST1

DIV OFFICE DURHAM

LENGTH = 3.560 MI

COUNTY : WAKE, DURHAM

WIDENING, GRADING, DRAINAGE, MILLING, PAVING, & STRUCTURE .

DBE GOAL 10.0% COMPLETION DATE : DEC 31 2010

NORTHERN WAKE FREEWAY INTERCHANGE IMPROVEMENTS AT I-540 AND I-40, AND I-40 FROM NC-147 TO EAST OF I-540.

ROADWAY ITEMS				
			3,900	LF STEEL BM GUARDRAIL
			10	EA ADDITIONAL GUARDRAIL POSTS
			6	EA GUARDRAIL ANCHOR UNITS, TYPE CAT-1
Lump Sum	LS MOBILIZATION		6	EA GUARDRAIL ANCHOR UNITS, TYPE 350
Lump Sum	LS CONSTRUCTION SURVEYING		2	EA GUARDRAIL ANCHOR UNITS, TYPE M-350
Lump Sum	LS CLEARING & GRUBBING . ACRE(S)		2	EA GUARDRAIL ANCHOR UNITS, TYPE B-77
1	ACR SUPPLEMENTARY CLEARING & GRUBBING		3,252	LF REMOVE EXISTING GUARDRAIL
43,500	CY UNCLASSIFIED EXCAVATION		1,980	LF WOVEN WIRE FENCE, 47" FABRIC
Lump Sum	LS BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (24+61.31 -L-)		130	EA 4" TIMBER FENCE POSTS, 7'-6" LONG
2,124	CY UNDERCUT EXCAVATION		80	EA 5" TIMBER FENCE POSTS, 8'-0" LONG
5,900	TON CLASS IV SUBGRADE STABILIZATION		265	TON RIP RAP, CLASS I
370	CY DRAINAGE DITCH EXCAVATION		3	TON RIP RAP, CLASS B
340	LF BERM DITCH CONSTRUCTION		2,135	SY FILTER FABRIC FOR DRAINAGE
13,750	SY REMOVAL OF EXISTING ASPHALT PAVEMENT		4	CY REINFORCED CONCRETE SIGN FOUNDATIONS
500	CY SELECT GRANULAR MATERIAL		2	CY PLAIN CONCRETE SIGN FOUNDATIONS
9,300	SY FABRIC FOR SOIL STABILIZATION		60	CY OVERHEAD FOOTING
110	SF TEMPORARY SHORING		4,007	LB SUPPORTS, BREAKAWAY STEEL BEAM
150	TON FOUNDATION CONDITIONING MATERIAL, MINOR STRS		172	LB SUPPORTS, SIMPLE STEEL BEAM
450	SY FOUNDATION CONDITIONING FABRIC		126	LF SUPPORTS, 3-LB STEEL U-CHANNEL
12	LF 30" RC PIPE CULVERTS, CLASS III		1	EA SUPPORTS, 2-LB STEEL U-CHANNEL
56	LF 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK		45	LF SUPPORTS, WOOD
6	EA 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK		Lump Sum	LS SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (10+00 -CD-)
122	LF PIPE REMOVAL		Lump Sum	LS SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (10+00 -RP2B-)
Lump Sum	LS FINE GRADING		Lump Sum	LS SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (25+70 -L-)
500	TON STABILIZER AGGREGATE		Lump Sum	LS SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (36+00 -L-)
200	TON INCIDENTAL STONE BASE		1	EA SIGN ERECTION, TYPE D
8,600	CY SHOULDER BORROW		2	EA SIGN ERECTION, TYPE E
15,800	SY MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")		1	EA SIGN ERECTION, TYPE F
246,489	SY MILLING ASPHALT PAVEMENT, **** DEPTH (2")		9	EA SIGN ERECTION, TYPE *** (OVERHEAD) (A)
29,236	SY MILLING ASPHALT PAVEMENT, **** DEPTH (5")		5	EA SIGN ERECTION, TYPE *** (OVERHEAD) (B)
510	SY INCIDENTAL MILLING		7	EA SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)
14,700	TON ASPHALT CONC BASE COURSE, TYPE B25.0C		1	EA SIGN ERECTION, MILEMARKERS
5,200	TON ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C		1	EA SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)
5,172	TON ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D		1	EA SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (B)
12,958	TON ASPHALT CONC SURFACE COURSE, TYPE S9.5C		2	EA DISPOSAL OF SUPPORT, STEEL BEAM
24,941	TON ASPHALT CONC SURFACE COURSE, TYPE S9.5D		4	EA DISPOSAL OF SIGN SYSTEM, OVERHEAD
880	TON ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22		5	EA DISPOSAL OF SIGN SYSTEM, STEEL BEAM
1,021	TON ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22		5	EA DISPOSAL OF SIGN SYSTEM, U-CHANNEL
1,372	TON ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22		1	EA STOCKPILE SIGN SYSTEM, WOOD
400	TON ASPHALT PLANT MIX, PAVEMENT REPAIR		457	SF WORK ZONE SIGNS (STATIONARY)
81,898	LF MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)		1,349	SF WORK ZONE SIGNS (PORTABLE)
1.56	CY PIPE COLLARS		188	SF WORK ZONE SIGNS (BARRICADE MOUNTED)
17	EA MASONRY DRAINAGE STRUCTURES		8	EA FLASHING ARROW PANELS, TYPE C
8.3	LF MASONRY DRAINAGE STRUCTURES		12	EA CHANGEABLE MESSAGE SIGN
17	EA FRAME WITH TWO GRATES, STD 840.20		65	DAY CHANGEABLE MESSAGE SIGN (SHORT TERM)
3	EA FRAME WITH COVER, STD 840.54		790	EA DRUMS
30	LF 2'-6" CONCRETE CURB & GUTTER		192	LF BARRICADES (TYPE III)
2,150	LF SHOULDER BERM GUTTER		240	HR FLAGGER
50	LF PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED			
1	EA ADJUSTMENT OF DROP INLETS			
3	EA CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER			

			1,775	LF	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	
1	EA	TEMPORARY CRASH CUSHIONS				
3	EA	TMIA				
406	LF	PORTABLE CONCRETE BARRIER	1,530	LF	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	
210	LF	PORTABLE CONCRETE BARRIER (ANCHORED)	620	LF	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	
400	LF	WATER FILLED BARRIER	9	EA	ELECTRICAL JUNCTION BOXES ***** (PC18)	
2,160	HR	LAW ENFORCEMENT	3	EA	ELECTRICAL JUNCTION BOXES ***** (PC30)	
480	EA	SKINNY DRUM	1	EA	ELECTRICAL JUNCTION BOXES ***** (PC36)	
3,413	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	8	EA	UNDERPASS LUMINARIES ***** (150W HPS)	
114,302	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	Lump Sum	LS	UNDERPASS CIRCUITRY AT ***** (UPL-1, PAGE ROAD)	
41,920	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	Lump Sum	LS	PORTABLE LIGHTING	
649	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1	EA	GENERIC LIGHTING ITEM 120' HIGH MOUNT STANDARD	
745	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	5	EA	GENERIC LIGHTING ITEM 80' HIGH MOUNT STANDARD	
3,188	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1	EA	GENERIC LIGHTING ITEM LIGHT CONTROL EQUIPMENT, RW, 2 40/480V	
10,711	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	1	EA	GENERIC LIGHTING ITEM RELOCATE CONTROL SYSTEM	
402	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	18,500	LF	TEMPORARY SILT FENCE	
61	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	1,000	TON	STONE FOR EROSION CONTROL, CLASS A	
87	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2,700	TON	STONE FOR EROSION CONTROL, CLASS B	
1,454	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,350	TON	SEDIMENT CONTROL STONE	
616	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	51	ACR	TEMPORARY MULCHING	
21	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (12") (III)	950	LB	SEED FOR TEMPORARY SEEDING	
7,048	LF	PAINT PAVEMENT MARKING LINES (4")	4.75	TON	FERTILIZER FOR TEMPORARY SEED- ING	
22,401	LF	PAINT PAVEMENT MARKING LINES (6")	2,100	LF	TEMPORARY SLOPE DRAINS	
900	LF	PAINT PAVEMENT MARKING LINES (8")	12	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	
4,296	LF	PAINT PAVEMENT MARKING LINES (12")	2,000	LF	SAFETY FENCE	
192	LF	PAINT PAVEMENT MARKING LINES (24")	5,800	CY	SILT EXCAVATION	
40	EA	PAINT PAVEMENT MARKING CHARAC- TER	60,000	SY	MATTING FOR EROSION CONTROL	
121	EA	PAINT PAVEMENT MARKING SYMBOL	100	SY	COIR FIBER MAT	
6,831	LF	REMOVAL OF PAVEMENT MARKING LINES (6")	1,650	SY	PERMANENT SOIL REINFORCEMENT MAT	
900	LF	REMOVAL OF PAVEMENT MARKING LINES (12")	1,300	LF	1/4" HARDWARE CLOTH	
24	EA	PERMANENT RAISED PAVEMENT MARKERS	200	LF	WATTLE	
2,797	EA	SNOWPLOWABLE PAVEMENT MARKERS	400	LB	POLYACRYLAMIDE (PAM)	
1	EA	PORTABLE DRIVE UNIT	2,750	LF	COIR FIBER BAFFLES	
32.4	CY	HIGH MOUNT FOUNDATIONS	6	EA	*** SKIMMER (1-1/2')	
40	EA	HIGH MOUNT LUMINAIRES ***** (400W HPS)	30	ACR	SEEDING & MULCHING	
8	EA	HIGH MOUNT LUMINAIRES ***** (750W HPS)	34	ACR	MOWING	
1	EA	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	400	LB	SEED FOR REPAIR SEEDING	
100	LF	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	1.25	TON	FERTILIZER FOR REPAIR SEEDING	
50	LF	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	700	LB	SEED FOR SUPPLEMENTAL SEEDING	
150	LF	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	20.5	TON	FERTILIZER TOPDRESSING	
200	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (2")	40	MHR	SPECIALIZED HAND MOWING	
40	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	36	EA	RESPONSE FOR EROSION CONTROL	
40	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	7	ACR	REFORESTATION	
50	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	2,675	LF	INDUCTIVE LOOP SAWCUT	
265	LF	** #8 W/G FEEDER CIRCUIT (2)	200	LF	LEAD-IN CABLE (***** (14-2)	
55	LF	** #6 W/G FEEDER CIRCUIT (2)			***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****	
210	LF	** #4 W/G FEEDER CIRCUIT (2)	1,264	LF	15" RC PIPE CULVERTS, CLASS III	
			300	LF	15" RC PIPE CULVERTS, CLASS III	*** OR ***
			964	LF	*** HDPE PIPE CULVERTS (15")	*** OR ***
			300	LF	15" RC PIPE CULVERTS, CLASS III	
			964	LF	*** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	
					*** END SCHEDULE AA ***	

STRUCTURE ITEMS

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24+32.55-L-)
Lump Sum	LS	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 24+32.55-L-)
Lump Sum	LS	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 24+32.55-L-)
12	LF	PILE EXCAVATION IN SOIL
20	LF	PILE EXCAVATION NOT IN SOIL
3,697	SF	REINFORCED CONCRETE DECK SLAB
3,404	SF	GROOVING BRIDGE FLOORS
85.3	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (24+32.55-L-)
13,787	LB	REINFORCING STEEL (BRIDGE)
1,511	LB	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)
115,500	LS	APPROX LBS STRUCTURAL STEEL
150	LF	HP12X53 STEEL PILES
186.02	LF	CONCRETE BARRIER RAIL
200	SY	4" SLOPE PROTECTION
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	EVAZOTE JOINT SEALS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 011

CONTRACT ID : C202493 45158.3.ST1

DIV OFFICE DURHAM

LENGTH = 9.600 MI

COUNTY : DURHAM

MILLING, RESURFACING & MILLED RUMBLE STRIPS.

DBE GOAL 7.0% COMPLETION DATE : DEC 16 2010

1 SECTION OF I-85, 1 SECTION OF US-15/501, AND 1 SECTION OF NC-147.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
428,769	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
136,186	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (4")
20,377	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
49,869	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
11,615	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5D
958	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2,992	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
639	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22
1,700	TON	PATCHING EXISTING PAVEMENT
204,019	LF	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
311,848	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
46,379	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
5,219	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
49,235	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)
50	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
204	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
26	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
115	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
11,359	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)
600	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (12") (III)
79,573	LF	PAINT PAVEMENT MARKING LINES (4")
11,345	LF	PAINT PAVEMENT MARKING LINES (8")
50	LF	PAINT PAVEMENT MARKING LINES (16")
181	LF	PAINT PAVEMENT MARKING LINES (24")
2	EA	PAINT PAVEMENT MARKING CHARAC- TER
34	EA	PAINT PAVEMENT MARKING SYMBOL
2,250	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
9,109	LF	REMOVAL OF PAVEMENT MARKING LINES (6")
600	LF	REMOVAL OF PAVEMENT MARKING LINES (12")
391	EA	PERMANENT RAISED PAVEMENT MARKERS
3,591	EA	SNOWPLOWABLE PAVEMENT MARKERS
Lump Sum	LS	PORTABLE LIGHTING
2,026	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 012

CONTRACT ID : C202496 45158.3.ST3

DIV OFFICE DURHAM

LENGTH = 2.900 MI

COUNTY : DURHAM

MILLING & RESURFACING.

DBE GOAL 8.0% COMPLETION DATE : SEE SPECIAL PROVISIONS

3 SECTIONS OF US-15/501 BUS AND 3 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
62,054	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
11,913	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")
6,684	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
400	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1,780	TON	PATCHING EXISTING PAVEMENT
29	EA	ADJUSTMENT OF MANHOLES
2	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
29,999	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
8,549	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
150	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,781	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
28	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
169	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
630	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
29,999	LF	PAINT PAVEMENT MARKING LINES (4")
8,549	LF	PAINT PAVEMENT MARKING LINES (8")
150	LF	PAINT PAVEMENT MARKING LINES (16")
1,781	LF	PAINT PAVEMENT MARKING LINES (24")
28	EA	PAINT PAVEMENT MARKING CHARAC- TER
169	EA	PAINT PAVEMENT MARKING SYMBOL
630	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
857	EA	PERMANENT RAISED PAVEMENT MARKERS
7,884	LF	INDUCTIVE LOOP SAWCUT

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 013

CONTRACT ID : C202481 45162.3.ST1

DIV OFFICE DURHAM

LENGTH = 24.050 MI

COUNTY : VANCE, WARREN

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

DBE GOAL 7.0% COMPLETION DATE : OCT 15 2010

1 SECTION OF US-1, US-1/158 BUS, NC-39, NC-903, NC-43 AND 1 SECTION OF SECONDARY ROAD.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
926	CY	BORROW EXCAVATION
489	TON	INCIDENTAL STONE BASE
46.28	SMI	SHOULDER RECONSTRUCTION
38,620	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
1,800	SY	INCIDENTAL MILLING
7,500	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
18,317	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
3,278	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
12,166	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
2,214	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
197	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
3,250	TON	PATCHING EXISTING PAVEMENT
1	EA	ADJUSTMENT OF MANHOLES
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
246,402	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
169,310	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
180	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
260	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
12	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
55	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
17,840	LF	PAINT PAVEMENT MARKING LINES (4")
160	LF	PAINT PAVEMENT MARKING LINES (24")
1,399	EA	PERMANENT RAISED PAVEMENT MARKERS
280	EA	SNOWPLOWABLE PAVEMENT MARKERS
35.71	ACR	SEEDING & MULCHING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 014

CONTRACT ID : C202505 45163.3.ST2

DIV OFFICE DURHAM

LENGTH = 2.650 MI

COUNTY : WAKE

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

DBE GOAL 7.0% COMPLETION DATE : SEE SPECIAL PROVISIONS

3 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
27	CY	BORROW EXCAVATION
1.34	SMI	SHOULDER RECONSTRUCTION
22,648	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
11,788	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")
9,316	SY	INCIDENTAL MILLING
1,760	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
6,218	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
457	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
450	TON	PATCHING EXISTING PAVEMENT
6	EA	ADJUSTMENT OF MANHOLES
15	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
32,171	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
34,974	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
141	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
38	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
88	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
36,612	LF	PAINT PAVEMENT MARKING LINES (4")
75	LF	PAINT PAVEMENT MARKING LINES (24")
377	EA	PERMANENT RAISED PAVEMENT MARKERS
0.98	ACR	SEEDING & MULCHING
1,392	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 015

CONTRACT ID : C202538 5CR.10321.13

DIV OFFICE DURHAM

LENGTH = 22.960 MI

COUNTY : DURHAM, WAKE

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : DEC 16 2010

1 SECTION OF US-70, 1 SECTION OF NC-55, 1 SECTION OF NC-751 & 13 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
780	CY	BORROW EXCAVATION
731	TON	INCIDENTAL STONE BASE
39.07	SMI	SHOULDER RECONSTRUCTION
72,520	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
24,922	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 2-1/2")
3,753	SY	INCIDENTAL MILLING
1,991	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
447	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
28,868	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
3,344	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1,837	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
201	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
20,140	TON	PATCHING EXISTING PAVEMENT
45	EA	ADJUSTMENT OF MANHOLES
20	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
220,634	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
197,844	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
26	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
1,390	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)
450	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,183	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
60	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
163	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1,000	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
62,947	LF	PAINT PAVEMENT MARKING LINES (4")
740	LF	PAINT PAVEMENT MARKING LINES (8")
350	LF	PAINT PAVEMENT MARKING LINES (16")
651	LF	PAINT PAVEMENT MARKING LINES (24")
8	EA	PAINT PAVEMENT MARKING CHARAC- TER
45	EA	PAINT PAVEMENT MARKING SYMBOL
1,877	EA	PERMANENT RAISED PAVEMENT MARKERS
25	ACR	SEEDING & MULCHING
22,500	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 016

CONTRACT ID : C202511 5CR.10911.9

DIV OFFICE DURHAM

LENGTH = 30.420 MI

COUNTY : VANCE, WARREN

WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : SEP 03 2010

1 SECTION OF US-1 BUS, US-158 BUS, NC-39, AND 7 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
991	CY	BORROW EXCAVATION
635	TON	INCIDENTAL STONE BASE
49.52	SMI	SHOULDER RECONSTRUCTION
62,452	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
10,500	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
2,739	SY	INCIDENTAL MILLING
640	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
12,368	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
19,729	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
2,051	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2,860	TON	PATCHING EXISTING PAVEMENT
3	EA	CONCRETE WHEELCHAIR RAMPS
1	EA	ADJUSTMENT OF DROP INLETS
27	EA	ADJUSTMENT OF MANHOLES
35	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
272,748	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
241,716	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
670	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
250	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,193	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
10	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
135	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
94,244	LF	PAINT PAVEMENT MARKING LINES (4")
50	LF	PAINT PAVEMENT MARKING LINES (24")
1,896	EA	PERMANENT RAISED PAVEMENT MARKERS
29.5	ACR	SEEDING & MULCHING
5,670	LF	INDUCTIVE LOOP SAWCUT
800	LF	LEAD-IN CABLE (***** (14-2)

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 017

CONTRACT ID : C202528

5CR.10921.23

DIV OFFICE DURHAM

LENGTH = 7.110 MI

COUNTY : WAKE

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 3.0% WBE 4.0% COMPLETION DATE : SEE SPECIAL PROVISIONS

US-64 FROM JT NEAR ASHVILLE AVE TO GREEN LEVEL RD PROJECT POINT, AND NC-55 FROM S OF PERRY RD TO JT N OF HUNTER ST.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
165	CY	BORROW EXCAVATION
384	TON	INCIDENTAL STONE BASE
8.25	SMI	SHOULDER RECONSTRUCTION
285,518	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
37,754	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (4")
5,527	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
36,594	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
259	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2,195	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
561	TON	PATCHING EXISTING PAVEMENT
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
156,374	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
47,844	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
7,055	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
1,400	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
136	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
337	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1,559	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
204,218	LF	PAINT PAVEMENT MARKING LINES (4")
7,055	LF	PAINT PAVEMENT MARKING LINES (8")
1,400	LF	PAINT PAVEMENT MARKING LINES (24")
130	EA	PAINT PAVEMENT MARKING CHARAC- TER
337	EA	PAINT PAVEMENT MARKING SYMBOL
373	EA	PERMANENT RAISED PAVEMENT MARKERS
2,158	EA	SNOWPLOWABLE PAVEMENT MARKERS
5.57	ACR	SEEDING & MULCHING
9,270	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 018

CONTRACT ID : C202518

5CR.20921.21

DIV OFFICE DURHAM

LENGTH = 21.010 MI

COUNTY : WAKE

WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 3.0% WBE 4.0% COMPLETION DATE : DEC 16 2010

8 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
473	CY	BORROW EXCAVATION
704	TON	INCIDENTAL STONE BASE
23.61	SMI	SHOULDER RECONSTRUCTION
175,733	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
44,691	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")
4,734	SY	INCIDENTAL MILLING
7,821	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
36,528	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
2,528	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
8,544	TON	PATCHING EXISTING PAVEMENT
20	EA	ADJUSTMENT OF MANHOLES
42	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
128,353	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
212,528	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
2,585	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
1,417	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
32	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
251	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1,640	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
76,566	LF	PAINT PAVEMENT MARKING LINES (4")
1,685	LF	PAINT PAVEMENT MARKING LINES (8")
892	LF	PAINT PAVEMENT MARKING LINES (24")
191	EA	PAINT PAVEMENT MARKING SYMBOL
1,640	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
2,889	EA	PERMANENT RAISED PAVEMENT MARKERS
17.2	ACR	SEEDING & MULCHING
8,294	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 019

CONTRACT ID : C202513 5CR.20921.22

DIV OFFICE DURHAM

LENGTH = 20.900 MI

COUNTY : WAKE

WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 3.0% WBE 4.0% COMPLETION DATE : DEC 16 2010

10 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
522	CY	MOBILIZATION
665	TON	BORROW EXCAVATION
26.1	SMI	INCIDENTAL STONE BASE
146,884	SY	SHOULDER RECONSTRUCTION
16,916	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
778	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2")
118,691	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
3,381	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")
651	TON	INCIDENTAL MILLING
2,500	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
40,739	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
2,588	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
9,264	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
6	EA	PATCHING EXISTING PAVEMENT
38	EA	CONCRETE WHEELCHAIR RAMPS
42	EA	ADJUSTMENT OF MANHOLES
141,536	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
232,077	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
5,070	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
4,070	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
80	EA	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
544	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
2,015	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
117,759	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)
4,810	LF	PAINT PAVEMENT MARKING LINES (4")
150	LF	PAINT PAVEMENT MARKING LINES (8")
3,978	LF	PAINT PAVEMENT MARKING LINES (16")
64	EA	PAINT PAVEMENT MARKING LINES (24")
481	EA	PAINT PAVEMENT MARKING CHARAC- TER
2,015	EA	PAINT PAVEMENT MARKING SYMBOL
3,232	EA	REMOVAL OF PAVEMENT MARKING LINES (4")
19.1	EA	PERMANENT RAISED PAVEMENT MARKERS
20,178	ACR	SEEDING & MULCHING
	LF	INDUCTIVE LOOP SAWCUT

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 020

CONTRACT ID : C202066 34866.3.1

DIV OFFICE FAYETTEVILLE

LENGTH = 0.791 MI

COUNTY : CUMBERLAND

GRADING, DRAINAGE, PAVING & STRUCTURES.

DBE GOAL 13.0% COMPLETION DATE : JUN 15 2012

SR-1003 (CAMDEN RD) FROM NC-59 TO HOPE MILLS BYPASS.

ROADWAY ITEMS					
			35	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
			2	EA	FRAME WITH COVER, STD 840.54
Lump Sum	LS	MOBILIZATION	7	EA	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN
Lump Sum	LS	CONSTRUCTION SURVEYING			
Lump Sum	LS	CLEARING & GRUBBING .. ACRE(S)	4	EA	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS
	1	ACR			SUPPLEMENTARY CLEARING & GRUBBING
	3,000	CY	5,710	LF	1'-6" CONCRETE CURB & GUTTER
Lump Sum	LS	UNCLASSIFIED EXCAVATION	7,625	LF	2'-6" CONCRETE CURB & GUTTER
		REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+70.00)	680	SY	4" CONCRETE SIDEWALK
Lump Sum	LS	REINFORCED BRIDGE APPROACH FILL, STATION ***** (39+85.50)	2	EA	CONCRETE WHEELCHAIR RAMPS
			131	SY	6" CONCRETE DRIVEWAY
Lump Sum	LS	UNDERCUT EXCAVATION	70	SY	4" CONCRETE ISLAND COVERS
	500	CY	680	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)
	300	TON	2,050	LF	STEEL BM GUARDRAIL
		CLASS IV SUBGRADE STABILIZATION	2	EA	STEEL BM GUARDRAIL TERMINAL SECTIONS
71,200	CY	BORROW EXCAVATION	10	EA	ADDITIONAL GUARDRAIL POSTS
575	CY	DRAINAGE DITCH EXCAVATION	2	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
6,220	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	7	EA	GUARDRAIL ANCHOR UNITS, TYPE III
4,100	SY	BREAKING OF EXISTING ASPHALT PAVEMENT	13	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
	500	CY			SELECT GRANULAR MATERIAL
	800	SY			FABRIC FOR SOIL STABILIZATION
8,752	SF	TEMPORARY SHORING	315	LF	CHAIN LINK FENCE, 48" FABRIC
2,225	SY	FOUNDATION CONDITIONING FABRIC	26	EA	METAL LINE POSTS FOR 48" CHAIN LINK FENCE
770	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	2	EA	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE
	388	LF	141	TON	RIP RAP, CLASS I
		*** DRAINAGE PIPE (66")	350	TON	RIP RAP, CLASS II
4,360	LF	15" DRAINAGE PIPE	110	TON	RIP RAP, CLASS B
944	LF	18" DRAINAGE PIPE	1,850	SY	FILTER FABRIC FOR DRAINAGE
480	LF	24" DRAINAGE PIPE	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
256	LF	30" DRAINAGE PIPE	670	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
84	LF	42" DRAINAGE PIPE	1	EA	SIGN ERECTION, TYPE D
136	LF	GENERIC PIPE ITEM 48" CS PIPE CULVERTS, 0.109" THICK	33	EA	SIGN ERECTION, TYPE E
			3	EA	SIGN ERECTION, TYPE F
349	LF	PIPE REMOVAL	32	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
Lump Sum	LS	FINE GRADING	3	EA	DISPOSAL OF SIGN SYSTEM, WOOD
	1,000	TON	302	SF	WORK ZONE SIGNS (STATIONARY)
	315	SY	196	SF	WORK ZONE SIGNS (PORTABLE)
		MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" TO 3")	208	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
6,220	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	2	EA	FLASHING ARROW PANELS, TYPE C
3,500	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2	EA	CHANGEABLE MESSAGE SIGN
4,945	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	220	EA	DRUMS
			100	EA	CONES
730	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	200	LF	BARRICADES (TYPE III)
45	CY	SUBDRAIN EXCAVATION	3,440	HR	FLAGGER
34	CY	SUBDRAIN FINE AGGREGATE	10	EA	TEMPORARY CRASH CUSHIONS
200	LF	6" PERFORATED SUBDRAIN PIPE	2	EA	TMIA
6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	1,143	LF	PORTABLE CONCRETE BARRIER
			1,126	LF	PORTABLE CONCRETE BARRIER (DRAINAGE)
1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	720	HR	LAW ENFORCEMENT
6	LF	6" OUTLET PIPE (SUBDRAINS)	21	EA	TUBULAR MARKERS (FIXED)
11	CY	ENDWALLS	739	EA	TEMPORARY RAISED PAVEMENT MARKERS
38	CY	REINFORCED ENDWALLS	1,345	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
1	CY	PIPE COLLARS	4,502	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
84	EA	MASONRY DRAINAGE STRUCTURES	38	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
24	CY	MASONRY DRAINAGE STRUCTURES	53	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
17	LF	MASONRY DRAINAGE STRUCTURES	67	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
6	EA	FRAME WITH TWO GRATES, STD 840.16	27	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
12	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	37,240	LF	PAINT PAVEMENT MARKING LINES (4")
32	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1,550	LF	PAINT PAVEMENT MARKING LINES (8")

183	LF	PAINT PAVEMENT MARKING LINES (24")	13,831	LB	REINFORCING STEEL (CULVERT)
20	EA	PAINT PAVEMENT MARKING SYMBOL			
856	LF	REMOVAL OF PAVEMENT MARKING LINES (4")			
330	LF	REMOVAL OF PAVEMENT MARKING LINES (8")			
1,435	EA	PERMANENT RAISED PAVEMENT MARKERS	1,320	SF	SOLDIER PILE RETAINING WALLS
12	LF	6" WATER LINE			
127	LF	8" WATER LINE			
2,682	LF	12" WATER LINE			
1	EA	8" VALVE			
4	EA	12" VALVE			
1	EA	6" TAPPING VALVE	Lump Sum	LS	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+70.00-L-)
1	EA	4" DCV BACK-FLOW PREVENTOR			
2	EA	FIRE HYDRANT			
403	LF	12" SANITARY GRAVITY SEWER	Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+70.00-L-)
3	EA	4" DIA UTILITY MANHOLE			
13	LF	UTILITY MANHOLE WALL, *** DIA (4')	Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (39+85.50-L-)
405	LF	ABANDON 12" UTILITY PIPE			
1	EA	ABANDON UTILITY MANHOLE			
1,100	LF	TRENCHLESS INSTALLATION OF 14" IN SOIL	1	EA	PDA TESTING
			2	EA	PDA ASSISTANCE
1	EA	GENERIC UTILITY ITEM WATER METER ASSEMBLY	3,185	CY	UNCLASSIFIED STRUCTURE EXCAVATION
325	LF	GENERIC UTILITY ITEM 12" RESTRAINED JOINT DUCTILE IRON WATER LINE	30,422	SF	REINFORCED CONCRETE DECK SLAB
			27,518	SF	GROOVING BRIDGE FLOORS
80	LF	GENERIC UTILITY ITEM 12" RIGID RESTRAINED JOINT DUCTILE IRON SEWER	318.2	CY	CLASS A CONCRETE (BRIDGE)
			Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (27+70.00-L-)
70	LF	GENERIC UTILITY ITEM 4" RESTRAINED JOINT DUCTILE IRON WATER LINE	Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (39+85.50-L-)
40	LF	GENERIC UTILITY ITEM 6" RESTRAINED JOINT DUCTILE IRON WATER LINE	48,706	LB	REINFORCING STEEL (BRIDGE)
40	LF	GENERIC UTILITY ITEM 8" RESTRAINED JOINT DUCTILE IRON WATER LINE	4,582.33	LF	36" PRESTRESSED CONCRETE GIR- DERS
			2,645	LF	HP12X53 STEEL PILES
			1,150	LF	HP12X53 GALVANIZED STEEL PILES
13,000	LF	TEMPORARY SILT FENCE	2,025	LF	HP14X73 GALVANIZED STEEL PILES
430	TON	STONE FOR EROSION CONTROL, CLASS A	45	EA	PILE REDRIVES
1,320	TON	STONE FOR EROSION CONTROL, CLASS B	635.29	LF	THREE BAR METAL RAIL
1,120	TON	SEDIMENT CONTROL STONE	1,990	TON	RIP RAP CLASS II (2'-0" THICK)
15	ACR	TEMPORARY MULCHING	2,215	SY	FILTER FABRIC FOR DRAINAGE
450	LB	SEED FOR TEMPORARY SEEDING	Lump Sum	LS	ELASTOMERIC BEARINGS
2.5	TON	FERTILIZER FOR TEMPORARY SEED- ING	Lump Sum	LS	EVAZOTE JOINT SEALS
1,050	LF	TEMPORARY SLOPE DRAINS			
10	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS			
5,000	LF	SAFETY FENCE			
2,250	CY	SILT EXCAVATION			
9,800	SY	MATting FOR EROSION CONTROL			
120	SY	COIR FIBER MAT			
2,900	LF	1/4" HARDWARE CLOTH			
360	LF	*** TEMPORARY PIPE (24")			
50	CY	STILLING BASINS			
3,900	LF	COIR FIBER BAFFLES			
13	EA	*** SKIMMER (1-1/2")			
18	ACR	SEEDING & MULCHING			
9	ACR	MOWING			
150	LB	SEED FOR REPAIR SEEDING			
0.5	TON	FERTILIZER FOR REPAIR SEEDING			
350	LB	SEED FOR SUPPLEMENTAL SEEDING			
10.5	TON	FERTILIZER TOPDRESSING			
135	LF	IMPERVIOUS DIKE			
30	MHR	SPECIALIZED HAND MOWING			
12	EA	RESPONSE FOR EROSION CONTROL			
0.5	ACR	REFORESTATION			
14,200	CY	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN			

WALL ITEMS

STRUCTURE ITEMS

CULVERT ITEMS

Lump Sum	LS	CULVERT EXCAVATION, STA ***** (45+86.00-L-)
66	TON	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT
120	CY	CLASS A CONCRETE (CULVERT)

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 021

CONTRACT ID : C202088 41822.3.1

DIV OFFICE FAYETTEVILLE

LENGTH = 0.696 MI

COUNTY : HARNETT

WIDENING, GRADING, DRAINAGE, PAVING, SIGNING, AND SIGNALS.

DBE GOAL 9.0% COMPLETION DATE : NOV 01 2010

NC-55 AT THE I-95 AND US-421 INTERCHANGE.

ROADWAY ITEMS				
		1	EA	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)
		20	EA	DISPOSAL OF SUPPORT, U-CHANNEL
Lump Sum	LS	15	EA	DISPOSAL OF SIGN, D, E OR F
Lump Sum	LS	18	EA	GENERIC SIGNING ITEM
Lump Sum	LS			WARNING FLAGS
1	ACR	56	SF	WORK ZONE SIGNS (STATIONARY)
		12	SF	WORK ZONE SIGNS (PORTABLE)
100	CY	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
363	SY			UNDERCUT EXCAVATION
290	TON	30	EA	DRUMS
		64	LF	BARRICADES (TYPE III)
		12	MD	FLAGGER
304	LF	16	HR	LAW ENFORCEMENT
398	LF	9,300	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
		9,650	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
536	LF	200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
		55	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
924	LF	20	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
496	LF	310	EA	PERMANENT RAISED PAVEMENT MARKERS
309	LF	131	LF	2" WATER LINE
130	TON	331	LF	8" WATER LINE
50	TON	60	LF	12" WATER LINE
540	SY	1	EA	2" BLOW OFF
		2	EA	RELOCATE WATER METER
5,225	TON	4,200	LF	TEMPORARY SILT FENCE
		60	TON	STONE FOR EROSION CONTROL, CLASS A
2,400	TON	110	TON	STONE FOR EROSION CONTROL, CLASS B
3,675	TON	180	TON	SEDIMENT CONTROL STONE
340	TON	7	ACR	TEMPORARY MULCHING
		200	LB	SEED FOR TEMPORARY SEEDING
225	TON	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
100	TON	550	CY	SILT EXCAVATION
		2,300	SY	MATTING FOR EROSION CONTROL
1	CY	14	SY	PERMANENT SOIL REINFORCEMENT MAT
15	EA	720	LF	1/4" HARDWARE CLOTH
11	LF	80	LF	COIR FIBER BAFFLES
4	EA	4	ACR	SEEDING & MULCHING
		2	ACR	MOWING
5	EA	150	LB	SEED FOR REPAIR SEEDING
		0.5	TON	FERTILIZER FOR REPAIR SEEDING
6	EA	250	LB	SEED FOR SUPPLEMENTAL SEEDING
		6	TON	FERTILIZER TOPDRESSING
6	EA	3	MHR	SPECIALIZED HAND MOWING
		20	EA	RESPONSE FOR EROSION CONTROL
3	EA	970	LF	SIGNAL CABLE
		5	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
2,400	LF	5	EA	VEHICLE SIGNAL HEAD (12", 4 SECTION)
20	LF	2	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
700	SY	380	LF	MESSENGER CABLE (3/8")
		690	LF	UNPAVED TRENCHING (***** (1, 2"))
420	LF	6	EA	JUNCTION BOX (STANDARD SIZE)
		1	EA	1" RISER WITH WEATHERHEAD
30	EA	1	EA	2" RISER WITH HEAT SHRINK TUBING
		1,060	LF	INDUCTIVE LOOP SAWCUT
20	EA	1,810	LF	LEAD-IN CABLE (***** (14-2))
		2	EA	900MHZ WIRELESS RADIO SYSTEM
100	LF	4	EA	METAL STRAIN SIGNAL POLE
		4	EA	SOIL TEST
5	EA	24	CY	DRILLED PIER FOUNDATION
		3	EA	SIGN FOR SIGNALS
14	EA			SIGN ERECTION, TYPE F

- 1 EA SIGNAL CABINET FOUNDATION
- 1 EA CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
- 7 EA DETECTOR CARD (TYPE 2070L)
- 1 EA CABINET BASE EXTENDER
- 1 EA GENERIC SIGNAL ITEM
AUXILIARY OUTPUT FILE
- 2 EA GENERIC SIGNAL ITEM
FURNISH WIRELESS LIGHTNING
ARRESTORS
- 1 EA GENERIC SIGNAL ITEM
FURNISH WIRELESS RADIO MODEMS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 022

CONTRACT ID : C202267 33562.3.1

DIV OFFICE GREENSBORO

LENGTH = 0.123 MI

COUNTY : ORANGE

GRADING, DRAINAGE, PAVING, AND STRUCTURE.

DBE GOAL 8.0% COMPLETION DATE : DEC 31 2010

BRIDGE OVER STROUD'S CREEK AND APPROACHES ON SR-1002.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
1,800	CY	UNCLASSIFIED EXCAVATION
Lump Sum	LS	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+55.00-L-)
600	CY	UNDERCUT EXCAVATION
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
Lump Sum	LS	GRADING
48	CY	DRAINAGE DITCH EXCAVATION
600	CY	SELECT GRANULAR MATERIAL
600	SY	FABRIC FOR SOIL STABILIZATION
50	SY	FOUNDATION CONDITIONING FABRIC
16	TON	GENERIC DRAINAGE ITEM FOUNDATION COND MATERIAL MINOR STRS
104	LF	15" DRAINAGE PIPE
40	LF	24" DRAINAGE PIPE
80	LF	PIPE REMOVAL
142	TON	AGGREGATE BASE COURSE
150	TON	INCIDENTAL STONE BASE
230	SY	INCIDENTAL MILLING
350	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
170	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
270	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
40	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2	EA	MASONRY DRAINAGE STRUCTURES
2	EA	FRAME WITH TWO GRATES, STD 840.29
40	LF	SHOULDER BERM GUTTER
350	LF	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED STEEL BEAM GUARDRAIL
5	EA	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ADDITIONAL GUARDRAIL POSTS
4	EA	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNIT, TYPE 350
4	EA	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNIT, TYPE III
233	TON	RIP RAP, CLASS I
20	TON	RIP RAP, CLASS II
155	TON	RIP RAP, CLASS B
1,290	SY	FILTER FABRIC FOR DRAINAGE
1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
38	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
3	EA	SIGN ERECTION, TYPE E
9	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
491	SF	WORK ZONE SIGNS (STATIONARY)
139	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
20	EA	DRUMS
160	LF	BARRICADES (TYPE III)
5,200	LF	PAINT PAVEMENT MARKING LINES (4")
24	EA	PERMANENT RAISED PAVEMENT MARKERS
700	LF	TEMPORARY SILT FENCE
230	TON	STONE FOR EROSION CONTROL, CLASS A
180	TON	STONE FOR EROSION CONTROL, CLASS B
150	TON	SEDIMENT CONTROL STONE
1.5	ACR	TEMPORARY MULCHING
100	LB	SEED FOR TEMPORARY SEEDING
1.25	TON	FERTILIZER FOR TEMPORARY SEEDING
200	LF	TEMPORARY SLOPE DRAINS

4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
850	LF	SAFETY FENCE
550	CY	SILT EXCAVATION
8,500	SY	MATTING FOR EROSION CONTROL
50	SY	COIR FIBER MAT
150	SY	PERMANENT SOIL REINFORCEMENT MAT
560	LF	1/4" HARDWARE CLOTH
40	LF	WATTLE
10	LB	POLYACRYLAMIDE (PAM)
380	LF	COIR FIBER BAFFLES
4	EA	*** SKIMMER (1-1/2")
5	ACR	SEEDING & MULCHING
1	ACR	MOWING
50	LB	SEED FOR REPAIR SEEDING
0.25	TON	FERTILIZER FOR REPAIR SEEDING
50	LB	SEED FOR SUPPLEMENTAL SEEDING
0.75	TON	FERTILIZER TOPDRESSING
10	MHR	SPECIALIZED HAND MOWING
12	EA	RESPONSE FOR EROSION CONTROL
0.25	ACR	REFORESTATION

STRUCTURE ITEMS

Lump Sum	LS	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+55.00-L-)
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+55.00-L-)
Lump Sum	LS	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,18+55.00-L-)
575	CY	UNCLASSIFIED STRUCTURE EXCAVATION
3,533	SF	CONCRETE WEARING SURFACE
4,829	SF	GROOVING BRIDGE FLOORS
68.5	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (18+55.00-L-)
11,221	LB	REINFORCING STEEL (BRIDGE)
595	LB	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)
140	LF	HP12X53 STEEL PILES
14	EA	STEEL PILE POINTS
179,519	LF	TWO BAR METAL RAIL
195,431	LF	1'-***X ***** CONCRETE PARAPET (1'-2"X2'-9 13/16")
475	TON	RIP RAP CLASS II (2'-0" THICK)
525	SY	FILTER FABRIC FOR DRAINAGE
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	EVAZOTE JOINT SEALS
1,268,583	LF	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 023

CONTRACT ID : C201589 38728.3.1

DIV OFFICE GREENSBORO

LENGTH = 12.120 MI

COUNTY : ORANGE

DIAMOND GRINDING AND CONCRETE PAVEMENT REPAIR.

DBE GOAL 3.0% COMPLETION DATE : SEP 01 2010

I-40 FROM I-40/I-85 SPLIT TO THE DURHAM COUNTY LINE.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
393,000	SY	GENERIC MISCELLANEOUS ITEM DIAMOND GRINDING PCC PAVEMENT
140	CY	UNDERCUT EXCAVATION
132	TON	CLASS IV SUBGRADE STABILIZA- TION
85	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
4	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1,310	SF	PATCHING CONCRETE PAVEMENT SPALLS
825	SY	GENERIC PAVING ITEM GEOTEXTILE FOR PAVEMENT STABI- LIZATION
290	SY	GENERIC PAVING ITEM REPAIR OF JOINTED CONCRETE PAVEMENT SLAB
677,000	LF	GENERIC PAVING ITEM JOINT CONSTRUCTION, REPAIR & SEALING
248,600	LF	GENERIC PAVING ITEM MILLED RUMBLE STRIPS IN EXIST- ING PCC SHOULDERS
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
300,000	LF	PAINT PAVEMENT MARKING LINES (4")
300,000	LF	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)
22,000	LF	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)
3,000	EA	SNOWPLOWABLE PAVEMENT MARKERS
Lump Sum	LS	PORTABLE LIGHTING

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 024

CONTRACT ID : C202372 34896.3.ST1

DIV OFFICE GREENSBORO

LENGTH = 0.450 MI

COUNTY : ORANGE

WIDENING, GRADING, DRAINAGE, PAVING & SIGNALS.

DBE GOAL 10.0% COMPLETION DATE : SEP 15 2010

SR-1107 (OLD FAYETTEVILLE RD) FROM NC-54 TO MCDOUGLE MIDDLE SCHOOL IN CARRBORO.

ROADWAY ITEMS					
			209	EA	DRUMS
			20	EA	CONES
			80	MD	FLAGGER
			2	EA	TMIA
Lump Sum	LS	MOBILIZATION	56	HR	LAW ENFORCEMENT
Lump Sum	LS	CONSTRUCTION SURVEYING	10	EA	SKINNY DRUM
1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	5,960	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
Lump Sum	LS	GRADING	7,824	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
6,000	CY	BORROW EXCAVATION	1,141	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
1.5	HR	PROOF ROLLING	180	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
283	SY	FOUNDATION CONDITIONING FABRIC	559	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
230	TON	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS	6	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
200	LF	12" DRAINAGE PIPE	48	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1,124	LF	15" DRAINAGE PIPE	28,465	LF	PAINT PAVEMENT MARKING LINES (4")
152	LF	18" DRAINAGE PIPE	1,488	LF	PAINT PAVEMENT MARKING LINES (8")
332	LF	24" DRAINAGE PIPE	1,040	LF	PAINT PAVEMENT MARKING LINES (24")
32	LF	30" DRAINAGE PIPE	12	EA	PAINT PAVEMENT MARKING CHARACTER
32	LF	36" DRAINAGE PIPE	150	EA	PAINT PAVEMENT MARKING SYMBOL
132	LF	GENERIC PIPE ITEM 12" SIDE DRAIN PIPE	460	LF	REMOVAL OF PAVEMENT MARKING LINES (8")
112	LF	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	145	EA	PERMANENT RAISED PAVEMENT MARKERS
884	LF	PIPE REMOVAL	104	LF	16" WATER LINE
250	TON	INCIDENTAL STONE BASE	3	EA	RELOCATE WATER METER
600	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	3	EA	RECONNECT WATER METER
1,760	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	1	EA	RELOCATE FIRE HYDRANT
1,400	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	48	LF	4" SANITARY GRAVITY SEWER
2,100	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1	EA	SANITARY SEWER CLEAN-OUT
270	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	94	LF	ABANDON 16" UTILITY PIPE
80	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	1	EA	REMOVE UTILITY MANHOLE
39	EA	MASONRY DRAINAGE STRUCTURES	2,250	LF	TEMPORARY SILT FENCE
7.3	LF	MASONRY DRAINAGE STRUCTURES	250	TON	STONE FOR EROSION CONTROL, CLASS A
16	EA	FRAME WITH TWO GRATES, STD 840.16	250	TON	STONE FOR EROSION CONTROL, CLASS B
1	EA	FRAME WITH TWO GRATES, STD 840.24	500	TON	SEDIMENT CONTROL STONE
1	EA	FRAME WITH TWO GRATES, STD 840.29	4.5	ACR	TEMPORARY MULCHING
2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	100	LB	SEED FOR TEMPORARY SEEDING
10	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
10	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	450	CY	SILT EXCAVATION
760	LF	1'-6" CONCRETE CURB & GUTTER	7,500	SY	MATTING FOR EROSION CONTROL
4,570	LF	2'-6" CONCRETE CURB & GUTTER	1,575	LF	1/4" HARDWARE CLOTH
100	LF	CONCRETE EXPRESSWAY GUTTER	50	LF	COIR FIBER BAFFLES
1,520	SY	4" CONCRETE SIDEWALK	5	ACR	SEEDING & MULCHING
10	EA	CONCRETE WHEELCHAIR RAMPS	2	ACR	MOWING
300	SY	6" CONCRETE DRIVEWAY	50	LB	SEED FOR REPAIR SEEDING
20	SY	4" CONCRETE PAVED DITCH	0.25	TON	FERTILIZER FOR REPAIR SEEDING
90	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	100	LB	SEED FOR SUPPLEMENTAL SEEDING
1	EA	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2.5	TON	FERTILIZER TOPDRESSING
1	EA	CONVERT EXISTING DROP INLET TO CATCH BASIN	5	MHR	SPECIALIZED HAND MOWING
20	TON	RIP RAP, CLASS 1	12	EA	RESPONSE FOR EROSION CONTROL
290	SY	FILTER FABRIC FOR DRAINAGE	2	EA	PEDESTRIAN SIGNAL HEAD (**, ** SECTION) (16", 1 SECTION W/COUNTDOWN)
572	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	1,760	LF	SIGNAL CABLE
48	EA	SIGN ERECTION, TYPE E	9	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
23	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2	EA	AUDIBLE PEDESTRIAN SIGNAL
152	SF	WORK ZONE SIGNS (STATIONARY)	725	LF	MESSENGER CABLE (3/8")
224	SF	WORK ZONE SIGNS (PORTABLE)	20	LF	PAVED TRENCHING (***** (1, 2")
2	EA	FLASHING ARROW PANELS, TYPE C	750	LF	UNPAVED TRENCHING (***** (1, 2")
2	EA	CHANGEABLE MESSAGE SIGN	110	LF	DIRECTIONAL DRILL (***** (1, 2")
			9	EA	JUNCTION BOX (STANDARD SIZE)
			6	EA	WOOD POLE

8	EA	GUY ASSEMBLY
1	EA	1/2" RISER WITH WEATHERHEAD
1	EA	1" RISER WITH WEATHERHEAD
7	EA	2" RISER WITH WEATHERHEAD
1,050	LF	INDUCTIVE LOOP SAWCUT
5,015	LF	LEAD-IN CABLE (*****) (14-2)
2	EA	SIGNAL PEDESTAL WITH FOUNDATION
3	EA	SIGN FOR SIGNALS
1	EA	LED BLANKOUT SIGN
1	EA	SIGNAL CABINET FOUNDATION
1	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
6	EA	DETECTOR CARD (TYPE 2070L)
1	EA	CABINET BASE EXTENDER

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 025

CONTRACT ID : C202537 7.107912

DIV OFFICE GREENSBORO

LENGTH = 44.547 MI

COUNTY : ROCKINGHAM

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : SEP 03 2010

2 SECTIONS OF US-311, 2 SECTIONS OF NC-150, 2 SECTIONS OF NC-704 & 37 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
986	CY	BORROW EXCAVATION
2,023	TON	INCIDENTAL STONE BASE
47.18	SMI	SHOULDER RECONSTRUCTION
280	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1")
54	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
3,749	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")
1,595	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")
1,050	SY	INCIDENTAL MILLING
9,249	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
25,626	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
2,218	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
199,266	SY	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE
14	EA	ADJUSTMENT OF MANHOLES
22	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
123,022	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
102,548	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
1,010	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
210	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
72	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
466	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
32	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
26	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
744,609	LF	PAINT PAVEMENT MARKING LINES (4")
730	EA	SNOWPLOWABLE PAVEMENT MARKERS
7.93	ACR	SEEDING & MULCHING
10.21	ACR	RESIDENTIAL SEEDING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 026

CONTRACT ID : C202525 7CR.10011.18

DIV OFFICE GREENSBORO

LENGTH = 17.808 MI

COUNTY : ALAMANCE

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 5.0% WBE 5.0% COMPLETION DATE : AUG 24 2010

1 SECTION OF NC-87, NC-62, AND NC-49 AND 7 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS					
			90	EA	PAINT PAVEMENT MARKING SYMBOL
			Lump Sum	LS	PORTABLE LIGHTING
			1.36	ACR	SEEDING & MULCHING
			3.59	ACR	RESIDENTIAL SEEDING
			1,227	LF	UNPAVED TRENCHING (***** (1, 2")
			40	EA	JUNCTION BOX (STANDARD SIZE)
			24	EA	2" RISER WITH WEATHERHEAD
			10,924	LF	INDUCTIVE LOOP SAWCUT
			2,340	LF	LEAD-IN CABLE (***** (14-2)
Lump Sum	LS	MOBILIZATION			
272	CY	BORROW EXCAVATION			
936	TON	INCIDENTAL STONE BASE			
13.56	SMI	SHOULDER RECONSTRUCTION			
41,908	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")			
14,690	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")			
559	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")			
2,731	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")			
1,127	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")			
899	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")			
5,193	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/4")			
3,070	SY	INCIDENTAL MILLING			
95	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B			
8,732	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B			
14,093	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A			
1,443	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22			
27	TON	PATCHING EXISTING PAVEMENT			
187,117	SY	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE			
50	EA	RETROFIT EXISTING WHEELCHAIR RAMPS			
3	EA	CONCRETE WHEELCHAIR RAMPS			
1	EA	ADJUSTMENT OF DROP INLETS			
66	EA	ADJUSTMENT OF MANHOLES			
81	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES			
50,440	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)			
73,972	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)			
584	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)			
1,103	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)			
1,703	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)			
25	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)			
20	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)			
25	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)			
1,615	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)			
20	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)			
126	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)			
449,149	LF	PAINT PAVEMENT MARKING LINES (4")			
36	LF	PAINT PAVEMENT MARKING LINES (6")			
558	LF	PAINT PAVEMENT MARKING LINES (8")			
20	LF	PAINT PAVEMENT MARKING LINES (12")			
1,360	LF	PAINT PAVEMENT MARKING LINES (24")			
20	EA	PAINT PAVEMENT MARKING CHARAC- TER			

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 027

CONTRACT ID : C202540 7CR.10681.16

DIV OFFICE GREENSBORO

LENGTH = 15.489 MI

COUNTY : ORANGE

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : SEP 03 2010

NC-54 FROM 560' WEST OF GREENWOOD DR TO COUNTY LINE AND 11 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS				
			3,256	LF UNPAVED TRENCHING (*****) (1, 2")
			44	EA JUNCTION BOX (STANDARD SIZE)
			8	EA 2" RISER WITH WEATHERHEAD
			11,361	LF INDUCTIVE LOOP SAWCUT
			19,849	LF LEAD-IN CABLE (*****) (14-2)
Lump Sum	LS	MOBILIZATION		
275	CY	BORROW EXCAVATION		
565	TON	INCIDENTAL STONE BASE		
22.16	SMI	SHOULDER RECONSTRUCTION		
14,193	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")		
75,469	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")		
1,067	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")		
17,852	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")		
271	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")		
856	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")		
4,128	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 5-1/2")		
1,283	SY	INCIDENTAL MILLING		
6,184	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B		
882	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B		
11,831	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B		
14,552	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A		
1,960	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22		
114	TON	PATCHING EXISTING PAVEMENT		
136,294	SY	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE		
56	EA	RETROFIT EXISTING WHEELCHAIR RAMPS		
2	EA	CONCRETE WHEELCHAIR RAMPS		
50	EA	ADJUSTMENT OF MANHOLES		
31	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES		
59,126	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)		
50,346	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)		
338	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)		
3,505	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)		
7,135	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)		
611	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)		
1,107	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)		
32	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)		
133	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)		
378,957	LF	PAINT PAVEMENT MARKING LINES (4")		
565	LF	PAINT PAVEMENT MARKING LINES (8")		
611	LF	PAINT PAVEMENT MARKING LINES (12")		
151	LF	PAINT PAVEMENT MARKING LINES (24")		
12	EA	PAINT PAVEMENT MARKING SYMBOL		
Lump Sum	LS	PORTABLE LIGHTING		
4.23	ACR	SEEDING & MULCHING		
4.11	ACR	RESIDENTIAL SEEDING		
7	LF	PAVED TRENCHING (*****) (1, 2")		

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID**L100119 028****CONTRACT ID : C202495 45121.3.ST2****DIV OFFICE WINSTON-SALEM****LENGTH = 4.805 MI****COUNTY : STOKES****ULTRATHIN HOT MIX.****DBE GOAL 5.0% COMPLETION DATE : AUG 15 2010****US-52 FROM THE KING CITY LIMIT TO THE SURRY COUNTY LINE.****ROADWAY ITEMS**

Lump Sum	LS	MOBILIZATION
325	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28
6,247	TON	ULTRATHIN HOT MIX ASPHALT, TYPE B
178,483	SY	APPLICATION OF ULTRATHIN HOT MIX ASPHALT
120	HR	LAW ENFORCEMENT
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
110,875	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
12,996	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
3,112	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
6	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
800	EA	SNOWPLOWABLE PAVEMENT MARKERS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 029

CONTRACT ID : C202484 45164.3.ST2

DIV OFFICE WINSTON-SALEM

LENGTH = 4.093 MI

COUNTY : FORSYTH

MILLING, MILLED RUMBLE STRIPS & SHOULDER RECONSTRUCTION.

DBE GOAL 8.0% COMPLETION DATE : SEP 30 2010

US-421 FROM PVT JOINT NORTH OF SR-1175 (WILLIAMS RD) TO THE YADKIN COUNTY LINE.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
327	CY	BORROW EXCAVATION
16.33	SMI	SHOULDER RECONSTRUCTION
2,068	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
63,156	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")
14,224	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
10,663	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C
14,212	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
501	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
853	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
86,180	LF	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)
320	HR	LAW ENFORCEMENT
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
86,980	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
10,982	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
1,660	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
195,924	LF	PAINT PAVEMENT MARKING LINES (6")
627	EA	SNOWPLOWABLE PAVEMENT MARKERS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 030

CONTRACT ID : C202515 45309.3.ST1

DIV OFFICE WINSTON-SALEM

LENGTH = 0.000 MI

COUNTY : FORSYTH, GUILFORD

DYNAMIC MESSAGE SIGN REPLACEMENT.

DBE GOAL 0.0% COMPLETION DATE : OCT 01 2010

I-40, I-40 BUSINESS, US-421, AND US-52.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
550	LF	UNPAVED TRENCHING (***** (1, 1-1/4" & 1, 1/2")
3	EA	INTERCONNECT CENTER
4	EA	CABINET BASE EXTENDER
37	EA	GENERIC SIGNAL ITEM 5/8" X 10" COPPER CLAD GROUND- ING ELECTRODE
12	EA	GENERIC SIGNAL ITEM DISPOSAL OF EXISTING CABINET FOUNDATION
16	EA	GENERIC SIGNAL ITEM DISPOSAL OF EXISTING DMS
16	EA	GENERIC SIGNAL ITEM DMS
4	EA	GENERIC SIGNAL ITEM MODIFY EXISTING DMS CABINET FOUNDATION
10	EA	GENERIC SIGNAL ITEM MODIFY EXISTING ELECTRICAL SERVICE EQUIPMENT
160	LF	GENERIC SIGNAL ITEM #4 AWG SOLID BARE COPPER GROUNDING CONDUCTOR
670	LF	GENERIC SIGNAL ITEM 4-WIRE THWN #6 AWG STRANDED COPPER FEEDER CONDUCTORS
670	LF	GENERIC SIGNAL ITEM 6-PAIR 19 AWG FILLED TELEPHONE CABLE

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 031

CONTRACT ID : C202529 9CR.10291.7

DIV OFFICE GREENSBORO

LENGTH = 45.411 MI

COUNTY : DAVIDSON

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 5.0% WBE 5.0% COMPLETION DATE : AUG 31 2010

I-85 BUS FROM CONCRETE JOINT EAST OF US-52 INTERCHANGE TO RANDOLPH COUNTY LINE, AND 11 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
2,375	CY	BORROW EXCAVATION
2,600	TON	INCIDENTAL STONE BASE
118.75	SMI	SHOULDER RECONSTRUCTION
11,678	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
50,740	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
400	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")
41,864	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
48,682	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
2,512	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2,921	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
300	TON	PATCHING EXISTING PAVEMENT
5	EA	ADJUSTMENT OF MANHOLES
39	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
240	HR	LAW ENFORCEMENT
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
360,341	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
363,411	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
297,486	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
59,371	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
850	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
12,237	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
350	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,926	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
90	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
313	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
2,537	EA	SNOWPLOWABLE PAVEMENT MARKERS

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 032

CONTRACT ID : C202530

9CR.10301.7

DIV OFFICE WINSTON-SALEM

LENGTH = 29.061 MI

COUNTY : DAVIE

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : AUG 31 2010

US-601 FROM BRG AT I-40 TO YADKIN COUNTY LINE, US-601 FROM RR BRG TO SR-1135, AND 6 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS		
	LS	MOBILIZATION	
1,162	CY	BORROW EXCAVATION	
3,010	TON	INCIDENTAL STONE BASE	
58.13	SMI	SHOULDER RECONSTRUCTION	
555	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	
24,594	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	
710	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	
22,457	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	
60	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	
17,685	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	
1,351	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	
1,061	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	
200	TON	PATCHING EXISTING PAVEMENT	
2	EA	ADJUSTMENT OF MANHOLES	
14	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES	
120	HR	LAW ENFORCEMENT	
313,148	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	
313,890	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	
100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	
150	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	
628	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	
36	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	
96	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	
778	EA	SNOWPLOWABLE PAVEMENT MARKERS	

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 033

CONTRACT ID : C202526 9CR.10341.7

DIV OFFICE WINSTON-SALEM

LENGTH = 19.478 MI

COUNTY : FORSYTH, DAVIDSON

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : AUG 31 2010

2 SECTIONS OF US-158 & 12 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
544	CY	BORROW EXCAVATION
1,606	TON	INCIDENTAL STONE BASE
27.23	SMI	SHOULDER RECONSTRUCTION
81,504	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
62,554	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
1,333	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2-1/2")
4,237	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")
2,854	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
27,353	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
262	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)
12,745	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1,793	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
765	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
300	TON	PATCHING EXISTING PAVEMENT
1	EA	ADJUSTMENT OF DROP INLETS
97	EA	ADJUSTMENT OF MANHOLES
69	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
60	HR	LAW ENFORCEMENT
141,127	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
262,621	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
2,050	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
190	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
850	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
2,530	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
92	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
434	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
39,696	LF	PAINT PAVEMENT MARKING LINES (4")
925	LF	PAINT PAVEMENT MARKING LINES (24")
1,058	EA	SNOWPLOWABLE PAVEMENT MARKERS
Lump Sum	LS	PORTABLE LIGHTING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 034

CONTRACT ID : C202531 9CR.10801.7

DIV OFFICE WINSTON-SALEM

LENGTH = 30.969 MI

COUNTY : ROWAN

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 5.0% WBE 5.0% COMPLETION DATE : AUG 31 2010

1 SECTION OF US-29, 2 SECTIONS OF NC-152 AND 10 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
1,149	CY	BORROW EXCAVATION
3,490	TON	INCIDENTAL STONE BASE
57.45	SMI	SHOULDER RECONSTRUCTION
3,568	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
18,363	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
435	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
22,320	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
24,576	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1,359	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1,475	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
260	TON	PATCHING EXISTING PAVEMENT
1	EA	ADJUSTMENT OF DROP INLETS
17	EA	ADJUSTMENT OF MANHOLES
18	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
130	HR	LAW ENFORCEMENT
333,227	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
327,034	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
1,525	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
140	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
150	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,268	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
52	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
142	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1,869	LF	PAINT PAVEMENT MARKING LINES (4")
978	EA	SNOWPLOWABLE PAVEMENT MARKERS

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 035

CONTRACT ID : C202520 9CR.10851.7

DIV OFFICE WINSTON-SALEM

LENGTH = 27.125 MI

COUNTY : STOKES, FORSYTH

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : AUG 31 2010

US-311/NC-89 FROM NC-65 AT COVE GRILL TO NC-8 & 11 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
321	CY	BORROW EXCAVATION
1,985	TON	INCIDENTAL STONE BASE
51.22	SMI	SHOULDER RECONSTRUCTION
58,221	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1/2")
335	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
16,850	SY	MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" TO 1-1/2")
35,481	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
2,128	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
220	TON	PATCHING EXISTING PAVEMENT
22	EA	ADJUSTMENT OF MANHOLES
20	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
271,121	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
306,140	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
2,254	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
809	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
68	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
105	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
664	EA	SNOWPLOWABLE PAVEMENT MARKERS

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 036

CONTRACT ID : C202519 10CR.10601.30

DIV OFFICE ALBEMARLE

LENGTH = 16.150 MI

COUNTY : MECKLENBURG

WIDENING, MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

MBE GOAL 3.0% WBE 4.0% COMPLETION DATE : AUG 01 2010

NC-49 FROM E OF SHOP CTR TO HARRIS TEETER DWY, NC-16 FROM BRG ON I-85 TO CONC PVT JT ON NC-16
& 11 SECT OF SECOND RDS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
277	CY	BORROW EXCAVATION
170	TON	INCIDENTAL STONE BASE
8.88	SMI	SHOULDER CONSTRUCTION
13.37	SMI	SHOULDER RECONSTRUCTION
201,160	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
19,500	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")
4,800	SY	INCIDENTAL MILLING
2,236	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
2,736	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C
35,146	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
4,755	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)
226	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2,419	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
9,860	TON	PATCHING EXISTING PAVEMENT
13	EA	RETROFIT EXISTING WHEELCHAIR RAMPS
2	EA	CONCRETE WHEELCHAIR RAMPS
300	SY	6" CONCRETE DRIVEWAY
1	EA	ADJUSTMENT OF CATCH BASINS
92	EA	ADJUSTMENT OF MANHOLES
73	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
Lump Sum	LS	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL
91,900	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
193,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
7,500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
3,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
5,880	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
1,800	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)
200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)
1,454	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
66	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)
277	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
45,200	LF	PAINT PAVEMENT MARKING LINES (4")
198	LF	PAINT PAVEMENT MARKING LINES (24")
2,555	EA	PERMANENT RAISED PAVEMENT MARKERS
Lump Sum	LS	PORTABLE LIGHTING
3,800	LF	TEMPORARY SILT FENCE
8	ACR	SEEDING & MULCHING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 037

CONTRACT ID : C202527

10CR.20041.20

DIV OFFICE ALBEMARLE

LENGTH = 4.190 MI

COUNTY : ANSON

DITCHING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 4.0% WBE 4.0% COMPLETION DATE : NOV 15 2010

3 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	DESCRIPTION
	LS	MOBILIZATION
168	CY	BORROW EXCAVATION
347	TON	STABILIZER AGGREGATE
270	TON	INCIDENTAL STONE BASE
8.38	SMI	SHOULDER RECONSTRUCTION
629	LF	DITCHING
207	SY	INCIDENTAL MILLING
4,112	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1,530	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)
347	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1,710	TON	PATCHING EXISTING PAVEMENT
44,410	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
41,020	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
281	EA	PERMANENT RAISED PAVEMENT MARKERS
715	LF	TEMPORARY SILT FENCE
87	TON	STONE FOR EROSION CONTROL, CLASS B
45	TON	SEDIMENT CONTROL STONE
4.1	ACR	SEEDING & MULCHING

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 038

CONTRACT ID : C202165 32579.2.3

DIV OFFICE NORTH WILKESBORO

LENGTH = 0.245 MI

COUNTY : ASHE

GRADING, DRAINAGE, PAVING, AND STRUCTURE.

DBE GOAL 8.0% COMPLETION DATE : DEC 31 2011

BRIDGE OVER SOUTH FORK NEW FIVER AND APPROACHES ON US-221 NORTHEAST OF JEFFERSON.

ROADWAY ITEMS

			5,185	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	
Lump Sum	LS	MOBILIZATION	12,000	LF	PAINT PAVEMENT MARKING LINES (4")	
Lump Sum	LS	GENERIC MISCELLANEOUS ITEM BUILDING SURVEYS	32	EA	SNOWPLOWABLE PAVEMENT MARKERS	
6,900	CY	UNCLASSIFIED EXCAVATION	2,300	LF	TEMPORARY SILT FENCE	
Lump Sum	LS	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.50)	430	TON	STONE FOR EROSION CONTROL, CLASS A	
1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	280	TON	STONE FOR EROSION CONTROL, CLASS B	
50	CY	UNDERCUT EXCAVATION	900	TON	SEDIMENT CONTROL STONE	
Lump Sum	LS	GRADING	7.5	ACR	TEMPORARY MULCHING	
20	CY	DRAINAGE DITCH EXCAVATION	200	LB	SEED FOR TEMPORARY SEEDING	
180	SY	FOUNDATION CONDITIONING FABRIC	1.75	TON	FERTILIZER FOR TEMPORARY SEED-ING	
60	TON	GENERIC DRAINAGE ITEM FOUNDATION CONDITION MATE-RIAL, MINOR STRS	200	LF	TEMPORARY SLOPE DRAINS	
180	LF	15" RC PIPE CULVERTS, CLASS III	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	
24	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	2,000	LF	SAFETY FENCE	
76	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	600	CY	SILT EXCAVATION	
172	LF	66" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK	12,000	SY	MATTING FOR EROSION CONTROL	
48	LF	GENERIC PIPE ITEM 16" DUCTILE IRON PIPE	400	SY	COIR FIBER MAT	
100	TON	INCIDENTAL STONE BASE	2,100	LF	1/4" HARDWARE CLOTH	
570	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	15	EA	SPECIAL STILLING BASINS	
380	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150	LF	WATTLE	
50	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40	LB	POLYACRYLAMIDE (PAM)	
20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	150	LF	COIR FIBER BAFFLES	
14	EA	RIGHT OF WAY MARKERS	1	EA	*** SKIMMER (1-1/2")	
45	CY	SUBDRAIN EXCAVATION	5	ACR	SEEDING & MULCHING	
34	CY	SUBDRAIN FINE AGGREGATE	4.5	ACR	MOWING	
200	LF	6" PERFORATED SUBDRAIN PIPE	50	LB	SEED FOR REPAIR SEEDING	
6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	0.25	TON	FERTILIZER FOR REPAIR SEEDING	
1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	125	LB	SEED FOR SUPPLEMENTAL SEEDING	
6	LF	6" OUTLET PIPE (SUBDRAINS)	3.25	TON	FERTILIZER TOPDRESSING	
1	CY	ENDWALLS	10	MHR	SPECIALIZED HAND MOWING	
6.6	CY	REINFORCED ENDWALLS	27	EA	RESPONSE FOR EROSION CONTROL	
0.45	CY	PIPE COLLARS	0.5	ACR	REFORESTATION	
8	EA	MASONRY DRAINAGE STRUCTURES			***** BEGIN SCHEDULE AA *****	
11.834	CY	MASONRY DRAINAGE STRUCTURES			***** (3 ALTERNATES) *****	
1.5	LF	MASONRY DRAINAGE STRUCTURES	22	LF	18" RC PIPE CULVERTS, CLASS III	
7	EA	FRAME WITH TWO GRATES, STD 840.29			*** OR ***	
1	EA	FRAME WITH COVER, STD 840.54	10	LF	18" RC PIPE CULVERTS, CLASS III	
410	LF	SHOULDER BERM GUTTER	12	LF	***" HDPE PIPE CULVERTS (18")	
537.5	LF	STEEL BM GUARDRAIL			*** OR ***	
5	EA	ADDITIONAL GUARDRAIL POSTS	10	LF	18" RC PIPE CULVERTS, CLASS III	
4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	12	LF	***" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	
4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350			*** END SCHEDULE AA ***	
2	TON	RIP RAP, CLASS B			WALL ITEMS	
1,760	SY	FILTER FABRIC FOR DRAINAGE	60	CY	FOUNDATION EXCAVATION (RETAIN-ING WALL)	
152	SF	WORK ZONE SIGNS (STATIONARY)	14.5	CY	CLASS A CONCRETE (RETAINING WALL)	
96	SF	WORK ZONE SIGNS (PORTABLE)	1,080	LB	REINFORCING STEEL (RETAINING WALL)	
20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)			STRUCTURE ITEMS	
30	EA	DRUMS				
20	EA	CONES				
48	LF	BARRICADES (TYPE III)				
6,400	HR	FLAGGER				
1	EA	TEMPORARY CRASH CUSHIONS				
1	EA	TMIA				
60	LF	PORTABLE CONCRETE BARRIER (ANCHORED)	Lump Sum	LS	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+47.50-L-)	

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+47.50-L-)
330	CY	FOUNDATION EXCAVATION
29.9	LF	***.***" DIA DRILLED PIERS IN SOIL (6'-0")
51	LF	***.***" DIA DRILLED PIERS NOT IN SOIL (6'-0")
14.9	LF	PERMANENT STEEL CASING FOR ***.***" DIA DRILLED PIER (6'-0")
2	EA	SID INSPECTION
2	EA	CROSSHOLE SONIC LOGGING
Lump Sum	LS	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+47.50-L-)
13,764	SF	REINFORCED CONCRETE DECK SLAB
11,970	SF	GROOVING BRIDGE FLOORS
301.7	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (17+47.50-L-)
59,748	LB	REINFORCING STEEL (BRIDGE)
7,290	LB	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)
1,351.5	LF	MODIFIED 63" PRESTRESSED CONC GIRDERS
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	EVAZOTE JOINT SEALS
Lump Sum	LS	STRUCTURE DRAINAGE SYSTEM AT STA***** (17+47.50-L-)
907.33	LF	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 039

CONTRACT ID : C202273 33832.3.1

DIV OFFICE NORTH WILKESBORO

LENGTH = 0.055 MI

COUNTY : WILKES

GRADING, DRAINAGE, PAVING, AND STRUCTURE.

DBE GOAL 6.0% COMPLETION DATE : OCT 15 2010

BRIDGE OVER COAL CREEK AND APPROACHES ON SR-1317 (OLD HWY 70).

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
1,250	CY	UNCLASSIFIED EXCAVATION
100	CY	UNDERCUT EXCAVATION
1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
Lump Sum	LS	GRADING
100	TON	CLASS IV SUBGRADE STABILIZATION
10	CY	DRAINAGE DITCH EXCAVATION
100	CY	SELECT GRANULAR MATERIAL
100	SY	FABRIC FOR SOIL STABILIZATION
30	SY	FOUNDATION CONDITIONING FABRIC
10	TON	GENERIC DRAINAGE ITEM FOUNDATION COND MATERIAL MINOR STRS
40	LF	GENERIC PIPE ITEM 15" RC PIPE CULVERTS CLASS IV
32	LF	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE
50	TON	INCIDENTAL STONE BASE
260	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
140	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
25	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
16	EA	RIGHT OF WAY MARKERS
22.4	CY	SUBDRAIN EXCAVATION
16.8	CY	SUBDRAIN FINE AGGREGATE
100	LF	6" PERFORATED SUBDRAIN PIPE
3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
6	LF	6" OUTLET PIPE (SUBDRAINS)
1	EA	MASONRY DRAINAGE STRUCTURES
1	EA	FRAME WITH TWO GRATES, STD 840.24
4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
225	LF	GENERIC GUARDRAIL ITEM STEEL BEAM GUARDRAIL
3	EA	GENERIC GUARDRAIL ITEM ADDITIONAL GUARDRAIL POSTS
600	LF	GENERIC FENCING ITEM TEMPORARY 4 STRAND BARRBED WIRE FENCE WITH POSTS
10	TON	RIP RAP, CLASS B
675	SY	FILTER FABRIC FOR DRAINAGE
335	SF	WORK ZONE SIGNS (STATIONARY)
119	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
96	LF	BARRICADES (TYPE III)
1,160	LF	PAINT PAVEMENT MARKING LINES (4")
450	LF	TEMPORARY SILT FENCE
250	TON	STONE FOR EROSION CONTROL, CLASS A
70	TON	STONE FOR EROSION CONTROL, CLASS B
150	TON	SEDIMENT CONTROL STONE
1	ACR	TEMPORARY MULCHING
75	LB	SEED FOR TEMPORARY SEEDING
1.25	TON	FERTILIZER FOR TEMPORARY SEEDING
250	LF	TEMPORARY SLOPE DRAINS
5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
700	LF	SAFETY FENCE
160	CY	SILT EXCAVATION
7,000	SY	MATting FOR EROSION CONTROL
20	SY	COIR FIBER MAT
300	SY	PERMANENT SOIL REINFORCEMENT MAT
400	LF	1/4" HARDWARE CLOTH

2	EA	SPECIAL STILLING BASINS
80	LF	WATTLE
20	LB	POLYACRYLAMIDE (PAM)
100	LF	COIR FIBER BAFFLES
1	EA	*** SKIMMER (1-1/2')
5	ACR	SEEDING & MULCHING
0.5	ACR	MOWING
50	LB	SEED FOR REPAIR SEEDING
0.25	TON	FERTILIZER FOR REPAIR SEEDING
50	LB	SEED FOR SUPPLEMENTAL SEEDING
0.5	TON	FERTILIZER TOPDRESSING
150	LF	IMPERVIOUS DIKE
10	MHR	SPECIALIZED HAND MOWING
12	EA	RESPONSE FOR EROSION CONTROL

CULVERT ITEMS

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+67.00-L-)
56.9	CY	CLASS A CONCRETE (CULVERT)
30	TON	RIP RAP CLASS II (2'-0" THICK)
Lump Sum	LS	GENERIC CULVERT ITEM PRECAST REINF CONC 3-SIDED CULVERT @ STA.15+67.00-L-

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 040

CONTRACT ID : C202227 33314.3.1

DIV OFFICE ASHEVILLE

LENGTH = 0.024 MI

COUNTY : MADISON

GRADING, PAVING, & STRUCTURE.

DBE GOAL 6.0% COMPLETION DATE : DEC 31 2010

BRIDGE OVER BIG PINE CREEK AND APPROACHES ON SR-1151.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION			
Lump Sum	LS	CONSTRUCTION SURVEYING			
100	CY	UNDERCUT EXCAVATION			
Lump Sum	LS	GRADING			
1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING			
100	TON	CLASS IV SUBGRADE STABILIZA- TION			
100	CY	SELECT GRANULAR MATERIAL			
100	SY	FABRIC FOR SOIL STABILIZATION			
42	TON	AGGREGATE BASE COURSE			
25	TON	INCIDENTAL STONE BASE			
42	GAL	PRIME COAT			
12	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B			
70	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A			
6	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22			
6	EA	RIGHT OF WAY MARKERS			
15	CY	SUBDRAIN EXCAVATION			
10	CY	SUBDRAIN FINE AGGREGATE			
50	LF	6" PERFORATED SUBDRAIN PIPE			
3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS			
1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET			
6	LF	6" OUTLET PIPE (SUBDRAINS)			
25	LF	STEEL BM GUARDRAIL			
12.5	LF	STEEL BM GUARDRAIL, SHOP CURVED			
5	EA	ADDITIONAL GUARDRAIL POSTS			
2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)			
1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)			
1	EA	GUARDRAIL ANCHOR UNITS, TYPE III			
12.5	LF	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)			
1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III SHOP CURVED)			
2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)			
3	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (350 TL-2)			
1	EA	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350 TL-2			
600	SY	FILTER FABRIC FOR DRAINAGE			
39	LF	SUPPORTS, 3-LB STEEL U-CHANNEL			
3	EA	SIGN ERECTION, TYPE E			
9	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL			
213	SF	WORK ZONE SIGNS (STATIONARY)			
144	SF	WORK ZONE SIGNS (PORTABLE)			
32	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)			
30	EA	DRUMS			
48	LF	BARRICADES (TYPE III)			
480	HR	FLAGGER			
25	EA	TEMPORARY RAISED PAVEMENT MARKERS			
5,642	LF	PAINT PAVEMENT MARKING LINES (4")			
350	LF	REMOVAL OF PAVEMENT MARKING LINES (4")			
700	LF	TEMPORARY SILT FENCE			
310	TON	STONE FOR EROSION CONTROL, CLASS A			
15	TON	STONE FOR EROSION CONTROL, CLASS B			

65	TON	SEDIMENT CONTROL STONE			
0.5	ACR	TEMPORARY MULCHING			
50	LB	SEED FOR TEMPORARY SEEDING			
0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING			
200	LF	TEMPORARY SLOPE DRAINS			
4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS			
550	LF	SAFETY FENCE			
40	CY	SILT EXCAVATION			
7,500	SY	MATTING FOR EROSION CONTROL			
280	LF	1/4" HARDWARE CLOTH			
20	LF	COIR FIBER BAFFLES			
0.5	ACR	SEEDING & MULCHING			
0.5	ACR	MOWING			
50	LB	SEED FOR REPAIR SEEDING			
0.25	TON	FERTILIZER FOR REPAIR SEEDING			
50	LB	SEED FOR SUPPLEMENTAL SEEDING			
0.25	TON	FERTILIZER TOPDRESSING			
12	MHR	SPECIALIZED HAND MOWING			
12	EA	RESPONSE FOR EROSION CONTROL			
0.1	ACR	REFORESTATION			

STRUCTURE ITEMS

Lump Sum	LS	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (11+17.00-L-)			
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11+17.00-L-)			
120	LF	PILE EXCAVATION IN SOIL			
60	LF	PILE EXCAVATION NOT IN SOIL			
30.6	CY	CLASS A CONCRETE (BRIDGE)			
4,218	LB	REINFORCING STEEL (BRIDGE)			
75	LF	HP12X53 STEEL PILES			
105	LF	HP12X53 GALVANIZED STEEL PILES			
75.21	LF	VERTICAL CONCRETE BARRIER RAIL			
35	TON	RIP RAP CLASS II (2'-0" THICK)			
39	SY	FILTER FABRIC FOR DRAINAGE			
Lump Sum	LS	ELASTOMERIC BEARINGS			
300.83	LF	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS			
345	SF	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES			

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 041

CONTRACT ID : C202269 33703.3.1

DIV OFFICE ASHEVILLE

LENGTH = 0.047 MI

COUNTY : BUNCOMBE

GRADING, DRAINAGE, PAVING, AND STRUCTURE.

DBE GOAL 7.0% COMPLETION DATE : DEC 31 2010

BRIDGE OVER REEM'S CREEK AND APPROACHES ON SR-2105.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
Lump Sum	LS	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+48.95)
100	CY	UNDERCUT EXCAVATION
Lump Sum	LS	GRADING
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
100	TON	CLASS IV SUBGRADE STABILIZATION
100	CY	SELECT GRANULAR MATERIAL
100	SY	FABRIC FOR SOIL STABILIZATION
70	SY	FOUNDATION CONDITIONING FABRIC
40	TON	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATERIAL, MINOR STRS
16	LF	15" DRAINAGE PIPE
94	LF	GENERIC PIPE ITEM 18" CS PIPE CULVERTS 0.064" THICK
72	LF	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE
2	EA	GENERIC PIPE ITEM CS PIPE TEES (18" X 18" X 18", 0.064")
238	LF	PIPE REMOVAL
100	TON	INCIDENTAL STONE BASE
150	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
40	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
80	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
15	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
65	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
22.4	CY	SUBDRAIN EXCAVATION
16.8	CY	SUBDRAIN FINE AGGREGATE
100	LF	6" PERFORATED SUBDRAIN PIPE
3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
6	LF	6" OUTLET PIPE (SUBDRAINS)
0.45	CY	PIPE COLLARS
1	EA	MASONRY DRAINAGE STRUCTURES
1	EA	FRAME WITH TWO GRATES, STD 840.29
2	EA	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350 (TL-2)
30	TON	RIP RAP, CLASS I
2	TON	RIP RAP, CLASS B
705	SY	FILTER FABRIC FOR DRAINAGE
410	SF	WORK ZONE SIGNS (STATIONARY)
100	SF	WORK ZONE SIGNS (PORTABLE)
90	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
20	EA	DRUMS
25	EA	CONES
40	LF	BARRICADES (TYPE III)
200	HR	FLAGGER
250	LF	WATER FILLED BARRIER
850	LF	RESET WATER FILLED BARRIER
2,600	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)
50	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)
1,600	LF	PAINT PAVEMENT MARKING LINES (4")
1,200	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
180	LF	8" WATER LINE

1	EA	8" VALVE
1	EA	8" TAPPING VALVE
1	EA	RELOCATE FIRE HYDRANT
180	LF	ABANDON 8" UTILITY PIPE
20	LF	TRENCHLESS INSTALLATION OF 8" IN SOIL
20	LF	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL
100	LF	TEMPORARY SILT FENCE
300	TON	STONE FOR EROSION CONTROL, CLASS A
75	TON	STONE FOR EROSION CONTROL, CLASS B
150	TON	SEDIMENT CONTROL STONE
1	ACR	TEMPORARY MULCHING
50	LB	SEED FOR TEMPORARY SEEDING
1.25	TON	FERTILIZER FOR TEMPORARY SEEDING
225	LF	TEMPORARY SLOPE DRAINS
4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
650	LF	SAFETY FENCE
250	CY	SILT EXCAVATION
7,800	SY	MATTING FOR EROSION CONTROL
20	SY	COIR FIBER MAT
200	SY	PERMANENT SOIL REINFORCEMENT MAT
625	LF	1/4" HARDWARE CLOTH
100	LF	WATTLE
20	LB	POLYACRYLAMIDE (PAM)
150	LF	COIR FIBER BAFFLES
2	EA	** SKIMMER (1-1/2")
5	ACR	SEEDING & MULCHING
0.5	ACR	MOWING
50	LB	SEED FOR REPAIR SEEDING
0.25	TON	FERTILIZER FOR REPAIR SEEDING
50	LB	SEED FOR SUPPLEMENTAL SEEDING
0.5	TON	FERTILIZER TOPDRESSING
20	MHR	SPECIALIZED HAND MOWING
12	EA	RESPONSE FOR EROSION CONTROL
0.1	ACR	REFORESTATION
20	DAY	GENERIC SIGNAL ITEM PORTABLE TRAFFIC SIGNAL SYSTEM

STRUCTURE ITEMS

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+48.95-L-)
145	LF	PILE EXCAVATION IN SOIL
45	LF	PILE EXCAVATION NOT IN SOIL
Lump Sum	LS	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+48.95-L-)
36.9	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (13+48.95-L-)
4,938	LB	REINFORCING STEEL (BRIDGE)
150	LF	HP12X53 STEEL PILES
225	LF	HP12X53 GALVANIZED STEEL PILES
121.5	LF	VERTICAL CONCRETE BARRIER RAIL
141	TON	RIP RAP CLASS II (2'-0" THICK)
157	SY	FILTER FABRIC FOR DRAINAGE
Lump Sum	LS	ELASTOMERIC BEARINGS
607.5	LF	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS
955	SF	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PILES

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L100119 042

CONTRACT ID : C202483 41860.3.ST1

DIV OFFICE SYLVA

LENGTH = 9.190 MI

COUNTY : POLK

MILLING, RESURFACING, GUARDRAIL & SHOULDER RECONSTRUCTION.

DBE GOAL 8.0% COMPLETION DATE : SEP 30 1010

I-26 FROM MP 61.75 TO THE SOUTH CAROLINA LINE, MP 71.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
7.95	SMI	SHOULDER RECONSTRUCTION
23,714	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")
379,983	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
109,766	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")
18,770	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D
24,960	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
36,389	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5D
1,559	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
882	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
3,141	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22
15,932	TON	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED
206,005	LF	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)
13	EA	FRAME WITH GRATE, STD 840.24
13	EA	GENERIC DRAINAGE ITEM DRAINAGE STRUCTURE REPAIR
14	EA	GENERIC DRAINAGE ITEM FUNNEL DRAIN INLET REPAIR
8,746	SY	4" CONCRETE PAVED DITCH
1,200	LF	GENERIC PAVING ITEM CONCRETE MEDIAN BARRIER WALL REPAIR
3,750	LF	STEEL BM GUARDRAIL
54	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
704	SF	WORK ZONE SIGNS (STATIONARY)
2,400	SF	WORK ZONE SIGNS (PORTABLE)
6	EA	FLASHING ARROW PANELS, TYPE C
6	EA	CHANGEABLE MESSAGE SIGN
100	EA	DRUMS
800	EA	CONES
4	EA	TMIA
800	EA	SKINNY DRUM
51,680	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
11,760	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
173,660	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
33,320	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
7,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
25	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
964,369	LF	PAINT PAVEMENT MARKING LINES (4")
47	EA	PAINT PAVEMENT MARKING SYMBOL
1,986	EA	SNOWPLOWABLE PAVEMENT MARKERS
600	EA	GENERIC TRAFFIC CONTROL ITEM GUARDRAIL DELINEATORS
250	EA	GENERIC TRAFFIC CONTROL ITEM REMOVE & REPLACE TOP MOUNTED BARRIER WALL DELINEATORS
100	EA	GENERIC TRAFFIC CONTROL ITEM SIDE MOUNTED BARRIER WALL DELINEATORS
Lump Sum	LS	PORTABLE LIGHTING

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 044

CONTRACT ID : C202514 14CR.10451.4

DIV OFFICE SYLVA

LENGTH = 19.710 MI

COUNTY : HENDERSON, POLK

MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 2.0% WBE 3.0% COMPLETION DATE : SEP 30 2010

US-64 FROM EAST OF SR-1006 TO SR-1749, NC-108 FROM I-26 EXIT RAMP TO US-176 & 12 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
39.66	SMI	SHOULDER RECONSTRUCTION
3,344	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")
38,111	SY	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2")
2,000	SY	INCIDENTAL MILLING
772	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
5,300	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
19,989	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
4,880	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
2,898	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)
1,673	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
292	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
4	EA	ADJUSTMENT OF DROP INLETS
4	EA	ADJUSTMENT OF MANHOLES
14	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
288	SF	WORK ZONE SIGNS (STATIONARY)
96	SF	WORK ZONE SIGNS (PORTABLE)
2	EA	FLASHING ARROW PANELS, TYPE C
2	EA	CHANGEABLE MESSAGE SIGN
24	EA	DRUMS
2	EA	TMIA
200	EA	SKINNY DRUM
965,452	LF	PAINT PAVEMENT MARKING LINES (4")
1,272	LF	PAINT PAVEMENT MARKING LINES (8")
1,456	LF	PAINT PAVEMENT MARKING LINES (24")
12	EA	PAINT PAVEMENT MARKING CHARAC- TER
218	EA	PAINT PAVEMENT MARKING SYMBOL
Lump Sum	LS	PORTABLE LIGHTING
1,872	LF	INDUCTIVE LOOP SAWCUT
1,640	LF	LEAD-IN CABLE (***** (18-2)

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L100119 045

CONTRACT ID : C202508 14CR.10501.4 DIV OFFICE SYLVA
 COUNTY : JACKSON, TRANSYLVANIA

LENGTH = 30.810 MI

WIDENING, MILLING, RESURFACING & SHOULDER RECONSTRUCTION.

MBE GOAL 2.0% WBE 3.0% COMPLETION DATE : SEP 30 2010

2 SECTIONS OF US-64, 3 SECTIONS OF NC-215 & 4 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
61.63	SMI	SHOULDER RECONSTRUCTION
37,304	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (3")
2,786	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
18,463	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
34,698	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
11,731	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)
3,831	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
12	EA	ADJUSTMENT OF MANHOLES
13	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
1,847,994	LF	PAINT PAVEMENT MARKING LINES (4")
1,350	LF	PAINT PAVEMENT MARKING LINES (8")
698	LF	PAINT PAVEMENT MARKING LINES (24")
12	EA	PAINT PAVEMENT MARKING CHARAC- TER
7	EA	PAINT PAVEMENT MARKING SYMBOL