

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT SECRETARY

October 9, 2002

Addendum No. 1

RE:

State Project: 6.451015R

Harnett County

US-401 From US-421 to the

Wake County Line.

OCTOBER 15, 2002 LETTING

To Whom It May Concern:

Reference is made to the Sketch Maps and Proposal form recently furnished to you on the above project.

The following revision has been made to the Sketch Maps:

On Sheet No. 3 of 4 of the Sketch Maps, the Quanity for "Seed and Mulching" has been revised to read "15 Acres" instead of "35 Acres". Please void Sheet No. 3 of 4 and staple the revised Sheet No. 3 of 4 thereto.

The following revisions have been made to the proposal form:

On Page No. 2 of 2 of the Item Sheets, Line 24-6084000000-E-1660 "Seeding and Mulching" has been revised. Please draw a single line thru 35 and insert 15 and initial same in ink.(Sample Attached).

On Page No. 39 a paragraph has been added under "MARKING BY CONTRACTOR: ALL FACILITIES". Please void Page No. 39 in your proposal and staple the revised Page No. 39 thereto.

WEBSITE: WWW.DOH.DOT.STATE.NC.US

We are sending new diskettes to those bidders who requested diskettes when ordering proposals for the above mentioned project. Please destroy the diskette previously furnished and replace with the diskette dated October 9, 2002.

Sincerely,

R. A. Garris, P.E. Contract Officer

RAG/rdk/pa (Attachments)

cc: Mr. J. D. Goins, P.E.

Mr. S. D. DeWitt, P.E

Mr. T. R. Gibson, P.E.

Ms. D. M. Barbour, P.E

Mr. J. V. Barbour, P.E.

Mr. Stuart Bourne, P.E.

Mr. Mark Staley (2)

Mr. Aydren Flowers

Mr. Ron Davenport, Jr., P.E

Mr. J. A. Bennett, P.E.

Ms. Kim Canady

Ms. Yang Steelman

Project File (2)

REVISED 10-9-02

Project: 6.451015R

Date: 10-08-02

Revised:

Harnett County

TIME LIMITATION FOR PLACEMENT AND REPLACEMENT OF PAVEMENT MARKINGS AND MARKERS COMPLETED BY CONTRACTORS ON NEWLY RESURFACED AREAS

MARKING BY CONTRACTOR: DIVIDED AND MULTI-LANE FACILITIES

For all Interstate highways and access ramps, place all markings including symbols and legends, by the end of each workday's operation.

For all divided and multi-lane facilities, place all center line and lane line markings and railroad and school symbols by the end of each workday's operation. Place all edge lines, gore lines, and other symbols within 3 calendar days after they have been obliterated by the resurfacing operation.

A Multi-lane facility is defined as any roadway having more than two lanes to include a two-lane, two-way with two-way left turn lane.

MARKING BY CONTRACTOR: TWO-LANE, TWO-WAY FACILITIES

For all two-lane, two-way facilities, place all center line markings, railroad and school symbols within 5 calendar days after they have been obliterated by the resurfacing operation. Place all edge lines and other symbols within 30 calendar days after they have been obliterated by the resurfacing operation.

MARKING BY CONTRACTOR: ALL FACILITIES

Place two applications of paint on newly resurfaced asphalt which will remain in place over three (3) months. Place the second application of paint upon ample drying time of the first, as determined by the Engineer.

There will be no direct payment for any temporary paint pavement markings necessary to maintain traffic flow and meet other requirements of this contract and the Standard Specifications. Such temporary pavement markings will be considered incidental to other bid items in the contract.

MARKERS BY CONTRACTOR: ALL FACILITIES

Install permanent pavement markers within sixty (60) calendar days after completing the resurfacing on each map.

R-4Revised

ITEMIZED PROPOSAL FOR CONTRACT NO. C200566

Page 2 of 2

County: HARNETT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	225 LF		
0020	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	480 LF		
 0021	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	22 EA		
 0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	19 EA		
 0023	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	750 EA		
0024	6084000000-E	1660	SEEDING & MULCHING	-35 - ACR	15 _{RoK}	
0025	6090000000-E	1661	SEED FOR REPAIR SEEDING	25 LB		
0026	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.13 TON		
4540	Sep11/Q 262328.73	VD94456400	000/E26 Total Amount Of Bid For	Entire Project :		