

CONTRACT #D000044 ROWAN COUNTY #95 B-5221

EXISTING BRIDGE #95
 17'-1" CLEAR ROADWAY
 SPANS: 2 @ 20'-6" CONTINUOUS
 TIMBER FLOOR ON I-BEAMS
 ABUTMENTS: MASS CONCRETE
 INTERIOR BENT: TIMBER CAP & PILES
 CONCRETE ENCASED

TBM #1:
 SEE ROADWAY PLANS

TBM #2:
 BRIDGE SPIKE IN 14" WALNUT
 58.7' LT. OF STA. 7+74.0 -BL-
 67.68' LT. OF STA. 12+68.97
 ELEV. = 661.76'

TBM #3:
 SEE ROADWAY PLANS

HORIZONTAL CURVE DATA

PI STA. 12+16.02 -L- $\Delta = 1^\circ 47' 16.4" (LT)$ $D = 1^\circ 08' 45.3"$ $L = 156.02'$ $T = 78.02'$ $R = 5000.00'$	PI STA. 15+07.24 -L- $\Delta = 12^\circ 33' 00.3" (LT)$ $D = 4^\circ 35' 01.2"$ $L = 273.80'$ $T = 137.45'$ $R = 1250.00'$
---	---

HYDROGRAPHIC DATA:

DESIGN DISCHARGE -	1550 CFS
FREQUENCY OF DESIGN FLOOD -	2 YEAR
DESIGN HIGH WATER ELEVATION -	662.0
DRAINAGE AREA -	15.1 SQ. MI.
BASIC DISCHARGE (Q 100) -	4070 CFS
BASIC HIGH WATER ELEVATION -	666.0

OVERTOPPING FLOOD DATA:

OVERTOPPING DISCHARGE -	3410 CFS
FREQUENCY OF OVERTOPPING FLOOD -	50 YEAR
OVERTOPPING FLOOD ELEVATION -	665.5

NOTES

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR THE DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH HEC 18, "EVALUATING SCOUR AT BRIDGES", MAY 2001.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR SEISMIC DESIGN OF HIGHWAY BRIDGES FOR SEISMIC CATEGORY A.

IN AS MUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1, OF THE STANDARD SPECIFICATIONS, ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE AT STATION 13+18.50".


WHEN DRIVING PILES, THE MAXIMUM BLOW COUNT SHALL NOT BE EXCEEDED.

PILES FOR END BENT #1 AND END BENT #2 SHALL BE DRIVEN TO A MINIMUM BEARING CAPACITY OF 45 TONS EACH.

THE SCOUR CRITICAL ELEVATION FOR BENT #1 IS ELEVATION 651. THE SCOUR CRITICAL ELEVATIONS ARE FOR USE BY MAINTENANCE FORCES TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.


THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH FHWA'S TECHNICAL ADVISORY T5140.20 (SCOUR AT BRIDGES).

THE QUANTITY OF RIP RAP TO BE PAID FOR WILL BE THE ACTUAL NUMBER OF TONS OF EACH CLASS OF RIP RAP WHICH HAS BEEN INCORPORATED INTO THE COMPLETED AND ACCEPTED WORK. THE RIP RAP WILL BE MEASURED BY BEING WEIGHED IN TRUCKS ON CERTIFIED PLATFORM SCALES OR OTHER CERTIFIED WEIGHING DEVICES. THE QUANTITY OF RIP RAP WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON:




PLAIN RIP RAP CLASS II (2'-0" THICK) & FILTER FABRIC

END BENT #1	55 TONS & 54 SY FILTER FABRIC
END BENT #2	100 TONS & 110 SY FILTER FABRIC
TOTAL	155 TONS & 164 SY FILTER FABRIC



PLAN
SCALE: 1" = 20'

- ⊙ DENOTES GEO-TECH BORE HOLE LOCATIONS.
- * DENOTES GUARDRAIL CONNECTION REQ'D., SEE "GUARDRAIL ANCHOR UNIT" SHEET.
- ① 60° TO EXTENDED TANGENT



PROFILE ALONG Q SURVEY
SCALE: 1" = 20'

DRILLED PIER NOTES

THE DRILLED PIERS AT BENT #1 HAVE BEEN DESIGNED FOR TIP BEARING ONLY. THE REQUIRED TIP BEARING CAPACITY IS 25 TSF.

THE REQUIRED TIP BEARING CAPACITY AT BENT #1 SHALL BE VERIFIED.

PERMANENT STEEL CASING MAY BE REQUIRED FOR DRILLED PIERS AT BENT #1. IF REQUIRED, THE CASING SHALL NOT EXTEND BELOW ELEVATION 653 FT WITHOUT THE ENGINEER'S PERMISSION. THE NEED FOR PERMANENT STEEL CASING WILL BE DETERMINED BY THE ENGINEER.

SPT TESTING IS NOT REQUIRED TO DETERMINE THE TIP BEARING CAPACITY OF DRILLED PIERS AT BENT #1.

SID INSPECTIONS ARE NOT REQUIRED TO DETERMINE THE BOTTOM CLEANLINESS OF THE DRILLED PIERS AT BENT #1.

FOR PERMANENT STEEL CASING, SEE SPECIAL PROVISIONS FOR DRILLED PIERS.

NO SEPARATE PAYMENT SHALL BE MADE FOR ANY ADDITIONAL STEEL REQUIRED IN CONSTRUCTION OF THE DRILLED PIER AS THIS IS CONSIDERED INCIDENTAL TO THE LINEAR FOOT PRICE FOR DRILLED PIER.

THE CONTRACTORS ATTENTION IS CALLED TO THE FACT THAT THE REINFORCEMENT FOR THE DRILLED PIER IS DETAILED WITH THREE FEET OF EXTRA LENGTH.

FOR DRILLED PIERS, SEE SPECIAL PROVISIONS.



PLANS PREPARED BY:

SIMPSON ENGINEERS & ASSOCIATES

5520 Oillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

GENERAL DRAWING
 (BRIDGE ON SR 2114
 OVER TOWN CREEK)

30' CLEAR ROADWAY - 60° SKEW

REVISIONS					SHEET NO.
NO.	BY	DATE	NO.	BY	DATE
1			3		
2			4		

TOTAL SHEETS: 29

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09

2/19/2010 3:45:08 PM g:\projects\blm\rowan 95\Drawings\NCMA94028.sd,gc,01.dgn

GENERAL NOTES:

2006 SPECIFICATIONS
EFFECTIVE: 07-18-06
REVISED: 07-30-08

GRADE LINE:

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

APPROXIMATE GUARDRAIL LENGTH				
STATION	LOCATION	STATION	LOCATION	LENGTH
-L- 10+83.44 +/-	RT	-L- 12+83.44 +/-	RT	200'
-L- 11+78.51 +/-	LT	-L- 12+66.01 +/-	LT	87.5'
-L- 13+70.90 +/-	RT	-L- 14+45.90 +/-	RT	75'
-L- 13+53.59 +/-	LT	-L- 14+37.35 +/-	LT	83.76'
-L- 14+57.54 +/-	LT	-L- 15+64.44 +/-	LT	106.9'
SUBTOTAL				553.16'
ANCHOR DEDUCTIONS				375'
TOTAL				178.16'
SAY				187.5'

ANCHOR DEDUCTIONS		
GRAU-350	6 X 50'	300'
TYPE B-77	4 X 18.75'	75'
TOTAL ANCHOR DEDUCTIONS		375'



EFF. 07-18-06
REV. 01-02-07

2006 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated July 18, 2006 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement
DIVISION 4 - MAJOR STRUCTURES	
422.10	Reinforced Bridge Approach Fills
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 8 - INCIDENTALS	
862.01	Guardrail Placement
862.02	Guardrail Installation
862.03	Structure Anchor Units
862.04	Anchoring End of Guardrail - B-77 and B-83 Anchor Units

2/19/2010 2:01:52 PM g:\projects\bmw\rowan_95\drawings\NCMA094028_sd_of_01.dgn




PROJECT SERVICES UNIT
STANDARDS AND SPECIAL DESIGN
Office 919-250-4128 FAX 919-250-4119

BRIDGE APPROACH FILLS
CORED SLAB & BOX BEAM BRIDGES
SUB REGIONAL TIER

ORIGINAL BY: K. A. Kempf	DATE: 6-10-08
MODIFIED BY:	DATE:
CHECKED BY:	DATE:
FILE SPEC.: k Kempf/english/bridge approach fills.dgn	

DESIGN DATA
 ADT 2004 = 1500
 ADT 2025 = 2800
 * V = 45 MPH
 * DESIGN EXCEPTION: FOR SHOULDER WIDTH
 DITCH WIDTH
 SUPER ELEVATION


B-5221




TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1:
 -L- STA 10+80.00 TO 12+74.73 (BEG. BRIDGE)
 -L- STA 13+62.25 (END BRIDGE) TO 15+75.00
 NOTE: FOR VARIABLE SLOPES SEE CROSS SECTIONS.
 SEE PLANS FOR TAPERS.
 TRANSITION FROM EXISTING TO TYPICAL 1 10+80 TO 11+80

CONTRACT # D000044





**VICINITY MAP
 OFFSITE DETOUR ROUTE**



Detail Showing Method of Wedging

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1½" IN DEPTH.
E1	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
W	WEDGING (SEE DETAIL SHOWING METHOD OF WEDGING)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY OTHERS FOR MONUMENT "GPS-4" WITH NAD 83 STATE PLANE GRID COORDINATES OF NORTHING: 703049.41(11) EASTING: 1574338.32(11F) THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 99987.14 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "GPS-4" TO -L- STATION 10+00.00 IS S 4° 26' 58.0" W 698.52' ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

-L-

PI Sta 12+16.02	PI Sta 15+07.24
$\Delta = 1^{\circ} 47' 16.4" (LT)$	$\Delta = 12^{\circ} 33' 00.3" (LT)$
$D = 1^{\circ} 08' 45.3"$	$D = 4^{\circ} 35' 01.2"$
$L = 156.02'$	$L = 273.80'$
$T = 78.02'$	$T = 137.45'$
$R = 5,000.00'$	$R = 1,250.00'$
SE = SEE PLAN VIEW	SE = SEE PLAN VIEW



BENCH MARKS

BM 1: BRIDGE SPIKE SET IN 18" POPLAR
 -BL- STA 5+96 LEFT 52.7'
 -L- STA 10+90.26 LEFT 47.22'
 N = 702448.2 E = 1574247.9
 EL = 668.01'


BM 2: BRIDGE SPIKE SET IN 14" WALNUT
 -BL- STA 7+74 LEFT 58.7'
 -L- STA 12+68.97 LEFT 67.68'
 N = 702626.5 E = 1574246.8
 EL = 661.76'

BM 3: BRIDGE SPIKE SET IN 16" PINE
 -BL- STA 10+72 RIGHT 41.4'
 -L- STA 15+65.79 RIGHT 38.83'
 N = 702919.2 E = 1574363.5
 EL = 664.98'


BRIDGE HYDRAULIC DATA

DESIGN DISCHARGE = 1550 CFS
 DESIGN FREQUENCY = 2 YRS
 DESIGN HW ELEVATION = 662 FT
 BASE DISCHARGE = 4070 CFS
 BASE FREQUENCY = 100 YRS
 BASE HW ELEVATION = 666 FT
 OVERTOPPING DISCHARGE = 3410 CFS
 OVERTOPPING FREQUENCY = 50 YRS
 OVERTOPPING ELEVATION = 665.5 FT


DATE OF SURVEY =
 W.S.ELEVATION =
 AT DATE OF SURVEY = 655.23 FT




Designer1
 C:\Users\woodkay\OneDrive\Documents\1122710.dwg
 2/17/2010 11:27:10 AM



Design: 1
 2: Yr 04/04/2018
 11:27:11 AM
 C:\Users\j\OneDrive\Documents\112711.dgn



Designer:1
 r:\roadwork\ssu\sp\img\9402b_rdy_1_1_xpl.dgn
 11/27/12 AM



LONG CHORD LAYOUT

ANGLES

- ① 59°55'54"
- ② 59°46'44"
- ③ 60°00'00"

-L- HORIZONTAL CURVE DATA

CURVE 1

PI = 12+16.02 -L-
 Δ = 1°47'16.4" LT.
 D = 1°08'45.3"
 L = 156.02'
 T = 78.02'
 R = 5000.0'

CURVE 2

PI = 15+07.24 -L-
 Δ = 12°33'00.3" LT.
 D = 4°35'01.2"
 L = 273.80'
 T = 137.45'
 R = 1250.0'

WBS NO. 42818.3.1
ROWAN COUNTY
 STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95



PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
SEA & A
 5520 Dilford Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA					
DEPARTMENT OF TRANSPORTATION					
RALEIGH					
LONG CHORD LAYOUT					
30' CLEAR ROADWAY - 60° SKEW					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					TOTAL SHEETS
					9
					29

DRAWN BY : R. SEALEY DATE : 3/09
 CHECKED BY : M. AVERETTE DATE : 3/09

2/19/2010 2:01:36 PM g:\projects\brm\rowan_95\Drawings\NCMA9402B_sd.ic_01.dgn

GENERAL NOTES

ASSUMED LIVE LOAD = HS 20 OR ALTERNATE LOADING. EXCEPT THAT CORED SLAB UNITS HAVE BEEN DESIGNED FOR HS 25.

CONCRETE = $f'c$ - 5000psi 30' SPAN ONLY (MIN. COMP. STRENGTH @ 28 DAYS).
 $f'ci$ - 4000psi 30' SPAN ONLY (MIN. COMP. STRENGTH @ TRANSFER OF STRESSING FORCE).

CONCRETE = $f'c$ - 7000psi 55' SPAN ONLY (MIN. COMP. STRENGTH @ 28 DAYS).
 $f'ci$ - 5500psi 55' SPAN ONLY (MIN. COMP. STRENGTH @ TRANSFER OF STRESSING FORCE).

ALL PRESTRESSING STRANDS SHALL MEET THE REQUIREMENTS OF ASTM A416.

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE HIGH STRENGTH CABLES IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

SIZE	TYPE	AREA	ULTIMATE STR.	APPLIED FORCE
5/16" Ø	HIGH STR.	0.217 SQ. IN. PER CABLE	58,590 LBS.	43,940 LBS. PER CABLE

EXP. JT. MAT'L. SHALL MEET THE REQUIREMENTS OF AASHTO SPECIFICATION M153 TYPE I, II, OR III.

JOINT SEALER SHALL BE LOW MODULUS SILICONE SEALANT. SEE SECTION 1028-4 OF THE STANDARD SPECIFICATIONS.


STRUCTURAL STEEL ITEMS SHALL BE OF A GRADE CONFORMING TO EITHER ASTM A36 OR A373, EXCEPT HIGH STRENGTH BOLTS. HIGH STRENGTH BOLTS SHALL BE ASTM A325. ALL STRUCTURAL STEEL SHALL BE GALVANIZED AS PER THE SPECIFICATION.

ALL MATERIAL AND WORKMANSHIP SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES OF THE NC DEPARTMENT OF TRANSPORTATION DATED JULY 2006 AND WITH THE SPECIAL PROVISIONS.


WHEN CORED SLABS ARE CAST, A POSITIVE HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS. THIS SYSTEM SHALL BE DESIGNED TO BE LEFT IN PLACE UNTIL THE CONCRETE HAS REACHED RELEASE STRENGTH AT LEAST THREE WEEKS PRIOR TO CASTING CORED SLABS. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM, IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4".

FOR DEFLECTION TABLE, SEE "PRECAST CONCRETE BARRIER RAIL SECTIONS" SHEET.



TIE LOCATION FOR #8B1




REINFORCING BAR TYPES

BAR DIMENSIONS ARE OUT TO OUT


SHEATH CHART		
SPAN LENGTH	NUMBER OF SHEATHED STRANDS PER EXTERIOR SLAB SECTIONS	NUMBER OF SHEATHED STRANDS PER INTERIOR SLAB SECTIONS
55'	4	4
30'	0	0

BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 4'-0" FROM END OF SLAB




30' SPAN

8 - 5/16" Ø H.S. STRANDS EXTERIOR SLAB SECTIONS




30' SPAN

8 - 5/16" Ø H.S. STRANDS INTERIOR SLAB SECTIONS




SHEAR KEY DETAIL

NOTE: OMIT SHEAR KEY ON OUTSIDE OF EXTERIOR CORED SLAB




SLAB END ELEVATION

THE 2 1/2" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH GROUT, SEE SPECIAL PROVISIONS.



55' SPAN


20 - 5/16" Ø H.S. STRANDS EXTERIOR SLAB SECTIONS



55' SPAN

20 - 5/16" Ø H.S. STRANDS INTERIOR SLAB SECTIONS

□ DENOTES SHEATHED STRAND (SEE SHEATH CHART)




TYPICAL SECTION

NOTE: 4" Ø PVC DRAINS THROUGH THE PRECAST BARRIER RAIL ARE REQUIRED ON LEFT SIDE OF BRIDGE ONLY. NO DECK DRAINS OVER OPEN WATER.

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 PRESTRESSED CORED
 SLAB DETAILS
 30' & 55' SPANS
 30' CLEAR ROADWAY - 60° SKEW


REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09

2/19/2010 3:45:07 PM g:\projects\brunrowan_95\Drawings\NCMA94028.sd.ts.01.dgn



PLAN OF SPAN



PART PLAN - SLAB SECTION

WBS NO. 42818.3.1
ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521


STATE OF NORTH CAROLINA				SHEET NO.	
DEPARTMENT OF TRANSPORTATION				11	
RALEIGH				TOTAL SHEETS	
STANDARD				29	
PRESTRESSED CORED SLAB					
30' SPAN					
30' CLEAR ROADWAY - 60° SKEW					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

DRAWN BY : R. SEALEY DATE : 3/09
 CHECKED BY : M. AVERETTE DATE : 3/09

2/19/2010 2:01:36 PM g:\projects\brm\rowan_95\Drawings\NCMA9402B_sd.csl_01.dgn



PLAN OF SPAN



PART PLAN - SLAB SECTION

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					SHEET NO. 12
STANDARD PRESTRESSED CORED SLAB 55' SPAN					TOTAL SHEETS 29
30' CLEAR ROADWAY - 60° SKEW					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

2/19/2010 2:01:35 PM g:\projects\bm\arowan_95\Drawings\NCMA9402B.sd.cs2.01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09



TYPICAL 5'-0" PRECAST UNIT

NOTE: 4" Ø PVC DRAINS THROUGH THE PRECAST BARRIER RAIL ARE REQUIRED ON LEFT SIDE OF BRIDGE ONLY. NO DECK DRAINS ARE ALLOWED OVER OPEN WATER.

TYPICAL 10'-0" PRECAST UNIT

NOTE: 4" Ø PVC DRAINS THROUGH THE PRECAST BARRIER RAIL ARE REQUIRED ON LEFT SIDE OF BRIDGE ONLY. NO DECK DRAINS ARE ALLOWED OVER OPEN WATER.

NOTES

EACH PRECAST RAIL UNIT SHALL BE CAST WITH CLASS AA CONCRETE.

RAIL TO BE FLUSH WITH CORED SLAB UNITS AT EACH END OF SPAN.

GROUT SHALL BE 1" ABOVE DRAINS BETWEEN RAIL SECTIONS EXCEPT AT BENTS WHERE LOW MODULUS SILICONE SHALL BE SUBSTITUTED IN PLACE OF GROUT.

EACH PRECAST RAIL UNIT SHALL BE SUPPLIED WITH LIFTING DEVICE(S). NO CABLES ARE TO BE WRAPPED AROUND THE RAIL UNITS FOR LIFTING.

THE EXPANSION JOINT SEALER SHALL BE LOW MODULUS SILICONE SEALANT. SEE SECTION 1028-4 OF THE STANDARD SPECIFICATIONS.

CONCRETE CHAMFERS: UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE ON PLANS.

BILL OF MATERIAL FOR ONE 5'-0" RAIL SECTION

BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
B3	#5	1	2'-8"	14
B4	#5	2	4'-11"	26
B5	#5	STR.	4'-7"	24


REINFORCING STEEL LBS. = 64
CLASS AA CONCRETE CU. YDS. = 0.5

BILL OF MATERIAL FOR ONE 10'-0" RAIL SECTION



BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
B3	#5	1	2'-8"	25
B4	#5	2	4'-11"	46
B6	#5	STR.	9'-7"	50

REINFORCING STEEL LBS. = 121
CLASS AA CONCRETE CU. YDS. = 1.0

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT





INTERIOR SLAB UNIT	30'	55'
CAMBER (SLAB UNIT ALONE IN PLACE)	5/16" (UP)	2 1/16" (UP)
DEFLECTION (SUPERIMPOSED DEAD LOAD)	1/16" (DOWN)	3/8" (DOWN)
FINAL DEFLECTION	1/4" (UP)	2 5/16" (UP)





* INCLUDES FUTURE WEARING SURFACE

EXTERIOR SLAB UNIT	30'	55'
CAMBER (SLAB UNIT ALONE IN PLACE)	1/4" (UP)	2 3/8" (UP)
DEFLECTION (SUPERIMPOSED DEAD LOAD)	1/16" (DOWN)	3/8" (DOWN)
FINAL DEFLECTION	3/16" (UP)	2" (UP)

* INCLUDES FUTURE WEARING SURFACE



DETAIL A
GROUTED RECESS AT END OF POST-TENSIONED STRAND CORED SLAB



SECTION AT END BENT

SECTION AT BENT

WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-
REPLACES BRIDGE NO. 95



PLANS PREPARED BY:
SIMPSON & ASSOCIATES
5520 Dillard Drive
Suite 120
Cary, NC 27518
(919) 852-0468
www.simpsonengr.com
LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
PRECAST CONCRETE
BARRIER RAIL SECTIONS
30' & 55' SPANS
30' CLEAR ROADWAY - 60° SKEW

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

13
10%
29

2/19/2010 2:01:34 PM g:\projects\rowan\95\Drawings\NCMA9402B_sd.br_01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
CHECKED BY: M. AVERETTE DATE: 3/09

NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 4 - 5/8" Ø BOLTS WITH NUTS AND WASHERS, RUBRAIL, AND ADHESIVELY ANCHORED BOLTS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M11.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 5/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)

THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.


AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.

THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR GUARDRAIL ANCHOR UNIT TYPE B-77.


THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.

THE C6 X 8.2 RUBRAIL IS TO BE ADHESIVELY ANCHORED TO THE RAIL USING THREE 5/8" Ø X 6" BOLTS WITH WASHERS. SEE ROADWAY STANDARD 862.03 FOR DETAILS AND LOCATION OF THE RUBRAIL.

FOR ADDITIONAL GUARDRAIL INFORMATION, SEE "GUARDRAIL ANCHOR UNIT" SHEET.




PLAN




ELEVATION

FOR LOCATION OF RUBRAIL, SEE ROADWAY STD. 862.03



SECTION E-E


GUARDRAIL ANCHOR ASSEMBLY DETAILS



PLAN

LOCATION OF ANCHORS FOR GUARDRAIL

END BENT #1 SHOWN, END BENT #2 SIMILAR.



SKETCH SHOWING POINTS OF ATTACHMENTS

* DENOTES GUARDRAIL ANCHOR ASSEMBLY

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95



PLANS PREPARED BY:
 SIMPSON ENGINEERS & ASSOCIATES
 5520 Dillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

GUARDRAIL ANCHORAGE FOR BARRIER RAIL


30' CLEAR ROADWAY - 60° SKEW

REVISIONS				SHEET NO.
NO.	BY	DATE	NO.	DATE
1			3	
2			4	

TOTAL SHEETS: 29


2/19/2010 2:01:34 PM G:\Projects\bmur\owan_95\Drawings\NCMA9402B.sd_gr_01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




PLAN OF APPROACH SLAB #1

NOTE TO CONTRACTOR: THE LAYOUT OF THE APPROACH SLAB IS ALONG THE EXTENDED TANGENT OF THE CURVE.




PLAN OF APPROACH SLAB #2

NOTE TO CONTRACTOR: THE LAYOUT OF THE APPROACH SLAB IS ALONG THE EXTENDED TANGENT OF THE CURVE.




SECTION N-N



END OF CURB WITHOUT SHOULDER BERM GUTTER

CURB DETAILS

WBS NO. 42818.3.1
ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 1 OF 2



PLANS PREPARED BY:
SIMPSON ENGINEERS ASSOCIATES
S&EA
 5520 Dilard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA		DEPARTMENT OF TRANSPORTATION		RALEIGH	
APPROACH SLAB					
30' CLEAR ROADWAY - 60° SKEW					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					SHEET NO. 15 TOTAL SHEETS 29

2/19/2010 2:01:33 PM c:\projects\mum\rowan_95\Drawings\NCMA9402B_sd.as1.01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09

BILL OF MATERIAL				
FOR ONE APPROACH SLAB (2 REQ'D)				
BAR NO.	NO.	TYPE	LENGTH	WEIGHT
*A1	23	STR	35'-9"	858
A2	18	STR	18'-10"	226
*B1	63	STR	11'-2"	1057
B2	63	STR	11'-8"	1104
REINFORCING STEEL				1,330
*EPOXY COATED				
REINFORCING STEEL				1,915
CLASS "A" CONCRETE BREAKDOWN				
TOTAL				14.0 Cu. Yds.

NOTES

THE COST OF THE CURB ON THE APPROACH SLAB SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE BID FOR BRIDGE APPROACH SLABS.

TEMPORARY DRAINAGE AND TEMPORARY BERM AND SLOPE DRAINS WILL BE PAID FOR UNDER THE LUMP SUM PRICE FOR BRIDGE APPROACH SLAB.

FOR BRIDGE APPROACH FILL INCLUDING FABRIC, 4"Ø DRAINAGE PIPE, AND #78M STONE BACKFILL, SEE BRIDGE APPROACH FILLS, SHEET 3.

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

FABRIC SHALL BE TYPE I ENGINEERING FABRIC IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.

*78M STONE BACKFILL (CLASS V SELECT MATERIAL) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

*78M STONE BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB.

FOR THE 4"Ø DRAINAGE PIPE OUTLET(S), SEE BRIDGE APPROACH FILLS, SHEET 3.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE 6" COMP. A.B.C. SHALL BE FLUSH WITH THE ROADWAY END OF THE APPROACH SLAB AND SHALL EXTEND 1'-0" OUTSIDE OF EACH EDGE OF THE APPROACH SLAB.


THE CONTRACTOR MAY USE 4" TYPE B-25.0B ASPHALT CONCRETE BASE COURSE IN LIEU OF 6" COMP. A.B.C. IF THIS OPTION IS USED, THE BASE COURSE SHALL BE FLUSH WITH THE ROADWAY END OF THE APPROACH SLAB, AND THE WIDTH SHALL BE THE SAME AS THAT OF THE APPROACH SLAB.

THE CONTRACTOR MAY USE 5" CLASS "A" CONCRETE BASE IN LIEU OF 6" COMP. A.B.C. IF THIS OPTION IS USED, THE CONCRETE BASE SHALL BE FLUSH WITH THE ROADWAY END OF THE APPROACH SLAB, AND THE WIDTH SHALL BE THE SAME AS THAT OF THE APPROACH SLAB. THE CONCRETE SHALL BE FINISHED TO A SMOOTH SURFACE AND A LAYER OF 30 LB ROOFING FELT SHALL BE PLACED BETWEEN THE CONCRETE BASE AND THE APPROACH SLAB TO PREVENT BOND. THE APPROACH SLAB SHALL NOT BE CAST UNTIL THE CONCRETE BASE HAS REACHED AN AGE OF THREE CURING DAYS.

FOR JOINT DETAILS, SEE "PRESTRESSED CONCRETE CORED SLAB UNIT" SHEETS.

THE JOINT AT THE END BENT SHALL BE GROUTED AS SOON AS PRACTICAL AFTER THE CONSTRUCTION OF THE APPROACH SLABS.

APPROACH SLAB GROOVING IS NOT REQUIRED.



SECTION THRU SLAB

WBS NO. 42818.3.1
ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 2 OF 2



PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Ollard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

APPROACH SLAB


30' CLEAR ROADWAY - 60° SKEW

REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

TOTAL SHEETS: 29

2/19/2010 3:45:06 PM g:\projects\dmu\rowan_95\Drawings\NCMA9402B_sd.as2_01.dgn


DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09



NOTES
 STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR #6 DI DOWELS.

TOP OF \bar{C} PILE ELEVATIONS	
PILE NO.	ELEVATION
P1	661.578
P2	661.683
P3	661.788
P4	661.893
P5	661.999
P6	662.104
P7	662.209

PLAN



ELEVATION




WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 1 OF 3


STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH				SUBSTRUCTURE		END BENT #1		30' CLEAR ROADWAY - 60° SKEW	
PLANS PREPARED BY: SIMPSON ENGINEERS & ASSOCIATES 5520 Dilford Drive Suite 120 Cary, NC 27518 (919) 852-0468 (919) 852-0598 (Fax) www.simpsonengr.com LICENSURE NO. C-2521									
REVISIONS									
NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.		TOTAL SHEETS	
1			3			17		29	
2			4						

2/19/2010 2:01:31 PM g:\projects\brm\rowan_95\Drawings\NCMA9402B.ed.ebl.a.01.dgn


DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




(W1) PLAN OF LEFT WING




(W2) PLAN OF RIGHT WING




(W1) ELEVATION OF LEFT WING



(W2) ELEVATION OF RIGHT WING




SECTION X-X



SECTION Y-Y

WBS NO. 42818.3.1
ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 2 OF 3




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dillard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 END BENT #1
 30' CLEAR ROADWAY - 60° SKEW

REVISIONS				SHEET NO.	
NO.	BY:	DATE:	NO.	DATE:	TOTAL SHEETS
1			3		18
2			4		29


2/19/2010 2:01:30 PM g:\projects\brm\rowan_95\Drawings\NCMA9402B_sd_eblb_01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




PILE SPLICE DETAILS


* POSITION OF PILE DURING WELDING.



LATERAL GUIDE DETAILS



SECTION A-A




ALL BAR DIMENSIONS ARE OUT TO OUT

BILL OF MATERIAL					
END BENT #1					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	9	1	47'-0"	1278
B2	2	5	STR	44'-6"	93
B3	8	4	STR	23'-6"	126
B4	11	4	STR	2'-5"	18
D1	22	6	STR	1'-6"	50
H1	5	4	5	6'-1"	20
H2	5	4	5	6'-5"	21
H3	5	4	4	5'-4"	18
H4	5	4	4	5'-0"	17
S1	44	4	2	7'-5"	218
S2	44	4	3	3'-2"	93
S3	14	4	6	6'-6"	61
S4	4	4	7	8'-6"	23
S5	4	4	8	4'-7"	12
V1	42	4	STR	4'-2"	117

TOTAL REINFORCING STEEL	2165 Lbs.
CLASS "A" CONCRETE BREAKDOWN	
POUR #1	12.4 Cu. Yds.
POUR #2	1.4 Cu. Yds.
TOTAL	13.8 Cu. Yds.
HP 12 X 53 STEEL PILES	
7 PILES REQUIRED - LIN. FEET	70

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 3 OF 3




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dilford Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
SUBSTRUCTURE					
END BENT #1					
30' CLEAR ROADWAY - 60° SKEW					
REVISIONS					SHEET NO.
NO.	BY	DATE	NO.	BY	DATE
1			3		
2			4		
					TOTAL SHEETS
					19
					29


2/19/2010 2:01:29 PM g:\projects\brm\rowan 95\Drawings\NCMA3402B.sd.eb1c.01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




PLAN OF DRILLED PIERS

NOTE: REINFORCING STEEL AND DIMENSIONS ARE TYPICAL FOR ALL DRILLED PIERS.




SECTION A-A



SECTION X-X

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT

* THE SP-1 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR.


BILL OF MATERIAL

FOR BENT #1


BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	6	10		45'-3"	1168
B2	6	5	STR	42'-5"	265
B3	6	10	STR	42'-5"	1095
B4	2	4	STR	3'-3"	4
B5	2	4	STR	3'-9"	5
D1	44	6	STR	1'-6"	99
M1	42	10	2	20'-5"	3690
S1	36	5	3	11'-6"	432
S2	2	4	4	3'-7"	5
S3	2	4	4	4'-2"	6
S4	2	4	4	4'-9"	6
S5	2	4	4	5'-4"	7
U1	8	4	4	6'-2"	33
U2	8	4	4	6'-6"	35
SP-1	3	**	5	432'-9"	1354

REINFORCING STEEL 6850 Lbs.
 SPIRAL REINFORCING STEEL 1354 Lbs.
 CLASS "A" CONCRETE BREAKDOWN POUR #2 (CAP) 23.4 Cu. Yds.

DRILLED PIER QUANTITIES
 DRILLED PIER CONCRETE POUR #1 (DRILLED PIER) 11.2 Cu. Yds.
 3'-0" Ø DRILLED PIERS IN SOIL 18.9 Lin. Ft.
 3'-0" Ø DRILLED PIERS NOT IN SOIL 24.0 Lin. Ft.
 3'-0" Ø PERMANENT STEEL CASING 18.9 Lin. Ft.



PLAN



ELEVATION

LATERAL GUIDE DETAILS

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 2 OF 2



PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dilford Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE

BENT #1

30' CLEAR ROADWAY - 60° SKEW


REVISIONS				SHEET NO.	
NO.	BY	DATE	NO.	BY	DATE
1			3		
2			4		

TOTAL SHEETS 29

2/19/2010 2:01:28 PM g:\projects\bm\rowan_95\Drawings\NEMA9402B.sd.bib.01.dgn


DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09

NOTES
 STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR #6 D1 DOWELS.



PLAN

TOP OF ϕ PILE ELEVATIONS	
PILE NO.	ELEVATION
P1	661.280
P2	661.396
P3	661.513
P4	661.630
P5	661.748
P6	661.864
P7	661.981



ELEVATION

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 1 OF 3




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Ollard Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 END BENT #2
 30' CLEAR ROADWAY - 60° SKEW


REVISIONS						SHEET NO. 22
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 29
2			4			

2/19/2010 2:01:28 PM G:\projects\bmurrowan_95\Drawings\NCMA9402B_sd_ab2a_01.dgn


DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




W1 PLAN OF LEFT WING




W2 PLAN OF RIGHT WING




W1 ELEVATION OF LEFT WING



W2 ELEVATION OF RIGHT WING



SECTION X-X




SECTION Y-Y

WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 2 OF 3

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 END BENT #2
 30' CLEAR ROADWAY - 60° SKEW






PLANS PREPARED BY:
SIMPSON
 ENGINEERS
 & ASSOCIATES
 5520 Dilford Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

TOTAL SHEETS	23
	29

2/19/2010 2:01:27 PM g:\p\projects\blm\1-0\an 95\Drawings\NCMA\9402B.sd,eb2b.01.dgn


DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09




ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL					
END BENT #2					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	9	1	47'-2"	1283
B2	2	5	STR	44'-8"	93
B3	8	4	STR	23'-7"	126
B4	11	4	STR	2'-5"	18
D1	22	6	STR	1'-6"	50
H1	5	4	5	6'-1"	20
H2	5	4	5	6'-5"	21
H3	5	4	4	5'-4"	18
H4	5	4	4	5'-0"	17
S1	44	4	2	7'-5"	218
S2	44	4	3	3'-2"	93
S3	14	4	6	6'-6"	61
S4	4	4	7	8'-6"	23
S5	4	4	8	4'-7"	12
V1	42	4	STR	4'-2"	117

TOTAL REINFORCING STEEL	2170 Lbs.
CLASS "A" CONCRETE BREAKDOWN	
POUR #1	12.4 Cu. Yds.
POUR #2	1.4 Cu. Yds.
TOTAL	13.8 Cu. Yds.
HP 12 X 53 STEEL PILES	
7 PILES REQUIRED - LIN. FEET	90



WBS NO. 42818.3.1
 ROWAN COUNTY
 STATION: 13+18.50 -L-
 REPLACES BRIDGE NO. 95 SHEET 3 OF 3




PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5520 Dilford Drive
 Suite 120
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsoneng.com
 LICENSURE NO. C-2521

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH						
SUBSTRUCTURE						
END BENT #2						
30' CLEAR ROADWAY - 60° SKEW						
REVISIONS						
NO.	BY	DATE	NO.	BY	DATE	SHEET NO.
1			3			24
2			4			TOTAL SHEETS 29

DRAWN BY: R. SEALEY DATE: 3/09
 CHECKED BY: M. AVERETTE DATE: 3/09

2/19/2010 2:01:26 PM g:\projects\brm\rowan_95\Drawings\NCM45402B_sd_ep2c.D1.dgn

EROSION CONTROL PLAN



Std. #	Description	Symbol
1605.01	Temporary Silt Fence	
1606.01	Special Sediment Control Fence	
1630.05	Temporary Diversion	
1630.06	Special Stilling Basin	
	Temporary Rock Silt Check Type-A with Matting and polyacrylamide (PAM)	
	Temporary Rock Silt Check Type-B	
	Wattle	
1634.02	Temporary Rock Sediment Dam Type-B	

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

2006 STANDARD SPECIFICATIONS

WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-
REPLACES BRIDGE NO. 95 SHEET 1 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

EROSION CONTROL PLAN

30' CLEAR ROADWAY - 60° SKEW

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	25
1			3			TOTAL SHEETS
2			4			29

2/19/2010 2:01:26 PM g:\projects\bm\rowan 95\Drawings\NCMA9402B.sd.ec1.01.dgn

DRAWN BY : R. SEALEY DATE : 3/09
CHECKED BY : M. AVERETTE DATE : 3/09

EROSION CONTROL PLAN


TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, NC.

2006 STANDARD SPECIFICATIONS






NOTES

USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.

INITIALLY APPLY 3.5 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



NOT TO SCALE

WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 2 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

EROSION CONTROL PLAN

30' CLEAR ROADWAY - 60° SKEW

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	26
1			3			TOTAL SHEETS
2			4			29

2/19/2010 2:01:25 PM c:\projects\mrowan\95\Drawings\NCMA9402B_sd.ec2.01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
CHECKED BY: M. AVERETTE DATE: 3/09

EROSION CONTROL PLAN


TEMPORARY ROCK SILT CHECK TYPE 'B' DETAIL

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALPH, N.C.



2006 STANDARD SPECIFICATIONS



NOTES:

USE CLASS 'B' EROSION CONTROL STONE FOR STRUCTURAL STONE.

THE ENGINEER MAY DIRECT THE OPTION OF CLASS "A" STONE FOR SITES HAVING LESS THAN ONE (1) ACRE DRAINAGE AREA AND A DITCH GRADE LESS THAN 3%.



WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 3 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

EROSION CONTROL PLAN

30' CLEAR ROADWAY - 60° SKEW

REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					TOTAL SHEETS
					27
					29

2/19/2010 2:01:24 PM g:\projects\brm\rowan 95\Drawings\NCMA9402B.sd.ec3.01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
CHECKED BY: M. AVERETTE DATE: 3/09

EROSION CONTROL PLAN

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALPHIGH, N.C.

2006 STANDARD SPECIFICATIONS

WATTLE WITH POLYACRYLAMIDE DETAIL

NOTES:

USE MINIMUM 12 IN. DIAMETER EXCELSIOR WATTLE.

USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. CROSS SECTION.

ONLY INSTALL WATTLE(S) TO A HEIGHT IN DITCH SO FLOW WILL NOT WASH AROUND WATTLE AND SCOUR DITCH SLOPES AND AS DIRECTED.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.






PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.

INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.

INSTALL MATTING IN ACCORDANCE WITH SECTION 1631 OF THE STANDARD SPECIFICATIONS.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH WATTLE.

INITIALLY APPLY 3.5 OUNCES OF ANIONIC OR NEUTRALLY CHARGED POLYACRYLAMIDE (PAM) OVER WATTLE WHERE WATER WILL FLOW AND AFTER EVERY RAINFALL EVENT THAT IS EQUAL TO OR EXCEEDS 0.50 IN.



WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 4 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

EROSION CONTROL PLAN

30' CLEAR ROADWAY - 60° SKEW


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	28
1			3			TOTAL SHEETS
2			4			29

2/19/2010 2:01:24 PM g:\projects\bmurrowen_95\Drawings\NCMA9402B_sd.ec4_01.dgn

DRAWN BY: R. SEALEY DATE: 3/09
CHECKED BY: M. AVERETTE DATE: 3/09

EROSION CONTROL PLAN

COIR FIBER BAFFLE DETAIL



NOTES:

1. INSTALL THREE(3) COIR FIBER BAFFLES IN SILT BASINS AND SEDIMENT DAMS AT DRAINAGE OUTLETS WITH A SPACING OF 1/4 THE BASIN LENGTH.
2. TWO(2) COIR FIBER BAFFLES CAN BE INSTALLED IN SILT BASINS AND DAMS LESS THAN 20 FT. IN LENGTH WITH A SPACING OF 1/3 THE BASIN LENGTH.
3. TOP HEIGHT OF COIR FIBER BAFFLES SHALL NOT BE BELOW BASE OF EMERGENCY SPILLWAY ELEVATION.

BAFFLE MATERIAL SHALL BE SECURED TO THE BOTTOM AND SIDES OF BASIN USING 12" LANDSCAPE STAPLES

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

ROADSIDE ENVIRONMENTAL UNIT
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALIGH, N.C.

2006 STANDARD SPECIFICATIONS

WBS NO. 42818.3.1
ROWAN COUNTY
STATION: 13+18.50 -L-

REPLACES BRIDGE NO. 95 SHEET 5 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALIGH

EROSION CONTROL
PLAN

30' CLEAR ROADWAY - 60° SKEW

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	29
1			3			TOTAL SHEETS
2			4			29

DRAWN BY : R. SEALEY DATE : 3/09
CHECKED BY : M. AVERETTE DATE : 3/09

2/19/2010 2:01:23 PM g:\projects\bmurrow\95\Drawings\NCMA9402B_sd.ec5_01.dgn