



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR


J. ERIC BOYETTE
SECRETARY

**IMPORTANT INFORMATION
PLEASE READ**

TO PREQUALIFIED BIDDERS AND PURCHASE ORDER PRIMES:

The requirements for bidding on NCDOT construction projects are changing. The current requirement to purchase plans or a proposal to be eligible to bid will be replaced by a requirement to register for the *Interested Parties List*. This change will be effective for any Central or Division letting June 1, 2022 and later.

For any letting June 1, 2022 and later:



Contractors bidding on NCDOT contracts must sign up for the *Interested Parties List* for each project they intend to submit bids on. As part of this new requirement, Contractors must sign up for the *Interested Parties List* no later than one business day prior to the Letting Date.

The purchase of plans or proposals will no longer be required to bid on NCDOT Central Let projects and will be replaced by the new requirement above to sign up for the *Interested Parties List*. Plans will continue to be available for purchase, however anyone who purchases plans shall still sign up for the *Interested Parties List* to be eligible to bid.

A one-page quick guide follows this letter and the quick guide a more detailed walkthrough on signing up for the *Interested Parties List* can be found on the Central and Division Letting Resources pages at the links below:


<https://connect.ncdot.gov/letting/Pages/Central.aspx>

<https://connect.ncdot.gov/letting/Pages/Division-Letting-Resources.aspx>

The links and functionality described in the guides will be available on our website in the near future. For more information or assistance with this new process please submit any questions to InterestedPartiesHelp@ncdot.gov.

For additional assistance with general bidding related questions please email AWPhelp@ncdot.gov.

Ronald E. Davenport, Jr., PE
State Contract Officer

DocuSigned by:

F81B6038A47A442...



Interested Parties List

To **register to bid on an upcoming NCDOT construction contract**, or to register in general to be notified about updates for selected upcoming contracts to be let, add your firm to the Interested Parties list for each contract in which you are interested. Interested parties will be informed by mail whenever there are addenda or other changes to the planned letting.

You are no longer required to be a Plan Holder to bid for any lettings occurring June 1, 2022, or later.

Interested parties and authorized bidders MUST sign up at least one full business day prior to the let date.

To Register:

1. Navigate to the details page for the selected contract. Press **Interested Parties for this letting** or go directly to the overall [Interested Parties list](#)
2. Press **Add Firm** and find your firm using the Search box. Select your firm name and press **Next**
3. Complete the contact information for the person to be notified of changes and press **Next**
4. Review the list of upcoming Central and Division contracts and select the upcoming contract(s) in which you are interested and press **Next**.
There is no need to register again for contracts for which you have previously registered.
5. The confirmation page will summarize your entered information. Press **Submit**.
6. A confirmation email will be sent to the provided address. Within one hour, the firm will appear on the publicly viewable Interested Parties list for each of the specified contracts. Allow five business days for NCDOT staff to upload your firm as an authorized bidder in Bid Express.

Email InterestedPartiesHelp@ncdot.gov if you have any problems registering.



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

NOTICE OF DBE OPPORTUNITIES

Upcoming Opportunities for DBE Firms to Participate on NCDOT Projects

As part of the North Carolina Department of Transportation's continuing commitment to promote Disadvantaged/Minority/Women Business Enterprise (D/M/WBE) participation, the Division of Highways Chief Engineer's Office would like to remind you of the broad range of construction, maintenance and operational opportunities available within NCDOT. One of these opportunities is the monthly advertisement of Central Let projects with letting typically held on the third Tuesday of each month. NCDOT advertises the Central Lettings at the location below with a separate letting page for each month. If your firm is eligible to bid (i.e. prequalified as a Bidder), you can download and print the bid related items from the upcoming monthly letting pages here:

[Central Highway Lettings](#)


Additionally, if you are interested in providing subcontractor work for any of the listed projects, we strongly encourage you to solicit each of the contractors bidding on the projects to see if they are interested in receiving a quote. Potential bidders or subcontractors may sign themselves up and provide contact information using the Interested Parties List button on each of the monthly letting pages. A screenshot of the IPL button is shown below for reference:

Interested Parties for
this Letting

I would like to personally thank you for your time in considering this opportunity with the North Carolina Department of Transportation.

Sincerely,

DocuSigned by:



Lamar Sylvester, PE

Chief Engineer

Division of Highways

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
OFFICE OF THE CHIEF ENGINEER
MAIL SERVICE CENTER 1536
RALEIGH NC 27699-1536

TELEPHONE: 919-707-2500
FAX: 919-733-9428
Customer Service: 1-877-368-4968

WEBSITE: WWW.NCDOT.GOV

LOCATION:
1 SOUTH WILMINGTON STREET
RALEIGH NC 27601

Notice Regarding Upcoming Buy America Changes

On January 14, 2025, the Federal Highway Administration (FHWA) terminated its General Waiver for Manufactured Products and established specific Buy America requirements for their use on Federal-aid highway projects.

This means that as of the following dates, materials defined as manufactured products permanently incorporated into Federal-aid highway projects will have to be manufactured in the United States.

Key Implementation Dates

- Phase 1: contracts obligated on or after **October 1, 2025**
 - Final assembly of all manufactured products permanently incorporated into Federal-aid highway projects must occur in the United States.
 - Phase 2: contracts obligated on or after **October 1, 2026**
 - Final assembly of all manufactured products permanently incorporated into Federal-aid highway projects must occur in the United States.
- AND
- The cost of U.S.-produced components in manufactured products must be greater than 55% of the total cost of all components.

Definition of Manufactured Products

Manufactured Products are defined as articles, materials, or supplies that:

- Have been processed into a specific form and shape, or
- Have been combined with other articles or supplies to create a product with different properties than the individual articles, materials, or supplies.

This places greater emphasis on using domestically produced materials on these projects and is consistent with the Build America, Buy America Act (BABA) under the Bipartisan Infrastructure Law (BIL).

**STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
INVITATION TO BID**

ELECTRONIC BIDS (UNLESS OTHERWISE SPECIFIED IN THE PROJECT SPECIAL PROVISIONS) FOR THE CONSTRUCTION OF THE FOLLOWING PROJECTS WILL BE PUBLICLY READ IN THE CONTRACT STANDARDS AND DEVELOPMENT UNIT RIVERWOOD CONFERENCE ROOM, LOCATED IN BUILDING B AT 1020 BIRCH RIDGE DRIVE, RALEIGH, N.C. OR VIA THE WEBCAST AT **2:00 PM** ON JANUARY 20, 2026. NO ELECTRONIC BIDS WILL BE RECEIVED AFTER 2:00 PM.

1. THE BIDDER SHALL SELF REGISTER AT THE FOLLOWING WEBSITE FOR EACH PROJECT FOR WHICH THEY INTEND TO SUBMIT A BID IN RESPONSE TO THIS INVITATION TO BID

<https://connect.ncdot.gov/letting/pages/Interested-Parties.aspx>

2. A BID BOND OR BID DEPOSIT IN THE AMOUNT OF 5% OF THE TOTAL AMOUNT BID WILL BE REQUIRED. THE BIDDER SHALL SUBMIT AN ELECTRONIC BID BOND WITH EACH ELECTRONIC BID SUBMITTAL UNLESS THEY ELECT TO FURNISH A BID DEPOSIT.

3. UPON RECEIPT OF AWARD LETTER, THE SUCCESSFUL BIDDER SHALL FURNISH A PROPERLY EXECUTED EXECUTION OF CONTRACT, NON-COLLUSION, DEBARMENT AND GIFT BAN CERTIFICATION, EXECUTED PAYMENT AND PERFORMANCE BONDS, AND OPTIONAL BID ITEMS ELIGIBLE FOR STEEL PRICE ADJUSTMENT FORM (SPA-1) FOR EACH CONTRACT. CERTIFICATION FORMS AND BOND FORMS ARE AVAILABLE AS PART OF THE CONTRACT EXECUTION FORMS AT THE FOLLOWING WEBSITE <https://connect.ncdot.gov/letting/Pages/Central-Letting-Forms.aspx>. BID ITEMS ELIGIBLE FOR STEEL PRICE ADJUSTMENT FORM (SPA-1) IS AVAILABLE AT THE FOLLOWING WEBSITE <https://connect.ncdot.gov/letting/Pages/Central-Letting-Resources.aspx>.

ALL QUESTIONS RELATED TO PROJECTS DURING THE ADVERTISEMENT PERIOD SHALL BE EMAILED TO THE STATE CONTRACT OFFICER AT ContractOfficer@ncdot.gov.

THE MINIMUM WAGE FOR LABOR WILL BE SHOWN IN THE PROPOSAL FORM FOR FEDERAL AID PROJECTS.

CONTRACTOR'S LICENSE: A GENERAL CONTRACTOR'S LICENSE IS REQUIRED IN ORDER TO SUBMIT A BID ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000.00 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. ON FEDERAL PROJECTS, THE APPROPRIATE CONTRACTOR'S LICENSE SHALL BE OBTAINED WITHIN 60 DAYS OF BID OPENING. FOR ADDITIONAL INFORMATION OR TO MAKE APPLICATION FOR A LICENSE, VISIT THE CONTRATOR LICENSING BOARD WEBSITE AT <https://www.nclbgc.org> OR EMAIL licensing@nclbgc.org.

PREQUALIFYING TO BID: ALL PROSPECTIVE BIDDERS SHALL BE PREQUALIFIED WITH THE DEPARTMENT OF TRANSPORTATION PRIOR TO SUBMITTING A BID. CONTRACTORS WHO ARE NOT PREQUALIFIED MAY OBTAIN INFORMATION AND FORMS FOR PREQUALIFYING FROM THE PREQUALIFICATION SECTION OF THE CONTRACT STANDARDS AND DEVELOPMENT UNIT AT <https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>. ALL REQUIRED PREQUALIFICATION STATEMENTS AND DOCUMENTS SHALL BE FILED WITH THE CONTRACTUAL SERVICES MANAGEMENT SECTION AT LEAST FOUR WEEKS PRIOR TO THE DATE OF OPENING BIDS.

THE DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY ENSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS INVITATION TO BID, MINORITY BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, OR NATIONAL ORIGIN IN COMPENSATION TO THIS AWARD.

PROPOSAL FORMS AT **\$25.00** EACH, PLANS (SMALL SIZE) AT **\$40.00** PER SET, PLANS (LARGE SIZE) AT **\$100.00** PER SET, AND CROSS-SECTIONS AT **\$40.00** PER SET, PLUS SALES TAX FOR N.C. RESIDENTS, MAY BE OBTAINED BY TELEPHONING (919-707-6925), FAXING (919-250-4127), OR VISITING THE WEBSITE AT: <https://connect.ncdot.gov/letting/Pages/Order-Plans.aspx>. THESE CHARGES ARE NOT DEPOSITS AND WILL NOT BE REFUNDED. ALL ORDERS FOR PROPOSAL FORMS, PLANS AND CROSS-SECTIONS DELIVERED IN NORTH CAROLINA ARE SUBJECT TO 7.25% SALES TAX. ORDERS MAILED TO OUT OF STATE CONTRACTORS ARE NOT SUBJECT TO SALES TAX. MAKE ALL CHECKS PAYABLE TO THE **"N.C. DEPARTMENT OF TRANSPORTATION"**.

THE RIGHT IS RESERVED TO REJECT ANY OR ALL BIDS.

**TODAY'S DATE IS DECEMBER 23, 2025.
BY ORDER OF THE DEPARTMENT OF TRANSPORTATION
(THE WORK WILL CONSIST APPROXIMATELY AS SHOWN ON THE FOLLOWING SHEETS)**

REVIEW OF PLANS AND PROPOSALS IN DIVISION OFFICE

IN ORDER TO FACILITATE AND ENCOURAGE THE INVOLVEMENT OF MINORITY BUSINESS ENTERPRISES IN THE HIGHWAY CONSTRUCTION PROCESS, IT IS THE POLICY OF THE DEPARTMENT OF TRANSPORTATION, DIVISION OF HIGHWAYS, THAT A SET OF PLANS AND PROPOSAL FOR EACH PROJECT TO BE LET WILL BE MAINTAINED FOR REVIEW BY ANY CONTRACTOR INTERESTED IN BIDDING UPON OR QUOTING WORK IN AN ADVERTISED PROJECT.

THE PROPOSALS AND PLANS WILL BE AVAILABLE FOR REVIEW BEGINNING TWO WEEKS PRIOR TO THE DATE OF BID OPENING IN THE DIVISION OFFICE WHICH WILL ADMINISTER THE CONTRACT. THE DEPARTMENT WILL, UPON REQUEST, MAKE AVAILABLE FROM ITS STAFF A PERSON TO EXPLAIN THE PROPOSED PROJECT AND TO ANSWER GENERAL QUESTIONS RELATING TO THE PROJECT. THE PLANS AND PROPOSALS CAN BE REVIEWED ANY TIME MONDAY THRU FRIDAY, EXCLUDING HOLIDAYS, BETWEEN THE HOURS OF 8:00 A.M. AND 4:30 P.M. IN THE DIVISION OFFICE. IN ORDER TO HAVE A MEMBER OF THE STAFF EXPLAIN THE PROJECT AND/OR ANSWER GENERAL QUESTIONS PERTAINING TO THE PROJECT, PRIOR APPOINTMENTS MUST BE MADE BY CALLING THE APPROPRIATE DIVISION OFFICE.

FOLLOWING ARE THE LOCATIONS AND TELEPHONE NUMBERS OF THE OFFICES IN WHICH THE PLANS AND PROPOSALS WILL BE MADE AVAILABLE, REFERENCE SHOULD BE MADE TO THE SHEETS CONTAINING THE INDIVIDUAL PROJECT QUANTITIES TO DETERMINE WHICH DIVISION OFFICE WILL ADMINISTER THE CONTRACT.

DIV NO.	DIVISION ENGINEER	TOWN	TELEPHONE
001	C. Win Bridgers, Jr., PE	EDENTON	(252) 482-1850
002	Mary Beth Houston	NEW BERN	(252) 514-4716
003	Trevor Carroll	CASTLE HAYNE	(910) 341-2000
004	W. Matthew Clarke	WILSON	(252) 237-6164
005	Rebecca Gallas	DURHAM	(919) 220-4600
006	Wallace Jernigan, PE	FAYETTEVILLE	(910) 364-0600
007	Wright Archer, III, PE	GREENSBORO	(336) 487-0000
008	Reuben Blakley, PE	CARTHAGE	(910) 773-8000
009	John Rhyne	WINSTON-SALEM	(336) 747-7800
010	Felix Obregon	ALBEMARLE	(704) 983-4400
011	Michael Poe, PE	NORTH WILKESBORO	(336) 903-9101
012	Mark Stafford, PE	SHELBY	(704) 480-5400
013	Timothy Anderson, PE	ASHEVILLE	(828) 250-3000
014	Wesley Grindstaff, PE	SYLVA	(828) 586-2141

===== SUMMARY OF PROPOSALS =====

Bid Letting Number: L260120

RPN Contract Id	WBS	County	Length	Job Type
001	C205129 51815.3.1	PAMLICO	0.057 MI	GRADING, DRAINAGE, PAVING AND STRUCTURE.
002	C204814 38608.3.1	WAYNE	0.607 MI	GRADING, DRAINAGE, PAVING, SIGNALS, AND STRUCTURES.
003	C205162 2026CPT.05.06.10921.1, ETC.	WAKE	22.839 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
004	C205036 44367.3.1	ROBESON	1.304 MI	GRADING, DRAINAGE, PAVING, SIGNALS, AND CULVERTS.
005	C205128 51603.3.1	ROCKINGHAM	0.104 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURE.
006	C205163 2026CPT.08.04.10531, ETC.	LEE	20.028 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
007	C205161 2026CPT.08.06.10191, ETC.	CHATHAM	41.276 MI	MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.
008	C205117 46891.3.1	CABARRUS	0.861 MI	GRADING, DRAINAGE, PAVING, AND SIGNALS.
009	C205132 BP12.R002.3	CLEVELAND	0.275 MI	GRADING, DRAINAGE, PAVING, AND STRUCTURES.

NOTE: C205129 PAMLICO BR-0173 HAS A MANDATORY PRE-BID CONFERENCE ON WEDNESDAY, JANUARY 7, 2026 AT 11:00AM AT NCDOT FERRY OFFICE BUILDING ON THE RIGHT SIDE OF THE FERRY TERMINAL 135 MINNESOTT BEACH RD, MINNESOTT BEACH, NC 28510.
CONTACT: LEE MAI AT LEEMAI@NCDOT.GOV OR AT 984-389-0229.

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L260120

001

CONTRACT ID : C205129 51815.3.1

DIV OFFICE NEW BERN

LENGTH = 0.057 MI

COUNTY : PAMLICO

GRADING, DRAINAGE, PAVING AND STRUCTURE.

DBE GOAL

COMPLETION DATE : MAY 14, 2027

BRIDGE #680078 OVER NEUSE RIVER ON NC-306.

ROADWAY ITEMS					
			24	EA	PAINT PAVEMENT MARKING CHARACTER
			28	EA	PAINT PAVEMENT MARKING SYMBOL
Lump Sum	LS	MOBILIZATION			
Lump Sum	LS	CONSTRUCTION SURVEYING	1,578	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
Lump Sum	LS	GRADING	86	LF	REMOVAL OF PAVEMENT MARKING LINES (8")
300	CY	UNDERCUT EXCAVATION	160	LF	REMOVAL OF PAVEMENT MARKING LINES (24")
5	CY	DRAINAGE DITCH EXCAVATION	23	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
300	CY	SELECT GRANULAR MATERIAL	Lump Sum	LS	PORTABLE LIGHTING
300	SY	GEOTEXTILE FOR SOIL STABILIZATION	100	LF	TEMPORARY SILT FENCE
10	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	35	TON	STONE FOR EROSION CONTROL, CLASS A
10	SY	FOUNDATION CONDITIONING GEOTEXTILE	40	TON	STONE FOR EROSION CONTROL, CLASS B
24	LF	18" RC PIPE CULVERTS, CLASS IV	55	TON	SEDIMENT CONTROL STONE
1	EA	PIPE CLEAN OUT	1.2	ACR	TEMPORARY MULCHING
30	TON	CLASS IV AGGREGATE STABILIZATION	100	LB	SEED FOR TEMPORARY SEEDING
60	TON	AGGREGATE BASE COURSE	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
50	SY	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	200	LF	TEMPORARY SLOPE DRAINS
10	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	460	LF	SAFETY FENCE
10	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	60	CY	SILT EXCAVATION
5	TON	ASPHALT BINDER FOR PLANT MIX	250	SY	MATting FOR EROSION CONTROL
44.8	CY	SUBDRAIN EXCAVATION	100	SY	COIR FIBER MAT
200	SY	GEOTEXTILE FOR SUBSURFACE DRAINS	25	LF	1/4" HARDWARE CLOTH
34	CY	SUBDRAIN COARSE AGGREGATE	1,225	SY	FLOATING TURBIDITY CURTAIN
200	LF	6" PERFORATED SUBDRAIN PIPE	2	EA	SPECIAL STILLING BASINS
1	EA	SUBDRAIN PIPE OUTLET	10	LB	FLOCCULANT
6	LF	6" OUTLET PIPE	40	LF	COIR FIBER WATTLE
0.45	CY	PIPE COLLARS	1.2	ACR	SEEDING & MULCHING
1	EA	MASONRY DRAINAGE STRUCTURES	0.6	ACR	MOWING
1	EA	FRAME WITH TWO GRATES, STD 840.24	50	LB	SEED FOR REPAIR SEEDING
9	LF	CHAIN LINK FENCE, *** FABRIC (72")	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1	EA	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	50	LB	SEED FOR SUPPLEMENTAL SEEDING
4	EA	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	0.75	TON	FERTILIZER TOPDRESSING
1	EA	GENERIC FENCING ITEM GATE REPLACEMENT	10	MHR	SPECIALIZED HAND MOWING
3	TON	RIP RAP, CLASS B	2	MHR	MANUAL LITTER REMOVAL
220	SY	GEOTEXTILE FOR DRAINAGE	1	TON	LITTER DISPOSAL
112	SF	WORK ZONE SIGNS (STATIONARY)	13	EA	RESPONSE FOR EROSION CONTROL
96	SF	WORK ZONE SIGNS (PORTABLE)	1	EA	CONCRETE WASHOUT STRUCTURE
46	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	0.1	ACR	REFORESTATION
40	EA	DRUMS	2	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT STRUCTURE ITEMS
36	LF	BARRICADES (TYPE III)	Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+23.61 -RAMP-)
8	DAY	FLAGGER	Lump Sum	LS	ASBESTOS ASSESSMENT
18	EA	TUBULAR MARKERS (FIXED)	53,860	LS	APPROX LBS STRUCTURAL STEEL
1,076	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	Lump Sum	LS	POLLUTION CONTROL
927	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	6	EA	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 14 X 73)
160	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	540	LF	HP 14 X 73 STEEL PILES
18	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	6	EA	PILE REDRIVES
5	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2	EA	DYNAMIC PILE TESTING
1,944	LF	PAINT PAVEMENT MARKING LINES (4")	Lump Sum	LS	GENERIC STRUCTURE ITEM PAINTING BULKHEAD SHEET PILING
80	LF	PAINT PAVEMENT MARKING LINES (24")	Lump Sum	LS	GENERIC STRUCTURE ITEM PAINTING CONTAINMENT FOR BULKHEAD
			Lump Sum	LS	GENERIC STRUCTURE ITEM PAINTING STEEL PILES

Lump Sum	LS	GENERIC STRUCTURE ITEM RAMP ELECTRICAL SYSTEM
Lump Sum	LS	GENERIC STRUCTURE ITEM RAMP MECHANICAL SYSTEM
69	LF	GENERIC STRUCTURE ITEM 1-1/4" DIA STEEL PIPE RAIL
7	CY	GENERIC STRUCTURE ITEM CLASS AA CONCRETE (BRIDGE)
383	LB	GENERIC STRUCTURE ITEM EPOXY COATED REINFORCING STEEL (BRIDGE)
223	SF	GENERIC STRUCTURE ITEM ULTRA HIGH MOLECULAR WEIGHT POLYETHYLENE FENDER (1-1/4")
120	SF	GENERIC STRUCTURE ITEM ULTRA HIGH MOLECULAR WEIGHT POLYETHYLENE FENDER (3-1/2")

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120

002

CONTRACT ID : C204814 38608.3.1

DIV OFFICE WILSON

LENGTH = 0.607 MI

COUNTY : WAYNE

GRADING, DRAINAGE, PAVING, SIGNALS, AND STRUCTURES.

DBE GOAL

COMPLETION DATE : NOV 11, 2028

BRIDGE #950020 OVER CSX TRANSPORTATION RAILROAD TRACKS ON US-70 BUS.

ROADWAY ITEMS					
			2,400	LF	2'-6" CONCRETE CURB & GUTTER
Lump Sum	LS	MOBILIZATION	100	LF	SHOULDER BERM GUTTER
Lump Sum	LS	CONSTRUCTION SURVEYING	1,100	SY	4" CONCRETE SIDEWALK
Lump Sum	LS	GENERIC MISCELLANEOUS ITEM VIBRATION MONITORING	11	EA	CONCRETE CURB RAMPS
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	220	SY	6" CONCRETE DRIVEWAY
400	CY	UNDERCUT EXCAVATION	1,190	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
Lump Sum	LS	GRADING	90	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED
4,700	CY	BORROW EXCAVATION	95	LF	GENERIC PAVING ITEM VARIABLE HEIGHT CONCRETE BARRIER, TYPE T2 MODIFIED
400	CY	SELECT GRANULAR MATERIAL	1	EA	ADJUSTMENT OF DROP INLETS
400	SY	GEOTEXTILE FOR SOIL STABILIZATION	1	EA	CONVERT EXISTING DROP INLET TO JUNCTION BOX
120	SF	TEMPORARY SHORING	400	LF	STEEL BEAM GUARDRAIL
Lump Sum	LS	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION 30+73.46 -L-	100	LF	STEEL BEAM GUARDRAIL, SHOP CURVED
50	TON	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	5	EA	ADDITIONAL GUARDRAIL POSTS
173	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	1	EA	GUARDRAIL END UNITS, TYPE AT-1
1,598	SY	FOUNDATION CONDITIONING GEOTEXTILE	1	EA	GUARDRAIL END UNITS, TYPE CAT-1
52	LF	15" DRAINAGE PIPE	3	EA	GUARDRAIL ANCHOR UNITS, TYPE III
2	EA	*** DRAINAGE PIPE ELBOWS (15")	1	EA	GUARDRAIL END UNITS, TYPE TL-2
548	LF	15" RC PIPE CULVERTS, CLASS IV	170	LF	REMOVE EXISTING GUARDRAIL
108	LF	18" RC PIPE CULVERTS, CLASS IV	2	TON	RIP RAP, CLASS B
372	LF	PIPE REMOVAL	235	SY	GEOTEXTILE FOR DRAINAGE
100	CY	SHALLOW UNDERCUT	655	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (A)
200	TON	CLASS IV SUBGRADE STABILIZATION	53	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (B)
300	SY	GEOTEXTILE FOR SUBGRADE STABILIZATION	35	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)
100	TON	INCIDENTAL STONE BASE	270	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
7,490	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	77	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (F)
2,790	SY	INCIDENTAL MILLING	3	CY	REINFORCED CONCRETE SIGN FOUNDATIONS
1,560	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,728	LB	SUPPORTS, BREAKAWAY STEEL BEAM
1,860	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	910	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
2,150	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1	EA	SIGN ERECTION, TYPE D
290	TON	ASPHALT BINDER FOR PLANT MIX	44	EA	SIGN ERECTION, TYPE E
145	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	6	EA	SIGN ERECTION, TYPE F
45	CY	SUBDRAIN EXCAVATION	3	EA	SIGN ERECTION, TYPE *** (OVERHEAD) (A)
200	SY	GEOTEXTILE FOR SUBSURFACE DRAINS	1	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)
34	CY	SUBDRAIN COARSE AGGREGATE	2	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)
200	LF	6" PERFORATED SUBDRAIN PIPE	33	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
1	EA	SUBDRAIN PIPE OUTLET	3	EA	DISPOSAL OF SIGN, A OR B (OVERHEAD)
6	LF	6" OUTLET PIPE	1	EA	DISPOSAL OF LIGHTING SYSTEM
12	EA	MASONRY DRAINAGE STRUCTURES	1,285	SF	WORK ZONE SIGNS (STATIONARY)
0.6	LF	MASONRY DRAINAGE STRUCTURES	192	SF	WORK ZONE SIGNS (PORTABLE)
2	EA	FRAME WITH TWO GRATES, STD 840.16	422	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
1	EA	FRAME WITH TWO GRATES, STD 840.24	2	EA	FLASHING ARROW BOARD
4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN
4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	30	DAY	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)
2	EA	FRAME WITH COVER, STD 840.54	225	EA	DRUMS
2	EA	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	30	EA	SEQUENTIAL FLASHING WARNING LIGHTS
170	LF	*** X *** CONCRETE CURB (8" X 12")	25	EA	CONES
			300	LF	BARRICADES (TYPE III)

24	LF	PEDESTRIAN CHANNELIZING DEVICES	10	LB	FLOCCULANT
180	DAY	FLAGGER	2.5	ACR	SEEDING & MULCHING
1	EA	TMA	1.25	ACR	MOWING
80	HR	LAW ENFORCEMENT	50	LB	SEED FOR REPAIR SEEDING
25	EA	SKINNY DRUM	0.25	TON	FERTILIZER FOR REPAIR SEEDING
20	EA	TEMPORARY RAISED PAVEMENT MARKERS	50	LB	SEED FOR SUPPLEMENTAL SEEDING
3,270	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1.5	TON	FERTILIZER TOPDRESSING
5,618	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	10	MHR	SPECIALIZED HAND MOWING
650	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2	MHR	MANUAL LITTER REMOVAL
1,200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1	TON	LITTER DISPOSAL
547	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	25	EA	RESPONSE FOR EROSION CONTROL
8	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	1	EA	CONCRETE WASHOUT STRUCTURE
29	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	20	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT
950	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	10	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION, TYPE I
160	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	1	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT
14,114	LF	PAINT PAVEMENT MARKING LINES (4")	8	EA	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)
4,958	LF	PAINT PAVEMENT MARKING LINES (6")	5,350	LF	SIGNAL CABLE
900	LF	PAINT PAVEMENT MARKING LINES (8")	30	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
502	LF	PAINT PAVEMENT MARKING LINES (24")	225	LF	MESSENGER CABLE (1/4")
16	EA	PAINT PAVEMENT MARKING CHARACTER	1,050	LF	TRACER WIRE
8	EA	PAINT PAVEMENT MARKING SYMBOL	650	LF	UNPAVED TRENCHING (*****) (1, 2")
2	EA	IN LANE ROUTE SHIELDS	200	LF	UNPAVED TRENCHING (*****) (3, 2")
7,360	LF	REMOVAL OF PAVEMENT MARKING LINES (4")	500	LF	DIRECTIONAL DRILL (*****) (1, 2")
40	LF	GENERIC PAVEMENT MARKING ITEM YIELD LINE THERMOPLASTIC PAVEMENT MARKING (24", 90 MILS)	600	LF	DIRECTIONAL DRILL (*****) (2, 2")
96	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	8	EA	JUNCTION BOX (STANDARD SIZE)
6	EA	PERMANENT RAISED PAVEMENT MARKERS	18	EA	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)
Lump Sum	LS	PORTABLE LIGHTING	7	EA	GUY ASSEMBLY
1,330	LF	6" WATER LINE	2	EA	1/2" RISER WITH WEATHERHEAD
416	LF	16" WATER LINE	1	EA	1" RISER WITH WEATHERHEAD
3,990	LB	DUCTILE IRON WATER PIPE FITTINGS	2	EA	2" RISER WITH WEATHERHEAD
8	EA	6" VALVE	1	EA	HEAT SHRINK TUBING RETROFIT KIT
1	EA	16" VALVE	9	EA	2" RISER WITH HEAT SHRINK TUBING
1	EA	2" BLOW OFF	2,050	LF	INDUCTIVE LOOP SAWCUT
15	EA	RECONNECT WATER METER	5,050	LF	LEAD-IN CABLE (14-2)
2	EA	RELOCATE FIRE HYDRANT	4,450	LF	COMMUNICATIONS CABLE (** FIBER) (24)
11	LF	FIRE HYDRANT LEG	325	LF	DROP CABLE
515	LF	WATER SERVICE LINE	5	EA	SPLICE ENCLOSURE
102	LF	8" SANITARY GRAVITY SEWER	2	EA	INTERCONNECT CENTER
90	LB	DUCTILE IRON SEWER PIPE FITTINGS	7	EA	DELINEATOR MARKER
4	EA	4' DIA UTILITY MANHOLE	1,850	LF	REMOVE EXISTING COMMUNICATIONS CABLE
9.5	LF	UTILITY MANHOLE WALL 4' DIA	13	EA	SIGN FOR SIGNALS
1,501	LF	ABANDON 6" UTILITY PIPE	3	EA	TYPE I POST WITH FOUNDATION
190	LF	ABANDON 8" UTILITY PIPE	3	EA	TYPE II PEDESTAL WITH FOUNDATION
398	LF	ABANDON 16" UTILITY PIPE	3	EA	SIGNAL CABINET FOUNDATION
1	EA	ABANDON UTILITY MANHOLE	18	EA	DETECTOR CARD (TYPE 170)
3	EA	REMOVE UTILITY MANHOLE	3	EA	INSTALL DEPARTMENT SUPPLIED 2070 CONTROLLER
6,400	LF	TEMPORARY SILT FENCE	3	EA	CABINET WITHOUT CONTROLLER (****) (TYPE 170E, BASE MOUNTED)
135	TON	STONE FOR EROSION CONTROL, CLASS A	3	EA	CABINET BASE EXTENDER
60	TON	STONE FOR EROSION CONTROL, CLASS B	2	EA	GENERIC SIGNAL ITEM ETHERNET EDGE SWITCH
210	TON	SEDIMENT CONTROL STONE	1	EA	GENERIC SIGNAL ITEM MICROWAVE VEHICLE DETECTION SYSTEM - MULTIPLE ZONES
2.5	ACR	TEMPORARY MULCHING	2	EA	GENERIC SIGNAL ITEM RECTANGULAR RAPID FLASHING BEACON ASSEMBLY
200	LB	SEED FOR TEMPORARY SEEDING	3	EA	GENERIC SIGNAL ITEM REMOVE EXISTING UTILITY POLE
1	TON	FERTILIZER FOR TEMPORARY SEEDING	WALL ITEMS		
200	LF	TEMPORARY SLOPE DRAINS	1,077	SF	MSE RETAINING WALL NO **** (1)
220	LF	SAFETY FENCE	408	SF	MSE RETAINING WALL NO **** (2)
160	CY	SILT EXCAVATION	437	SF	SOLDIER PILE RETAINING WALLS
1,515	SY	MATting FOR EROSION CONTROL			
650	LF	1/4" HARDWARE CLOTH			

STRUCTURE ITEMS

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURES AT STATION ***** (30+73.46 -L-)
Lump Sum	LS	ASBESTOS ASSESSMENT
Lump Sum	LS	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (30+73.46 -L-)
10,093	SF	REINFORCED CONCRETE DECK SLAB
8,795	SF	GROOVING BRIDGE FLOORS
170	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (30+73.46 -L-)
21,918	LB	REINFORCING STEEL (BRIDGE)
1,305.94	LF	45" PRESTRESSED CONCRETE GIRDERS
17	EA	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)
18	EA	PILE DRIVING EQUIPMENT SETUP FOR *** GALVANIZED STEEL PILES (PP 24 X 0.5)
975	LF	HP 12 X 53 STEEL PILES
1,980	LF	PP ** X **** GALVANIZED STEEL PILES (24 X 0.5)
19	EA	PILE REDRIVES
3	EA	DYNAMIC PILE TESTING
627.06	LF	TWO BAR METAL RAIL
426.71	LF	1'-**" X ***** CONCRETE PARAPET (1'-2" X 3'-3")
372.7	LF	**" CHAIN LINK FENCE (72")
326	SY	4" SLOPE PROTECTION
539	SY	**" SLOPE PROTECTION (8")
720	TON	RIP RAP CLASS II (2'-0" THICK)
800	SY	GEOTEXTILE FOR DRAINAGE
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	GENERIC STRUCTURE ITEM STRIP SEAL EXPANSION JOINTS
215.9	LF	GENERIC STRUCTURE ITEM 1'-2" X 2'-6" CONCRETE PARAPET WITH MOMENT SLAB

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120 003

CONTRACT ID : C205162 2026CPT.05.06.10921.1 DIV OFFICE DURHAM LENGTH = 22.839 MI
 COUNTY : WAKE

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

DBE GOAL COMPLETION DATE : SEP 02, 2027

3 SECTIONS OF PRIMARY ROADS, AND 26 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
773	TON	INCIDENTAL STONE BASE
30.92	SMI	SHOULDER RECONSTRUCTION
2,871	TON	AGGREGATE SHOULDER BORROW
113,718	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (1-1/2")
17,310	SY	INCIDENTAL MILLING
11,766	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
19,334	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
2,087	TON	ASPHALT BINDER FOR PLANT MIX
3,769	TON	PATCHING EXISTING PAVEMENT
4	EA	CONCRETE CURB RAMPS
4	SY	GENERIC PAVING ITEM REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
8	LF	GENERIC PAVING ITEM REMOVE AND REPLACE 2'-6" CONCRETE CURB AND GUTTER
4	EA	GENERIC PAVING ITEM REMOVE CONCRETE CURB RAMPS
17	EA	ADJUSTMENT OF MANHOLES
20	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
2,452	SF	WORK ZONE ADVANCE/GENERAL WARNING SIGNING
12	LF	PEDESTRIAN CHANNELIZING DEVICES
Lump Sum	LS	TEMPORARY TRAFFIC CONTROL
360	HR	LAW ENFORCEMENT
1	EA	GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES
5	EA	GENERIC TRAFFIC CONTROL ITEM PEDESTRIAN TRANSPORT SERVICE
371,129	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
1,949	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
1,416	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
150	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)
2,228	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)
82	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)
97	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
32	LF	GENERIC PAVEMENT MARKING ITEM YIELD LINE THERMOPLASTIC PAVEMENT MARKING (24", 90 MILS)
1,119	EA	GENERIC PAVEMENT MARKING ITEM INLAID CRADLE MARKERS
10,764	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120

004

CONTRACT ID : C205036 44367.3.1

DIV OFFICE FAYETTEVILLE

LENGTH = 1.304 MI

COUNTY : ROBESON

GRADING, DRAINAGE, PAVING, SIGNALS, AND CULVERTS.

DBE GOAL

COMPLETION DATE : MAY 14, 2030

SR-1997 (FAYETTEVILLE RD) FROM FARRINGDOM ST TO EAST 22ND ST.

ROADWAY ITEMS					
			6	LF	6" OUTLET PIPE
Lump Sum	LS	MOBILIZATION	3	EA	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE
Lump Sum	LS	CONSTRUCTION SURVEYING	5.085	CY	PIPE COLLARS
Lump Sum	LS	GRADING	0.486	CY	PIPE PLUGS
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	115	CY	FLOWABLE FILL
850	CY	UNDERCUT EXCAVATION	265	EA	MASONRY DRAINAGE STRUCTURES
210	CY	DRAINAGE DITCH EXCAVATION	22.948	CY	MASONRY DRAINAGE STRUCTURES
800	CY	SELECT GRANULAR MATERIAL	134.1	LF	MASONRY DRAINAGE STRUCTURES
1,500	SY	GEOTEXTILE FOR SOIL STABILIZATION	42	EA	FRAME WITH TWO GRATES, STD 840.16
15,500	SF	TEMPORARY SHORING	3	EA	FRAME WITH TWO GRATES, STD 840.24
50	TON	GENERIC GRADING ITEM	3	EA	FRAME WITH TWO GRATES, STD 840.29
		HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	44	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **
2,180	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	70	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **
6,860	SY	FOUNDATION CONDITIONING GEOTEXTILE			(F)
124	LF	24" DRAINAGE PIPE	74	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **
52	LF	***** RC PIPE CULVERTS, CLASS IV (12")			(G)
32	LF	***** RC PIPE CULVERTS, CLASS IV (60")	7	EA	FRAME WITH COVER, STD 840.54
252	LF	***** RC PIPE CULVERTS, CLASS IV (72")	24	EA	STEEL FRAME WITH TWO GRATES, STD 840.37
10,192	LF	15" RC PIPE CULVERTS, CLASS IV	36	EA	CONCRETE TRANSITIONAL SECTION FOR DROP INLET
2,624	LF	18" RC PIPE CULVERTS, CLASS IV	100	LF	*** X *** CONCRETE CURB (8" X 12")
4,302	LF	24" RC PIPE CULVERTS, CLASS IV	180	LF	*** X *** CONCRETE CURB (8" X 18")
960	LF	30" RC PIPE CULVERTS, CLASS IV	360	LF	***,*** CONCRETE CURB & GUTTER (2'-9")
1,582	LF	36" RC PIPE CULVERTS, CLASS IV	710	LF	1'-6" CONCRETE CURB & GUTTER
300	LF	42" RC PIPE CULVERTS, CLASS IV	22,880	LF	2'-6" CONCRETE CURB & GUTTER
24	LF	15" CS PIPE CULVERTS, 0.064" THICK	6,210	SY	4" CONCRETE SIDEWALK
18	LF	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (30", 0.250")	83	EA	CONCRETE CURB RAMPS
18	LF	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (30", 0.250")	680	SY	6" CONCRETE DRIVEWAY
6,385	LF	PIPE REMOVAL	600	SY	4" CONCRETE ISLAND COVER
3,000	CY	SHALLOW UNDERCUT	4,080	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
6,000	TON	CLASS IV SUBGRADE STABILIZATION	390	SY	*** MONOLITHIC CONCRETE MEDIAN (***** (6", SURFACE MOUNTED)
75	TON	CLASS IV AGGREGATE STABILIZATION	295	LF	GENERIC PAVING ITEM 1'-10" ROLLED CURB AND GUTTER
9,000	SY	GEOTEXTILE FOR SUBGRADE STABILIZATION	1	EA	ADJUSTMENT OF CATCH BASINS
1,000	TON	INCIDENTAL STONE BASE	1	EA	ADJUSTMENT OF DROP INLETS
6,560	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (3")	2	EA	IMPACT ATTENUATOR UNITS, TYPE TL-3
1,580	SY	MILLING ASPHALT PAVEMENT, ***" TO ***** (0" TO 3")	1,875	LF	STEEL BEAM GUARDRAIL
5,000	SY	INCIDENTAL MILLING	212.5	LF	STEEL BEAM GUARDRAIL, SHOP CURVED
16,420	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	4	EA	STEEL BEAM GUARDRAIL TERMINAL SECTIONS
14,660	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	10	EA	ADDITIONAL GUARDRAIL POSTS
18,400	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2	EA	GUARDRAIL END UNITS, TYPE AT-1
2,530	TON	ASPHALT BINDER FOR PLANT MIX	6	EA	GUARDRAIL END UNITS, TYPE CAT-1
3,950	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	5	EA	GUARDRAIL END UNITS, TYPE TL-3
450	SY	GENERIC PAVING ITEM 9" JOINTED CONCRETE TRUCK APRON	6	EA	GUARDRAIL END UNITS, TYPE TL-2
112	CY	SUBDRAIN EXCAVATION	369	LF	REMOVE & RESET EXISTING GUARDRAIL
500	SY	GEOTEXTILE FOR SUBSURFACE DRAINS	193.5	LF	REMOVE EXISTING GUARDRAIL
84	CY	SUBDRAIN COARSE AGGREGATE	150	LF	TEMPORARY STEEL BEAM GUARDRAIL, SHOP CURVED
500	LF	6" PERFORATED SUBDRAIN PIPE	1	EA	TEMPORARY GUARDRAIL END UNITS, TYPE *****
1	EA	SUBDRAIN PIPE OUTLET			(AT-1)

1	EA	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TL-2)	147	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
10	EA	TEMPORARY ADDITIONAL GUARDRAIL POSTS	69	LF	GENERIC PAVEMENT MARKING ITEM YIELD LINE PAINT PAVEMENT MARKING (24")
275	LF	CHAIN LINK FENCE RESET	69	LF	GENERIC PAVEMENT MARKING ITEM YIELD LINE THERMOPLASTIC PAVEMENT MARKING (24", 90 MILS)
490	TON	RIP RAP, CLASS I	790	EA	PERMANENT RAISED PAVEMENT MARKERS
16	TON	RIP RAP, CLASS B	23	EA	OBJECT MARKERS (TYPE **) (I)
5,090	SY	GEOTEXTILE FOR DRAINAGE	423	LF	6" WATER LINE
1,710	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	2,981	LF	8" WATER LINE
4	EA	SIGN ERECTION, TYPE D	1,773	LF	12" WATER LINE
84	EA	SIGN ERECTION, TYPE E	26,830	LB	DUCTILE IRON WATER PIPE FITTINGS
10	EA	SIGN ERECTION, TYPE F	13	EA	6" VALVE
5	EA	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	3	EA	8" VALVE
10	EA	SIGN ERECTION, RELOCATE TYPE ***** (GROUND MOUNTED) (E)	12	EA	*** INSERTION VALVE (12")
Lump Sum	LS	SUPPORTS, OVERHEAD SIGN STRUCTURE ***** (41+60 -L-)	2	EA	*** INSERTION VALVE (6")
Lump Sum	LS	SUPPORTS, OVERHEAD SIGN STRUCTURE ***** (49+20 -L-)	15	EA	*** INSERTION VALVE (8")
Lump Sum	LS	SUPPORTS, OVERHEAD SIGN STRUCTURE ***** (60+05 -L-)	30	EA	RELOCATE WATER METER
62	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	26	EA	RECONNECT WATER METER
10	EA	DISPOSAL OF SUPPORT, U-CHANNEL	5	EA	RELOCATE 2" DCV BACKFLOW PREVENTION ASSEMBLY
1,537	SF	WORK ZONE SIGNS (STATIONARY)	11	EA	RELOCATE FIRE HYDRANT
122	SF	WORK ZONE SIGNS (PORTABLE)	530	LF	FIRE HYDRANT LEG
1,121	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	1,107	LF	WATER SERVICE LINE
3	EA	FLASHING ARROW BOARD	1,545	LF	8" SANITARY GRAVITY SEWER
5	EA	PORTABLE CHANGEABLE MESSAGE SIGN	1,107	LF	12" SANITARY GRAVITY SEWER
6	EA	WORK ZONE PRESENCE LIGHTING	33	LF	2" FORCE MAIN SEWER
607	EA	DRUMS	6	EA	SANITARY SEWER CLEAN-OUT
410	LF	BARRICADES (TYPE III)	363	LF	SEWER SERVICE LINE
1,676	LF	PEDESTRIAN CHANNELIZING DEVICES	30	EA	4' DIA UTILITY MANHOLE
28	DAY	FLAGGER	56.7	LF	UTILITY MANHOLE WALL 4' DIA
10	EA	TEMPORARY CRASH CUSHIONS	453	LF	ABANDON 6" UTILITY PIPE
7	EA	REMOVE & RESET TEMPORARY CRASH CUSHION	3,940	LF	ABANDON 8" UTILITY PIPE
2	EA	TMA	2,846	LF	ABANDON 12" UTILITY PIPE
384	LF	PORTABLE CONCRETE BARRIER	5	EA	ABANDON UTILITY MANHOLE
2,151	LF	PORTABLE CONCRETE BARRIER (ANCHORED)	4	EA	REMOVE UTILITY MANHOLE
497	LF	REMOVE AND RESET PORTABLE CONCRETE BARRIER	59	LF	16" ENCASEMENT PIPE
630	LF	REMOVE & RESET PORTABLE CONCRETE BARRIER (ANCHORED)	46	LF	24" ENCASEMENT PIPE
32	HR	LAW ENFORCEMENT	25	LF	BORE AND JACK OF *** (24")
63	EA	TUBULAR MARKERS (FIXED)	3	EA	STEEL PILE PIERS
2	EA	GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES	23,025	LF	TEMPORARY SILT FENCE
3	EA	GENERIC TRAFFIC CONTROL ITEM TEMPORARY CURB RAMPS	570	TON	STONE FOR EROSION CONTROL, CLASS A
1,038	EA	TEMPORARY RAISED PAVEMENT MARKERS	605	TON	STONE FOR EROSION CONTROL, CLASS B
36,313	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,420	TON	SEDIMENT CONTROL STONE
5,178	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	5.12	ACR	TEMPORARY MULCHING
189	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)	300	LB	SEED FOR TEMPORARY SEEDING
2,844	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	1.5	TON	FERTILIZER FOR TEMPORARY SEEDING
25	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	405	LF	TEMPORARY SLOPE DRAINS
174	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	380	LF	SAFETY FENCE
72,917	LF	PAINT PAVEMENT MARKING LINES (4")	940	CY	SILT EXCAVATION
2,342	LF	PAINT PAVEMENT MARKING LINES (8")	14,000	SY	MATTING FOR EROSION CONTROL
2,235	LF	PAINT PAVEMENT MARKING LINES (24")	1,200	SY	COIR FIBER MAT
46	EA	PAINT PAVEMENT MARKING CHARACTER	15,920	LF	1/4" HARDWARE CLOTH
101	EA	PAINT PAVEMENT MARKING SYMBOL	31	EA	SPECIAL STILLING BASINS
72,917	LF	REMOVAL OF PAVEMENT MARKING LINES (4")	290	LB	FLOCCULANT
2,342	LF	REMOVAL OF PAVEMENT MARKING LINES (8")	1,960	LF	COIR FIBER WATTLE
2,235	LF	REMOVAL OF PAVEMENT MARKING LINES (24")	210	LF	COIR FIBER WATTLE BARRIER
			60	LF	COIR FIBER BAFFLE
			5.12	ACR	SEEDING & MULCHING
			2.6	ACR	MOWING
			100	LB	SEED FOR REPAIR SEEDING
			0.25	TON	FERTILIZER FOR REPAIR SEEDING
			125	LB	SEED FOR SUPPLEMENTAL SEEDING
			3.75	TON	FERTILIZER TOPDRESSING

Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+80.00 -Y2-)
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (43+26.00 -L-)
Lump Sum	LS	BOX CULVERT EXCAVATION, STA ***** (20+80.00 -Y2-)
Lump Sum	LS	BOX CULVERT EXCAVATION, STA ***** (43+26.00 -L-)
Lump Sum	LS	BOX CULVERT EXCAVATION, STA ***** (68+62.00 -L-)
1,405	TON	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT
2,063.6	CY	CLASS A CONCRETE (CULVERT)
284,512	LB	REINFORCING STEEL (CULVERT)
225	SF	SHEET PILE RETAINING WALLS

FEDERAL AID PROPOSAL, CONTRACTOR LICENSE NOT REQUIRED TO BID

L260120

005

CONTRACT ID : C205128 51603.3.1

DIV OFFICE GREENSBORO

LENGTH = 0.104 MI

COUNTY : ROCKINGHAM

GRADING, DRAINAGE, PAVING, AND STRUCTURE.

DBE GOAL

COMPLETION DATE : NOV 11, 2027

BRIDGE #780176 OVER NC-14/NC-87 ON SR-1700 (FISHER HILL RD)

ROADWAY ITEMS					
Lump Sum	LS	MOBILIZATION	525	SY	GEOTEXTILE FOR DRAINAGE
Lump Sum	LS	CONSTRUCTION SURVEYING	250	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	1	EA	SIGN ERECTION, TYPE D
550	CY	UNDERCUT EXCAVATION	4	EA	SIGN ERECTION, TYPE E
Lump Sum	LS	GRADING	6	EA	SIGN ERECTION, TYPE F
6,100	CY	BORROW EXCAVATION	11	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
15	CY	DRAINAGE DITCH EXCAVATION	638	SF	WORK ZONE SIGNS (STATIONARY)
200	CY	SELECT GRANULAR MATERIAL	128	SF	WORK ZONE SIGNS (PORTABLE)
400	SY	GEOTEXTILE FOR SOIL STABILIZATION	114	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
760	SF	TEMPORARY SHORING	8	DAY	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)
Lump Sum	LS	GENERIC GRADING ITEM TYPE 2 BRIDGE APPROACH FILL, STATION 15+22.40 -L-	50	EA	DRUMS
128	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	96	LF	BARRICADES (TYPE III)
501	SY	FOUNDATION CONDITIONING GEOTEXTILE	104	DAY	FLAGGER
24	LF	15" DRAINAGE PIPE	4	EA	TEMPORARY CRASH CUSHIONS
116	LF	18" DRAINAGE PIPE	590	LF	PORTABLE CONCRETE BARRIER (ANCHORED)
8	EA	*** DRAINAGE PIPE ELBOWS (18")	34.17	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)
156	LF	15" RC PIPE CULVERTS, CLASS IV	3,304	LF	PAINT PAVEMENT MARKING LINES (4")
128	LF	18" RC PIPE CULVERTS, CLASS IV	10	LF	PAINT PAVEMENT MARKING LINES (24")
344	LF	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (15", 0.625")	3,868	LF	POLYUREA PAVEMENT MARKING LINES (**", *** MILS) (4", 30 MILS)
97	LF	PIPE REMOVAL	765	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
100	CY	SHALLOW UNDERCUT	10	LF	REMOVAL OF PAVEMENT MARKING LINES (24")
200	TON	CLASS IV SUBGRADE STABILIZATION	21	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS
300	SY	GEOTEXTILE FOR SUBGRADE STABILIZATION	722	LF	6" WATER LINE
100	TON	INCIDENTAL STONE BASE	955	LB	DUCTILE IRON WATER PIPE FITTINGS
1,810	SY	MILLING ASPHALT PAVEMENT, ***** DEPTH (1-1/2")	2	EA	6" VALVE
500	SY	INCIDENTAL MILLING	3	EA	RELOCATE WATER METER
430	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	2	EA	RECONNECT WATER METER
90	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	336	LF	WATER SERVICE LINE
600	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	625	LF	ABANDON 6" UTILITY PIPE
65	TON	ASPHALT BINDER FOR PLANT MIX	95	LF	16" ENCASEMENT PIPE
115	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	95	LF	BORE AND JACK OF *** (16")
0.05	CY	PIPE PLUGS	765	LF	TEMPORARY SILT FENCE
14	EA	MASONRY DRAINAGE STRUCTURES	150	TON	STONE FOR EROSION CONTROL, CLASS A
2	EA	FRAME WITH TWO GRATES, STD 840.16	245	TON	STONE FOR EROSION CONTROL, CLASS B
8	EA	FRAME WITH TWO GRATES, STD 840.29	180	TON	SEDIMENT CONTROL STONE
2	EA	FRAME WITH COVER, STD 840.54	1	ACR	TEMPORARY MULCHING
2	EA	GENERIC DRAINAGE ITEM FRAME WITH COVER, STD 840.55	100	LB	SEED FOR TEMPORARY SEEDING
67	LF	SHOULDER BERM GUTTER	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
230	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	200	LF	TEMPORARY SLOPE DRAINS
475	LF	STEEL BEAM GUARDRAIL	60	LF	SAFETY FENCE
137.5	LF	STEEL BEAM GUARDRAIL, SHOP CURVED	380	CY	SILT EXCAVATION
5	EA	ADDITIONAL GUARDRAIL POSTS	2,000	SY	MATTING FOR EROSION CONTROL
2	EA	GUARDRAIL END UNITS, TYPE AT-1	585	LF	1/4" HARDWARE CLOTH
3	EA	GUARDRAIL END UNITS, TYPE TL-3	70	LB	FLOCCULANT
3	EA	GUARDRAIL END UNITS, TYPE TL-2	120	LF	COIR FIBER WATTLE
8	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77	1	ACR	SEEDING & MULCHING
632	LF	REMOVE EXISTING GUARDRAIL	0.5	ACR	MOWING
26	TON	RIP RAP, CLASS B	50	LB	SEED FOR REPAIR SEEDING
			0.25	TON	FERTILIZER FOR REPAIR SEEDING
			50	LB	SEED FOR SUPPLEMENTAL SEEDING

0.75	TON	FERTILIZER TOPDRESSING
10	MHR	SPECIALIZED HAND MOWING
13	EA	RESPONSE FOR EROSION CONTROL
1	EA	CONCRETE WASHOUT STRUCTURE
18	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT
6	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION, TYPE 1
3	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT
WALL ITEMS		
1,576	SF	MSE RETAINING WALL NO **** (1)
1,448	SF	MSE RETAINING WALL NO **** (2)
STRUCTURE ITEMS		
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+22.40 -L-)
Lump Sum	LS	ASBESTOS ASSESSMENT
1,885	SF	REINFORCED CONCRETE DECK SLAB
2,131	SF	GROOVING BRIDGE FLOORS
67.4	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (15+22.40 -L-)
9,304	LB	REINFORCING STEEL (BRIDGE)
222.875	LF	36" PRESTRESSED CONCRETE GIRDERS
16	EA	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)
960	LF	HP 12 X 53 STEEL PILES
1	EA	DYNAMIC PILE TESTING
113.4	LF	CONCRETE BARRIER RAIL
20.2	SY	4" SLOPE PROTECTION
Lump Sum	LS	ELASTOMERIC BEARINGS
Lump Sum	LS	FOAM JOINT SEALS

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120 006

CONTRACT ID : C205163 2026CPT.08.04.10531 DIV OFFICE CARTHAGE LENGTH = 20.028 MI

COUNTY : LEE

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

DBE GOAL

COMPLETION DATE : SEP 02, 2027

4 SECTIONS OF PRIMARY ROADS, AND 14 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
25.35	SMI	SHOULDER RECONSTRUCTION
3,920	TON	AGGREGATE SHOULDER BORROW
71,090	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (1-1/2")
6,528	SY	INCIDENTAL MILLING
16,753	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
6,546	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1,510	TON	ASPHALT BINDER FOR PLANT MIX
726	TON	PATCHING EXISTING PAVEMENT
17,200	LF	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS, (18")
38,280	LF	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS, (8")
2,292	SF	WORK ZONE ADVANCE/GENERAL WARNING SIGNING
Lump Sum	LS	TEMPORARY TRAFFIC CONTROL
80	HR	LAW ENFORCEMENT
80,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
88,840	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
895	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
136	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)
27	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
508,985	LF	PAINT PAVEMENT MARKING LINES (4")
895	LF	PAINT PAVEMENT MARKING LINES (12")
136	LF	PAINT PAVEMENT MARKING LINES (24")
15	EA	PAINT PAVEMENT MARKING SYMBOL
443	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS
Lump Sum	LS	PORTABLE LIGHTING
3,050	LF	SIGNAL CABLE
3,050	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120 007

CONTRACT ID : C205161 2026CPT.08.06.10191 DIV OFFICE CARTHAGE LENGTH = 41.276 MI

COUNTY : CHATHAM

MILLING, RESURFACING, AND SHOULDER RECONSTRUCTION.

DBE GOAL COMPLETION DATE : SEP 02, 2027

6 SECTIONS OF PRIMARY ROADS, AND 16 SECTIONS OF SECONDARY ROADS.

ROADWAY ITEMS

Lump Sum	LS	MOBILIZATION
265	CY	BORROW EXCAVATION
435	TON	INCIDENTAL STONE BASE
11.86	SMI	SHOULDER CONSTRUCTION
51.83	SMI	SHOULDER RECONSTRUCTION
6,525.25	TON	AGGREGATE SHOULDER BORROW
190,440	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (1-1/2")
480	SY	MILLING ASPHALT PAVEMENT, ***" TO *****" (0" TO 1-1/2")
16,420	SY	INCIDENTAL MILLING
11,569	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C
43,338	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
5,022	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
3,755	TON	ASPHALT BINDER FOR PLANT MIX
1,797	TON	PATCHING EXISTING PAVEMENT
60,200	SY	ASPHALT SURFACE TREATMENT, MAT COAT, #*** STONE (#67)
24,100	GAL	EMULSION FOR ASPHALT SURFACE TREATMENT
300	TON	GENERIC PAVING ITEM JOINT REPAIR
275	SY	6" CONCRETE DRIVEWAY
6	EA	ADJUSTMENT OF MANHOLES
8	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
4,810	SF	WORK ZONE ADVANCE/GENERAL WARNING SIGNING
Lump Sum	LS	TEMPORARY TRAFFIC CONTROL
40	HR	LAW ENFORCEMENT
480,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
150	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
170	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)
535	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)
25	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)
52	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
420,600	LF	PAINT PAVEMENT MARKING LINES (4")
694,972	LF	PAINT PAVEMENT MARKING LINES (6")
335	LF	PAINT PAVEMENT MARKING LINES (24")
1	EA	PAINT PAVEMENT MARKING SYMBOL
1,322	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS
150	EA	PERMANENT RAISED PAVEMENT MARKERS
Lump Sum	LS	PORTABLE LIGHTING
260	LF	TEMPORARY SILT FENCE
7,308	SY	MATTING FOR EROSION CONTROL
497	LF	COIR FIBER WATTLE
7.44	ACR	SEEDING & MULCHING
593	LB	SEED FOR REPAIR SEEDING
8.9	TON	FERTILIZER FOR REPAIR SEEDING
1,500	LF	SIGNAL CABLE
1,500	LF	INDUCTIVE LOOP SAWCUT

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120

008

CONTRACT ID : C205117 46891.3.1

DIV OFFICE ALBEMARLE

LENGTH = 0.861 MI

COUNTY : CABARRUS

GRADING, DRAINAGE, PAVING, AND SIGNALS.

DBE GOAL

COMPLETION DATE : APR 29, 2028

US-29 FROM 0.6 MILES WEST OF SR-1414 (ROCK HILL CHURCH RD) TO JUST EAST OF SR-1414 (ROCK HILL CHURCH RD).

ROADWAY ITEMS					
			330	SY	MILLING ASPHALT PAVEMENT, **** TO ***** (1-1/2" TO 3")
Lump Sum	LS	MOBILIZATION			
Lump Sum	LS	CONSTRUCTION SURVEYING	1,200	SY	INCIDENTAL MILLING
Lump Sum	LS	CLEARING & GRUBBING .. ACRE(S)	4,990	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
2	ACR	SUPPLEMENTARY CLEARING & GRUBBING	8,060	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
38,200	CY	UNCLASSIFIED EXCAVATION	7,350	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
9,265	CY	UNDERCUT EXCAVATION	1,050	TON	ASPHALT BINDER FOR PLANT MIX
5,200	CY	BORROW EXCAVATION	550	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
75	CY	DRAINAGE DITCH EXCAVATION	80	EA	RIGHT-OF-WAY MARKERS
1,510	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	370	CY	SUBDRAIN EXCAVATION
140	SY	REMOVAL OF EXISTING CONCRETE PAVEMENT	1,650	SY	GEOTEXTILE FOR SUBSURFACE DRAINS
10	HR	PROOF ROLLING	278	CY	SUBDRAIN COARSE AGGREGATE
200	CY	SELECT GRANULAR MATERIAL, CLASS III	1,650	LF	6" PERFORATED SUBDRAIN PIPE
1,500	SY	GEOTEXTILE FOR SOIL STABILIZATION	4	EA	SUBDRAIN PIPE OUTLET
930	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	24	LF	6" OUTLET PIPE
2,920	SY	FOUNDATION CONDITIONING GEOTEXTILE	20	TON	BLOTTING SAND
208	LF	15" DRAINAGE PIPE	16.2	CY	ENDWALLS
60	LF	18" DRAINAGE PIPE	0.45	CY	PIPE COLLARS
56	LF	24" DRAINAGE PIPE	0.13	CY	PIPE PLUGS
96	LF	36" DRAINAGE PIPE	7	CY	FLOWABLE FILL
140	LF	**** RC PIPE CULVERTS, CLASS IV (48")	89	EA	MASONRY DRAINAGE STRUCTURES
3,656	LF	15" RC PIPE CULVERTS, CLASS IV	41.4	LF	MASONRY DRAINAGE STRUCTURES
1,646	LF	18" RC PIPE CULVERTS, CLASS IV	1	EA	FRAME WITH TWO GRATES, STD 840.16
612	LF	24" RC PIPE CULVERTS, CLASS IV	7	EA	FRAME WITH TWO GRATES, STD 840.24
468	LF	30" RC PIPE CULVERTS, CLASS IV	33	EA	FRAME WITH TWO GRATES, STD 840.29
240	LF	36" RC PIPE CULVERTS, CLASS IV	3	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)
264	LF	*** RC PIPE CULVERTS, CLASS V (12")	22	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
752	LF	*** RC PIPE CULVERTS, CLASS V (15")	20	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
240	LF	*** RC PIPE CULVERTS, CLASS V (18")	1	EA	FRAME WITH COVER, STD 840.54
104	LF	*** RC PIPE CULVERTS, CLASS V (24")	29	EA	CONCRETE TRANSITIONAL SECTION FOR DROP INLET
40	LF	*** RC PIPE CULVERTS, CLASS V (30")	640	LF	*** X *** CONCRETE CURB (8" X 12")
64	LF	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	50	LF	***,*** CONCRETE CURB & GUTTER (2'-0")
124	LF	15" CS PIPE CULVERTS, 0.064" THICK	7,650	LF	2'-6" CONCRETE CURB & GUTTER
2	EA	*** CS PIPE ELBOWS, ***** THICK (36", 0.079")	5,310	SY	4" CONCRETE SIDEWALK
1,415	LF	PIPE REMOVAL	20	EA	CONCRETE CURB RAMPS
Lump Sum	LS	FINE GRADING	140	SY	6" CONCRETE DRIVEWAY
7,810	SY	LIME TREATED SOIL (SLURRY METHOD)	2,630	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
100	TON	LIME FOR LIME TREATED SOIL	3,170	LF	GENERIC PAVING ITEM 2'-6" CONCRETE CURB & GUTTER (SPILL CURB)
230	CY	SHALLOW UNDERCUT	1	EA	ADJUSTMENT OF CATCH BASINS
415	TON	CLASS IV SUBGRADE STABILIZATION	5	EA	ADJUSTMENT OF MANHOLES
350	TON	STABILIZER AGGREGATE	1	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
2,719	SY	GEOTEXTILE FOR SUBGRADE STABILIZATION	750	LF	STEEL BEAM GUARDRAIL
5,045	TON	AGGREGATE BASE COURSE	150	LF	STEEL BEAM GUARDRAIL, SHOP CURVED
7,810	SY	SOIL CEMENT BASE	2	EA	STEEL BEAM GUARDRAIL TERMINAL SECTIONS
219	TON	PORTLAND CEMENT FOR SOIL CEMENT BASE	10	EA	ADDITIONAL GUARDRAIL POSTS
2,350	GAL	ASPHALT CURING SEAL	2	EA	GUARDRAIL END UNITS, TYPE CAT-1
200	TON	INCIDENTAL STONE BASE	2	EA	GUARDRAIL END UNITS, TYPE TL-2
17,790	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")			

150	LF	REMOVE EXISTING GUARDRAIL	74	LF	16" ENCASEMENT PIPE
175	TON	RIP RAP, CLASS I	107	LF	24" ENCASEMENT PIPE
70	TON	RIP RAP, CLASS B	55	LF	30" ENCASEMENT PIPE
975	SY	GEOTEXTILE FOR DRAINAGE	1	EA	GENERIC UTILITY ITEM
1,700	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	2"	IRRIGATION PUMP RELOCATION	
121	EA	SIGN ERECTION, TYPE E	10,655	LF	TEMPORARY SILT FENCE
5	EA	SIGN ERECTION, TYPE F	255	TON	STONE FOR EROSION CONTROL, CLASS A
68	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	1,240	TON	STONE FOR EROSION CONTROL, CLASS B
224	SF	WORK ZONE SIGNS (STATIONARY)	1,365	TON	SEDIMENT CONTROL STONE
192	SF	WORK ZONE SIGNS (PORTABLE)	22.5	ACR	TEMPORARY MULCHING
180	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	1,300	LB	SEED FOR TEMPORARY SEEDING
1	EA	FLASHING ARROW BOARD	8.5	TON	FERTILIZER FOR TEMPORARY SEEDING
401	EA	DRUMS	725	LF	TEMPORARY SLOPE DRAINS
200	LF	BARRICADES (TYPE III)	260	LF	SAFETY FENCE
152	LF	PEDESTRIAN CHANNELIZING DEVICES	5,520	CY	SILT EXCAVATION
270	DAY	FLAGGER	16,580	SY	MATting FOR EROSION CONTROL
240	HR	LAW ENFORCEMENT	100	SY	COIR FIBER MAT
36,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,650	LF	1/4" HARDWARE CLOTH
155	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	900	SY	LOW PERMEABILITY GEOTEXTILE
4,500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	170	LF	*** TEMPORARY PIPE (18")
1,900	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	155	LF	*** TEMPORARY PIPE (24")
100	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	25	LF	TEMPORARY PIPE FOR STREAM CROSSING
15,092	LF	PAINT PAVEMENT MARKING LINES (4")	160	SY	FLOATING TURBIDITY CURTAIN
230	LF	PAINT PAVEMENT MARKING LINES (24")	1	EA	SPECIAL STILLING BASINS
28	EA	PAINT PAVEMENT MARKING SYMBOL	390	LB	FLOCCULANT
15,282	LF	REMOVAL OF PAVEMENT MARKING LINES (4")	20	LF	WATTLE
215	LF	REMOVAL OF PAVEMENT MARKING LINES (24")	490	LF	COIR FIBER WATTLE
26	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	1,225	LF	COIR FIBER BAFFLE
450	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	4	EA	*** SKIMMER (1-1/2")
Lump Sum	LS	PORTABLE LIGHTING	18	ACR	SEEDING & MULCHING
105	LF	6" WATER LINE	15	ACR	MOWING
1,792	LF	12" WATER LINE	250	LB	SEED FOR REPAIR SEEDING
441	LF	16" WATER LINE	0.75	TON	FERTILIZER FOR REPAIR SEEDING
11,200	LB	DUCTILE IRON WATER PIPE FITTINGS	425	LB	SEED FOR SUPPLEMENTAL SEEDING
2	EA	6" VALVE	12.25	TON	FERTILIZER TOPDRESSING
10	EA	12" VALVE	40	LF	IMPERVIOUS DIKE
1	EA	16" VALVE	10	MHR	SPECIALIZED HAND MOWING
8	EA	*** INSERTION VALVE (12")	9	MHR	MANUAL LITTER REMOVAL
1	EA	*** INSERTION VALVE (6")	2	TON	LITTER DISPOSAL
1	EA	12" TAPPING SLEEVE & VALVE	75	EA	RESPONSE FOR EROSION CONTROL
2	EA	16" TAPPING SLEEVE & VALVE	1	EA	CONCRETE WASHOUT STRUCTURE
2	EA	2" BLOW OFF	462	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT
1	EA	4" WATER METER	154	EA	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION, TYPE 2
5	EA	RELOCATE WATER METER	5	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT
1	EA	RECONNECT WATER METER	6	EA	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)
5	EA	RELOCATE 2" DCV BACKFLOW PREVENTION ASSEMBLY	5,680	LF	SIGNAL CABLE
1	EA	8" RPZ BACKFLOW PREVENTION ASSEMBLY	17	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
5	EA	FIRE HYDRANT	7	EA	VEHICLE SIGNAL HEAD (12", 4 SECTION)
63	LF	FIRE HYDRANT LEG	4	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
5	EA	12" LINE STOP	965	LF	MESSENGER CABLE (1/4")
2	EA	16" LINE STOP	1,205	LF	UNPAVED TRENCHING (***** (2, 2"))
144	LF	WATER SERVICE LINE	9	EA	JUNCTION BOX (STANDARD SIZE)
477	LF	8" SANITARY GRAVITY SEWER	2	EA	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)
4	EA	4' DIA UTILITY MANHOLE	3	EA	WOOD POLE
65	LF	ABANDON 6" UTILITY PIPE	13	EA	GUY ASSEMBLY
307	LF	ABANDON 8" UTILITY PIPE	1	EA	HEAT SHRINK TUBING RETROFIT KIT
2,026	LF	ABANDON 12" UTILITY PIPE	1	EA	2" RISER WITH HEAT SHRINK TUBING
146	LF	ABANDON 16" UTILITY PIPE	2,030	LF	INDUCTIVE LOOP SAWCUT
2	EA	REMOVE FIRE HYDRANT	6,400	LF	LEAD-IN CABLE (14-2)
45	LF	12" ENCASEMENT PIPE	3	EA	SITE SURVEY
			4	EA	LUMINAIRE ARM FOR VIDEO SYSTEM

4	EA	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT
1	EA	EXTERNAL LOOP EMULATOR PROCESSING UNIT
595	LF	COMMUNICATIONS CABLE (** FIBER) (12)
420	LF	DROP CABLE
2	EA	SPLICE ENCLOSURE
1	EA	INTERCONNECT CENTER
620	LF	BACK PULL FIBER OPTIC CABLE
12	EA	SIGN FOR SIGNALS
6	EA	TYPE II PEDESTAL WITH FOUNDATION
1	EA	CONTROLLERS WITH CABINET (*****) (TYPE 2070LX, BASE MOUNTED)
17	EA	DETECTOR CARD (TYPE 170)
1	EA	CABINET BASE EXTENDER
1	EA	GENERIC SIGNAL ITEM 2070LX CONTROLLER
1	EA	GENERIC SIGNAL ITEM ETHERNET EDGE SWITCH
2	EA	GENERIC SIGNAL ITEM REMOVE EXISTING JUNCTION BOX

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260120

009

CONTRACT ID : C205132

BP12.R002.3

DIV OFFICE SHELBY

LENGTH = 0.275 MI

COUNTY : CLEVELAND

GRADING, DRAINAGE, PAVING, AND STRUCTURES.

DBE GOAL

COMPLETION DATE : NOV 11, 2028

BRIDGE #220075 ON NC-226 (POLKVILLE ROAD) OVER HINTON CREEK.

ROADWAY ITEMS

			4	EA	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III)
Lump Sum	LS	MOBILIZATION			
Lump Sum	LS	CONSTRUCTION SURVEYING	4	EA	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TL-3)
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING			
450	CY	UNDERCUT EXCAVATION	5	EA	TEMPORARY ADDITIONAL GUARDRAIL POSTS
Lump Sum	LS	GRADING	10	TON	RIP RAP, CLASS I
31,000	CY	BORROW EXCAVATION	640	TON	RIP RAP, CLASS II
200	CY	SELECT GRANULAR MATERIAL	280	TON	RIP RAP, CLASS B
200	SY	GEOTEXTILE FOR SOIL STABILIZATION	2,825	SY	GEOTEXTILE FOR DRAINAGE
Lump Sum	LS	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION 18+04.74 -L-	2	EA	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)
70	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	2	EA	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (E)
200	SY	FOUNDATION CONDITIONING GEOTEXTILE			
80	LF	15" DRAINAGE PIPE	70	SF	WORK ZONE SIGNS (STATIONARY)
48	LF	18" DRAINAGE PIPE	330	SF	WORK ZONE SIGNS (PORTABLE)
60	LF	24" RC PIPE CULVERTS, CLASS III	190	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
260	LF	15" RC PIPE CULVERTS, CLASS IV	70	EA	DRUMS
128	LF	15" CS PIPE CULVERTS, 0.064" THICK	72	LF	BARRICADES (TYPE III)
6	EA	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	60	DAY	FLAGGER
70	LF	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (24", 0.500")	40	EA	TEMPORARY RAISED PAVEMENT MARKERS
70	LF	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (24", 0.500")	6,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
252	LF	PIPE REMOVAL	14,200	LF	PAINT PAVEMENT MARKING LINES (6")
100	CY	SHALLOW UNDERCUT	1,200	LF	REMOVAL OF PAVEMENT MARKING LINES (6")
200	TON	CLASS IV SUBGRADE STABILIZATION	20	EA	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS
500	SY	GEOTEXTILE FOR SUBGRADE STABILIZATION	7,855	LF	TEMPORARY SILT FENCE
1,518	TON	AGGREGATE BASE COURSE	245	TON	STONE FOR EROSION CONTROL, CLASS A
200	TON	INCIDENTAL STONE BASE	1,165	TON	STONE FOR EROSION CONTROL, CLASS B
1,310	GAL	PRIME COAT	750	TON	SEDIMENT CONTROL STONE
940	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	9	ACR	TEMPORARY MULCHING
350	SY	INCIDENTAL MILLING	500	LB	SEED FOR TEMPORARY SEEDING
750	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	2.5	TON	FERTILIZER FOR TEMPORARY SEEDING
760	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	770	LF	TEMPORARY SLOPE DRAINS
1,260	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	260	LF	SAFETY FENCE
145	TON	ASPHALT BINDER FOR PLANT MIX	2,000	CY	SILT EXCAVATION
44.8	CY	SUBDRAIN EXCAVATION	10,050	SY	MATTING FOR EROSION CONTROL
200	SY	GEOTEXTILE FOR SUBSURFACE DRAINS	100	SY	COIR FIBER MAT
33.6	CY	SUBDRAIN COARSE AGGREGATE	835	LF	1/4" HARDWARE CLOTH
200	LF	6" PERFORATED SUBDRAIN PIPE	75	LF	*** TEMPORARY PIPE (24")
1	EA	SUBDRAIN PIPE OUTLET	230	SY	FLOATING TURBIDITY CURTAIN
6	LF	6" OUTLET PIPE	9	EA	SPECIAL STILLING BASINS
1.5	CY	ENDWALLS	265	LB	FLOCCULANT
16	CY	FLOWABLE FILL	50	LF	COIR FIBER BAFFLE
8	EA	MASONRY DRAINAGE STRUCTURES	9	ACR	SEEDING & MULCHING
7	EA	FRAME WITH TWO GRATES, STD 840.29	6	ACR	MOWING
710	LF	SHOULDER BERM GUTTER	100	LB	SEED FOR REPAIR SEEDING
800	LF	STEEL BEAM GUARDRAIL	0.25	TON	FERTILIZER FOR REPAIR SEEDING
5	EA	ADDITIONAL GUARDRAIL POSTS	200	LB	SEED FOR SUPPLEMENTAL SEEDING
4	EA	GUARDRAIL END UNITS, TYPE TL-3	5.5	TON	FERTILIZER TOPDRESSING
4	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77	55	LF	IMPERVIOUS DIKE
875	LF	TEMPORARY STEEL BEAM GUARDRAIL	10	MHR	SPECIALIZED HAND MOWING
			4	MHR	MANUAL LITTER REMOVAL
			1	TON	LITTER DISPOSAL

75	EA	RESPONSE FOR EROSION CONTROL
1	EA	CONCRETE WASHOUT STRUCTURE
1	ACR	REFORESTATION
6	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT STRUCTURE ITEMS
Lump Sum	LS	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (18+04.74 -L-)
Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+04.74 -L-)
Lump Sum	LS	ASBESTOS ASSESSMENT
80.5	LF	3'-6" DIA DRILLED PIERS IN SOIL
28	LF	3'-6" DIA DRILLED PIERS NOT IN SOIL
2	EA	CSL TESTING
Lump Sum	LS	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18+04.74 -L-)
6,280	SF	REINFORCED CONCRETE DECK SLAB
6,145	SF	GROOVING BRIDGE FLOORS
111.8	CY	CLASS A CONCRETE (BRIDGE)
Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (18+04.74 -L-)
25,108	LB	REINFORCING STEEL (BRIDGE)
3,264	LB	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)
628.17	LF	45" PRESTRESSED CONCRETE GIRDERS
12	EA	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)
435	LF	HP 12 X 53 STEEL PILES
1	EA	DYNAMIC PILE TESTING
316.55	LF	CONCRETE BARRIER RAIL
1,040	TON	RIP RAP CLASS II (2'-0" THICK)
1,154	SY	GEOTEXTILE FOR DRAINAGE
Lump Sum	LS	ELASTOMERIC BEARINGS