



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

January 14, 2025

Addendum No. 2

RE: Contract # C204992

WBS # 50205.3.4

STATE FUNDED

Hoke County (R-5709C)

NC-211 FROM NORTH OF SR-1225 (ASHEMONT RD) TO EAST OF SR-1244
(W PALMER ST)/SR-1311 (MOCKINGBIRD HILL RD)

January 21, 2025 Letting

To Whom It May Concern:

Reference is made to the proposal furnished to you on this project.

The following revisions have been made to the proposal.

Page No.	Revision
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 01-14-2025".

Please void the above listed Page in your proposal and staple the revised Page thereto.

On the item sheets the following pay item revision has been made:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0281-7481260000-N SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	1 EACH	4 EACH

The Contractor's bid must include this pay item revision.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

Website: www.ncdot.gov

The electronic bidding file has been updated to reflect this revision. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

Signed by:

52C46046381F443...

Ronald E. Davenport, Jr., PE
State Contract Officer

RED/cms
Attachments

cc: Mr. Wiley W. Jones III, PE
Mr. Reuben Blakley, PE
Mr. Ken Kennedy, PE
Mr. Malcolm Bell

Mr. Forrest Dungan, PE
Ms. Jaci Kincaid
Mr. Jon Weathersbee, PE
Project File (2)

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No.2 DATED 01-14-2025

DATE AND TIME OF BID OPENING: **Jan 21, 2025 AT 02:00 PM**

CONTRACT ID C204992
WBS 50205.3.4

FEDERAL-AID NO. STATE FUNDED
COUNTY HOKE
T.I.P NO. R-5709C
MILES 9.621
ROUTE NO. NC-211
LOCATION NC-211 FROM NORTH OF SR-1225 (ASHEMONT RD) TO EAST OF SR-1244
 (W PALMER ST)/SR-1311 (MOCKINGBIRD HILL RD).

TYPE OF WORK GRADING, DRAINAGE, PAVING, AND SIGNALS.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	4 ACR		
0004	0015000000-N	205	SEALING ABANDONED WELLS	3 EA		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	156,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	39,700 CY		
0007	0106000000-E	230	BORROW EXCAVATION	872,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10,920 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	620 LF		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	124,430 SY		
0011	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	20,370 SY		
0012	0192000000-N	260	PROOF ROLLING	100 HR		
0013	0194000000-E	265	SELECT GRANULAR MATERIAL, CLASS III	16,697 CY		
0014	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	16,575 SY		
0015	0199000000-E	SP	TEMPORARY SHORING	2,340 SF		
0016	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	75 TON		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	6,729 TON		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	68,976 SY		
0019	0335000000-E	305	*** DRAINAGE PIPE (72")	56 LF		
0020	0335200000-E	305	15" DRAINAGE PIPE	4,016 LF		
0021	0335300000-E	305	18" DRAINAGE PIPE	1,292 LF		
0022	0335400000-E	305	24" DRAINAGE PIPE	644 LF		
0023	0335500000-E	305	30" DRAINAGE PIPE	212 LF		
0024	0335600000-E	305	36" DRAINAGE PIPE	232 LF		
0025	0335800000-E	305	48" DRAINAGE PIPE	28 LF		
0026	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	8 EA		
0027	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (18")	4 EA		
0028	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,520 LF		
0029	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,788 LF		
0030	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,420 LF		
0031	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	608 LF		
0032	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	2,052 LF		
0033	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	688 LF		
0034	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	248 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	16 LF		
0036	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	448 LF		
0037	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	156 LF		
0038	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	72 LF		
0039	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	132 LF		
0040	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (54")	116 LF		
0041	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (60")	396 LF		
0042	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	464 LF		
0043	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	860 LF		
0044	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	352 LF		
0045	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	412 LF		
0046	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	1,392 LF		
0047	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	860 LF		
0048	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (15")	712 LF		
0049	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (24")	148 LF		
0050	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (36")	104 LF		
0051	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (42")	96 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (48")	172 LF		
0053	0536000000-E	310	**** HDPE PIPE CULVERTS (6")	36 LF		
0054	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (30", 0.500")	36 LF		
0055	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (36", 0.500")	108 LF		
0056	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (42", 0.500")	290 LF		
0057	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (48", 0.625")	190 LF		
0058	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (54", 0.750")	136 LF		
0059	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (60", 0.875")	352 LF		
0060	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (72", 1.000")	52 LF		
0061	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (30", 0.500")	36 LF		
0062	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (36", 0.500")	108 LF		
0063	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (42", 0.500")	290 LF		
0064	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (48", 0.625")	190 LF		
0065	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (54", 0.750")	136 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0066	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (60", 0.875")	352 LF		
0067	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (72", 1.000")	52 LF		
0068	0995000000-E	340	PIPE REMOVAL	6,184 LF		
0069	0996000000-N	350	PIPE CLEAN OUT	2 EA		
0070	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0071	1099500000-E	505	SHALLOW UNDERCUT	3,950 CY		
0072	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	11,250 TON		
0073	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	16,650 SY		
0074	1121000000-E	520	AGGREGATE BASE COURSE	154,840 TON		
0075	1220000000-E	545	INCIDENTAL STONE BASE	6,190 TON		
0076	1275000000-E	600	PRIME COAT	118,710 GAL		
0077	1330000000-E	607	INCIDENTAL MILLING	2,340 SY		
0078	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	39,170 TON		
0079	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	102,150 TON		
0080	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,800 TON		
0081	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	88,950 TON		
0082	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	12,165 TON		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0083	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	953 TON		
0084	1891000000-E	SP	GENERIC PAVING ITEM 12" JOINTED CONCRETE TRUCK APRON	460 SY		
0085	2000000000-N	806	RIGHT-OF-WAY MARKERS	624 EA		
0086	2022000000-E	815	SUBDRAIN EXCAVATION	5,914 CY		
0087	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	17,600 SY		
0088	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	2,957 CY		
0089	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	17,600 LF		
0090	2070000000-N	815	SUBDRAIN PIPE OUTLET	36 EA		
0091	2077000000-E	815	6" OUTLET PIPE	216 LF		
0092	2209000000-E	838	ENDWALLS	115.3 CY		
0093	2220000000-E	838	REINFORCED ENDWALLS	59.8 CY		
0094	2253000000-E	840	PIPE COLLARS	19.35 CY		
0095	2275000000-E	SP	FLOWABLE FILL	470 CY		
0096	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	265 EA		
0097	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	39.46 CY		
0098	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	197.4 LF		
0099	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0100	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	32 EA		
0101	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	80 EA		
0102	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	40 EA		
0103	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	14 EA		
0104	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0105	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	18 EA		
0106	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	18 EA		
0107	2396000000-N	840	FRAME WITH COVER, STD 840.54	11 EA		
0108	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	47 EA		
0109	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	44 EA		
0110	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	1,000 LF		
0111	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	6,280 LF		
0112	2556000000-E	846	SHOULDER BERM GUTTER	6,910 LF		
0113	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,030 LF		
0114	2591000000-E	848	4" CONCRETE SIDEWALK	1,480 SY		
0115	2605000000-N	848	CONCRETE CURB RAMPS	2 EA		
0116	2612000000-E	848	6" CONCRETE DRIVEWAY	1,048 SY		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0117	2619000000-E	850	4" CONCRETE PAVED DITCH	22 SY		
0118	2627000000-E	852	4" CONCRETE ISLAND COVER	600 SY		
0119	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	9,390 SY		
0120	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	6 EA		
0121	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0122	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0123	3030000000-E	862	STEEL BEAM GUARDRAIL	7,600 LF		
0124	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	430 LF		
0125	3105000000-N	862	STEEL BEAM GUARDRAIL TERMINAL SECTIONS	2 EA		
0126	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0127	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	10 EA		
0128	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	12 EA		
0129	3360000000-E	863	REMOVE EXISTING GUARDRAIL	5,850 LF		
0130	3389150000-N	862	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TL-3)	1 EA		
0131	3435000000-N	SP	GENERIC GUARDRAIL ITEM STEEL BOLLARDS	4 EA		
0132	3575000000-E	SP	GENERIC FENCING ITEM WILDLIFE FENCE WITH POSTS	5,410 LF		
0133	3628000000-E	876	RIP RAP, CLASS I	740 TON		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0134	3635000000-E	876	RIP RAP, CLASS II	90 TON		
0135	3642000000-E	876	RIP RAP, CLASS A	10 TON		
0136	3649000000-E	876	RIP RAP, CLASS B	8,160 TON		
0137	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	24,070 SY		
0138	3678000000-E	SP	GENERIC EROSION CONTROL ITEM TIED CONCRETE BLOCK MAT	17,450 SF		
0139	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	5,470 LF		
0140	4096000000-N	904	SIGN ERECTION, TYPE D	12 EA		
0141	4102000000-N	904	SIGN ERECTION, TYPE E	244 EA		
0142	4108000000-N	904	SIGN ERECTION, TYPE F	43 EA		
0143	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)	11 EA		
0144	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	136 EA		
0145	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	11 EA		
0146	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	3,508 SF		
0147	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	745 SF		
0148	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	834 SF		
0149	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0150	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0151	4430000000-N	1130	DRUMS	1,000 EA		
0152	4434000000-N	1140	SEQUENTIAL FLASHING WARNING LIGHTS	26 EA		
0153	4435000000-N	1135	CONES	300 EA		
0154	4445000000-E	1145	BARRICADES (TYPE III)	2,104 LF		
0155	4447000000-E	SP	PEDESTRIAN CHANNELIZING DEVICES	16 LF		
0156	4455000000-N	1150	FLAGGER	480 DAY		
0157	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		
0158	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	4 EA		
0159	4480000000-N	1165	TMA	2 EA		
0160	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,260 LF		
0161	4500000000-E	1170	REMOVE AND RESET PORTABLE CONCRETE BARRIER	1,080 LF		
0162	4510000000-N	1190	LAW ENFORCEMENT	24 HR		
0163	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	3,477 EA		
0164	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	40,204 LF		
0165	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	243,038 LF		
0166	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	128 LF		
0167	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	32,778 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0168	4704000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)	240 LF		
0169	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	1,163 LF		
0170	4720000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	26 EA		
0171	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	211 EA		
0172	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	938,378 LF		
0173	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	67,470 LF		
0174	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	23,208 LF		
0175	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	720 LF		
0176	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	6,910 LF		
0177	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	60 EA		
0178	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	516 EA		
0179	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	59,666 LF		
0180	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	53 LF		
0181	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	2,335 LF		
0182	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	416 LF		
0183	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	55 EA		
0184	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM YIELD LINE THERMOPLASTIC PAVEMENT MARKING (24", 90 MILS)	132 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0185	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,032 EA		
0186	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	2,820 LF		
0187	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (IG25)	7 EA		
0188	5325600000-E	1510	6" WATER LINE	2,291 LF		
0189	5325800000-E	1510	8" WATER LINE	11,650 LF		
0190	5326200000-E	1510	12" WATER LINE	40,207 LF		
0191	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	41,150 LB		
0192	5540000000-E	1515	6" VALVE	55 EA		
0193	5546000000-E	1515	8" VALVE	28 EA		
0194	5558000000-E	1515	12" VALVE	45 EA		
0195	5562000000-E	1515	*** INSERTION VALVE (6")	5 EA		
0196	5562000000-E	1515	*** INSERTION VALVE (8")	1 EA		
0197	5643100000-E	1515	3/4" WATER METER	39 EA		
0198	5649000000-N	1515	RECONNECT WATER METER	37 EA		
0199	5666000000-N	1515	FIRE HYDRANT	41 EA		
0200	5673000000-E	1515	FIRE HYDRANT LEG	400 LF		
0201	5686000000-E	1515	*** WATER SERVICE LINE (1")	650 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0202	5686000000-E	1515	*** WATER SERVICE LINE (3/4")	5,889 LF		
0203	5691300000-E	1520	8" SANITARY GRAVITY SEWER	1,941 LF		
0204	5691400000-E	1520	10" SANITARY GRAVITY SEWER	410 LF		
0205	5775000000-E	1525	4' DIA UTILITY MANHOLE	12 EA		
0206	5781000000-E	1525	UTILITY MANHOLE WALL 4' DIA	48.51 LF		
0207	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,978 LF		
0208	5801000000-E	1530	ABANDON 8" UTILITY PIPE	53,878 LF		
0209	5802000000-E	1530	ABANDON 10" UTILITY PIPE	345 LF		
0210	5804000000-E	1530	ABANDON 12" UTILITY PIPE	270 LF		
0211	5815000000-N	1530	REMOVE WATER METER	68 EA		
0212	5815500000-N	1530	REMOVE FIRE HYDRANT	36 EA		
0213	5816000000-N	1530	ABANDON UTILITY MANHOLE	11 EA		
0214	5835600000-E	1540	12" ENCASEMENT PIPE	320 LF		
0215	5835700000-E	1540	16" ENCASEMENT PIPE	286 LF		
0216	5835900000-E	1540	20" ENCASEMENT PIPE	38 LF		
0217	5836000000-E	1540	24" ENCASEMENT PIPE	1,569 LF		
0218	5872500000-E	1550	BORE AND JACK OF *** (12")	289 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0219	5872500000-E	1550	BORE AND JACK OF *** (16")	286 LF		
0220	5872500000-E	1550	BORE AND JACK OF *** (20")	113 LF		
0221	5872500000-E	1550	BORE AND JACK OF *** (24")	1,508 LF		
0222	5882000000-N	SP	GENERIC UTILITY ITEM 12" PRESSURE REDUCING VALVE ASSEMBLY	2 EA		
0223	5882000000-N	SP	GENERIC UTILITY ITEM ABANDON METER VAULT	1 EA		
0224	5882000000-N	SP	GENERIC UTILITY ITEM ABANDON PRV VAULT	1 EA		
0225	6000000000-E	1605	TEMPORARY SILT FENCE	62,500 LF		
0226	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	6,850 TON		
0227	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	16,750 TON		
0228	6012000000-E	1610	SEDIMENT CONTROL STONE	12,500 TON		
0229	6015000000-E	1615	TEMPORARY MULCHING	600 ACR		
0230	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	24,200 LB		
0231	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	121 TON		
0232	6024000000-E	1622	TEMPORARY SLOPE DRAINS	13,300 LF		
0233	6029000000-E	SP	SAFETY FENCE	1,600 LF		
0234	6030000000-E	1630	SILT EXCAVATION	61,400 CY		
0235	6036000000-E	1631	MATTING FOR EROSION CONTROL	295,500 SY		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0236	6037000000-E	1629	COIR FIBER MAT	450 SY		
0237	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	6,000 SY		
0238	6042000000-E	1632	1/4" HARDWARE CLOTH	12,500 LF		
0239	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	2,750 SY		
0240	6045000000-E	SP	*** TEMPORARY PIPE (24")	70 LF		
0241	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0242	6071002000-E	1642	FLOCCULANT	18,000 LB		
0243	6071012000-E	1642	COIR FIBER WATTLE	20,625 LF		
0244	6071013000-E	1642	WATTLE BARRIER	1,375 LF		
0245	6071030000-E	1640	COIR FIBER BAFFLE	22,700 LF		
0246	6071050000-E	1644	*** SKIMMER (1-1/2")	12 EA		
0247	6071050000-E	1644	*** SKIMMER (2")	8 EA		
0248	6071050000-E	1644	*** SKIMMER (2-1/2")	6 EA		
0249	6084000000-E	1660	SEEDING & MULCHING	400 ACR		
0250	6087000000-E	1660	MOWING	500 ACR		
0251	6090000000-E	1661	SEED FOR REPAIR SEEDING	6,500 LB		
0252	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	18 TON		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0253	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	9,000 LB		
0254	6108000000-E	1665	FERTILIZER TOPDRESSING	350 TON		
0255	6111000000-E	SP	IMPERVIOUS DIKE	460 LF		
0256	6114500000-N	1667	SPECIALIZED HAND MOWING	75 MHR		
0257	6114800000-N	SP	MANUAL LITTER REMOVAL	250 MHR		
0258	6114900000-E	SP	LITTER DISPOSAL	18.75 TON		
0259	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	190 EA		
0260	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	20 EA		
0261	6120000000-E	SP	CULVERT DIVERSION CHANNEL	15 CY		
0262	6674000000-N	SP	GENERIC PLANTING ITEM (LS) REMOVAL OF JAPANESE KNOTWEED	Lump Sum	L.S.	
0263	7060000000-E	1705	SIGNAL CABLE	3,950 LF		
0264	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	26 EA		
0265	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	4 EA		
0266	7204000000-N	1705	LOUVER	2 EA		
0267	7264000000-E	1710	MESSENGER CABLE (3/8")	1,050 LF		
0268	7288000000-E	1715	PAVED TRENCHING (***** (1, 2"))	25 LF		
0269	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	2,100 LF		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0270	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2"))	500 LF		
0271	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	14 EA		
0272	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	12 EA		
0273	7360000000-N	1720	WOOD POLE	4 EA		
0274	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0275	7408000000-E	1722	1" RISER WITH WEATHERHEAD	5 EA		
0276	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
0277	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,875 LF		
0278	7456100000-E	1726	LEAD-IN CABLE (14-2)	6,175 LF		
0279	7481000000-N	SP	SITE SURVEY	4 EA		
0280	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	18 EA		
0281	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	4 EA		
0282	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4 EA		
0283	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	2 EA		
0284	7613000000-N	SP	SOIL TEST	6 EA		
0285	7614100000-E	SP	DRILLED PIER FOUNDATION	48 CY		
0286	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	2 EA		

County: HOKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0287	7636000000-N	1745	SIGN FOR SIGNALS	9 EA		
0288	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	2 EA		
0289	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4 EA		
0290	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (2070LX, BASE MOUNTED)	4 EA		
0291	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (2070LX, POLE MOUNTED)	1 EA		
0292	7744000000-N	1751	DETECTOR CARD (TYPE 170)	15 EA		
0293	7901000000-N	1753	CABINET BASE EXTENDER	4 EA		
0294	7980000000-N	SP	GENERIC SIGNAL ITEM LUMINAIRE ARM FOR TEMPORARY VIDEO SYSTEM	12 EA		
0295	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	

1426/Jan13/Q4306218.57/D1104361057000/E295

Total Amount Of Bid For Entire Project :