

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

JOSH STEIN GOVERNOR J.R. "JOEY" HOPKINS

June 26, 2025

Addendum No. 1

RE: Contract # C205075 WBS # 17BP.2.C.13, 47482.3.1 STATE FUNDED, FEDERAL AID NO. 4748201 Carteret County (17BP.2.C.13, U-6058) NC-101 FROM S OF SR-1170 (W BEAUFORT RD) TO N OF US-70 AND SR-1493 (LIVE OAK STREET) AT NC-101.

July 15, 2025 Letting

To Whom It May Concern:

Reference is made to the plans and proposal furnished to you on this project.

The following revisions have been made to the Signing Plans.

Sheet No.	Revision
SIGN-1	General Notes Section and Summary of Quantities Section
	updated. Removed general note regarding Department
	notification. Added quantity information for contractor
	furnished signs.

Please void the above listed Sheet in your plans and staple the revised Sheet thereto.

The contract will be prepared accordingly.

Sincerely,

Ronald E. Davenport, Jr.

Ronald E. Davenport, Jr., PE State Contract Officer

RED/jcm Attachments

Website: www.ncdot.gov

cc: Mr. Wiley W. Jones III, PE Mr. Forrest Dungan, PE

Ms. Mary Beth Houston, PE Ms. Jaci Kincaid

Mr. Ken Kennedy, PE Mr. Jon Weathersbee, PE

Mr. Malcolm Bell Project File (2)

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN CARTERET COUNTY

LOCATION: SINGLE LANE ROUNDABOUT AT THE INTERSECTION OF SR 1493 (LIVE OAK STREET) AND NC 101 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

U-6058

SHEET NO.

SIGN-1

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	<u>TITLE</u>
901.50	ARROWS AND SHIELDS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.20	SECONDARY SIGN MOUNTING
904.30	SUPPLEMENTAL SIGN MOUNTING
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS
910.40	SINGLE LANE ROUNDABOUT SIGNING
910D40	SINGLE LANE URBAN ROUNDABOUT SIGNING, WITH PEDESTRIANS

SUMMARY OF QUANTITIES ITEM DESCRIPTION ITEM NO. QUANTITY UNIT DESC. SECT. NO. NO. 64.25 4025000000 CONTRACTOR FURNISHED, TYPE D SIGN 4025000000 CONTRACTOR FURNISHED, TYPE E SIGN 210.27 901 CONTRACTOR FURNISHED, TYPE F SIGN 4025000000 30.75 901 4072000000 SUPPORTS, 3 LB STEEL U-CHANNEL 735 LF 4096000000 SIGN ERECTION, TYPE D EΑ 4102000000 SIGN ERECTION, TYPE E EΑ SIGN ERECTION, TYPE F 4108000000 EΑ 4116100000 SIGN ERECTION, RELOCATE SIGN TYPE E EΑ DISPOSAL OF SIGN SYSTEM, U-CHANNEL EΑ 4155000000 DISPOSAL OF SIGN SYSTEM, WOOD EΑ 15 DISPOSAL OF SIGN SYSTEM ON SPAN WIRE EΑ 4360000000

PROJECT NOTES

- 1. DISPOSAL OF SIGN SYSTEM, U-CHANNEL
- 2. DISPOSAL OF SIGN SYSTEM, OVERHEAD ON WIRE
- 3. SIGN ERECTION, RELOCATE SIGN TYPE E 4. DISPOSAL OF SIGN SYSTEM, WOOD

GENERAL NOTES

- ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- ALL EXISTING SIGNS ON "U" CHANNEL & WOOD POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE GRADE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

SHEET NO. DESCRIPTION SIGN-1 SIGNING PLAN TITLE SHEET SIGN-2 TYPE D SIGNS SIGN-3 TYPE E & F SIGNS SIGN-4-6 EXISTING SIGNS SIGN-7-9 PROPOSED SIGNS

TRANSYSTEMS

1 Glenwood Avenue Raleigh, NC 27603 Tel:919.789.9977 Fax:919.789.9591 License: F-0453