



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

October 10, 2025

Addendum No. 1

RE: Contract # C205093

WBS # 48647.3.1

STATE FUNDED

Davie County (U-6187)

NEW ROUTE FROM SR-1630 (BALTIMORE RD) TO I-40

October 21, 2025 Letting

To Whom It May Concern:

Reference is made to the plans and proposal furnished to you on this project.

The following revisions have been made to the Roadway Plans.

Sheet No.	Revision
3D-4	○ Top elevation for 2GI 0861 revised ○ Structure depth for 2GI 0861 revised ○ Top elevation for JB w/MH 0862 revised ○ Structure depth for JB w/MH 0862 revised ○ Top elevation for JB w/MH 0869 revised ○ Structure depth for JB w/MH 0869 revised ○ Sheet total quantities for 5'-10' structure depth revised ○ Sheet total quantities for 10' and above structure depth revised
3D-6	○ Project total quantities for 5'-10' structure depth revised ○ Project total quantities for 10' and above structure depth revised

Please void the above listed Sheets in your plans and staple the revised Sheets thereto.

The following revisions have been made to the proposal.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

Page No.	Revision
Proposal Cover	Note added that reads “Includes Addendum No. 1 Dated 10-10-2025”.
G-20 & G-23	The Project Special Provision entitled MINORITY BUSINESS ENTERPRISE AND WOMEN BUSINESS ENTERPRISE has been revised.

Please void the above listed Pages in your proposal and staple the revised Pages thereto.

On the item sheets the following pay item revisions have been made:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0093- 2308000000-E 840	MASONRY DRAINAGE STRUCTURES	153.2 LF	107.2 LF
0303- 8130000000-N 414	BOX CULVERT EXCAVATION, STA 30+32.50 -Y2-	NEW ITEM	LUMP SUM

The Contractor’s bid must include these pay item revisions.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

Signed by:

52C46046381F443...

Ronald E. Davenport, Jr., PE
State Contract Officer

RED/jjr
Attachments

cc: Mr. Wiley W. Jones III, PE
Mr. John P. Rhyne, PE
Mr. Ken Kennedy, PE
Mr. Malcolm Bell

Mr. Forrest Dungan, PE
Ms. Jaci Kincaid
Mr. Jon Weathersbee, PE
Project File (2)

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No.1 DATED 10-10-2025

DATE AND TIME OF BID OPENING: **Oct 21, 2025 AT 02:00 PM**

CONTRACT ID C205093
WBS 48647.3.1

FEDERAL-AID NO. STATE FUNDED
COUNTY DAVIE
T.I.P NO. U-6187
MILES 1.184
ROUTE NO. SR-1630
LOCATION NEW ROUTE FROM SR-1630 (BALTIMORE RD) TO I-40.

TYPE OF WORK GRADING, DRAINAGE, PAVING, SIGNALS, AND STRUCTURES.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY & STRUCTURE PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

PAYOUT SCHEDULE:

(1-19-10) (Rev. 1-17-12)

108

SP1 G57

Submit an Anticipated Monthly Payout Schedule prior to beginning construction. The Anticipated Monthly Payout Schedule will be used by the Department to monitor funding levels for this project. Include a monthly percentage breakdown (in terms of the total contract amount) of the work anticipated to be completed. The schedule should begin with the date the Contractor plans to begin construction and end with the anticipated completion date. Submit updates of the Anticipated Monthly Payout Schedule on March 15, June 15, September 15, and December 15 of each calendar year until project acceptance. Submit the original Anticipated Monthly Payout Schedule and all subsequent updates to the Resident Engineer with a copy to the State Construction Engineer at 1 South Wilmington Street, 1543 Mail Service Center, Raleigh, NC 27699-1543.

SCHEDULE OF ESTIMATED COMPLETION PROGRESS:

(7-15-08)(Rev. 6-17-25)

108-2

SP1 G58

The Contractor's attention is directed to the Standard Special Provision entitled *Availability of Funds Termination of Contracts* included elsewhere in this proposal. The Department of Transportation's schedule of estimated completion progress for this project as required by that Standard Special Provision is as follows:

	<u>Fiscal Year</u>	<u>Progress (% of Dollar Value)</u>
2026	(7/01/25 - 6/30/26)	22% of Total Amount Bid
2027	(7/01/26 - 6/30/27)	33% of Total Amount Bid
2028	(7/01/27 - 6/30/28)	28% of Total Amount Bid
2029	(7/01/28 - 6/30/29)	17% of Total Amount Bid

The Contractor shall also furnish his own progress schedule in accordance with Article 108-2 of the *Standard Specifications*. Any acceleration of the progress as shown by the Contractor's progress schedule over the progress as shown above shall be subject to the approval of the Engineer.

MINORITY BUSINESS ENTERPRISE AND WOMEN BUSINESS ENTERPRISE:

(10-16-07)(Rev. 10-21-25)

102-15(J)

SP1 G66

Description

The purpose of this Special Provision is to carry out the North Carolina Department of Transportation's policy of ensuring nondiscrimination in the award and administration of contracts financed in whole or in part with State funds.

Definitions

Additional MBE/WBE Subcontractors - Any MBE/WBE submitted at the time of bid that will not be used to meet the Combined MBE /WBE Goal. No submittal of a Letter of Intent is required.

Combined MBE/WBE Goal: A portion of the total contract, expressed as a percentage that is to be performed by committed MBE/WBE subcontractors.

<http://connect.ncdot.gov/business/SmallBusiness/Documents/DBE%20Subcontractor%20Quote%20Comparison%20Example.xls>

DBE Regular Dealer/Distributor Affirmation Form – Form is used to make a preliminary counting determination for each DBE listed as a regular dealer or distributor to assess its eligibility for 60 or 40 percent credit, respectively of the cost of materials or supplies based on its demonstrated capacity and intent to perform as a regular dealer or distributor, as defined in section 49 CFR 26.55 under the contract at issue. A Contractor will submit the completed form with the Letter of Intent.

<https://connect.ncdot.gov/projects/construction/Construction%20Forms/DBE%20Regular%20Dealer-Distributor%20Affirmation%20Form%20-%20USDOT%202024.pdf>

Combined MBE/WBE Goal

There is NO MBE/WBE Goal for this project.

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000720000-N	SP	FIELD OFFICE	36 MO		
0004	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM SURVEYING FOR MITIGATION	Lump Sum	L.S.	
0005	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0006	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0007	0022000000-E	225	UNCLASSIFIED EXCAVATION	228,500 CY		
0008	0036000000-E	225	UNDERCUT EXCAVATION	9,000 CY		
0009	0106000000-E	230	BORROW EXCAVATION	214,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	18,950 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	2,620 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	600 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	1,130 SY		
0014	0192000000-N	260	PROOF ROLLING	20 HR		
0015	0195000000-E	265	SELECT GRANULAR MATERIAL	8,220 CY		
0016	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	11,220 SY		
0017	0241000000-E	SP	GENERIC GRADING ITEM CULVERT LOAD TRANSFER MAT	4,360 SY		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0241000000-E	SP	GENERIC GRADING ITEM GEOTEXTILE FOR EMBANKMENT STABILIZATION, TYPE 5A	22,540 SY		
0019	0248000000-N	SP	GENERIC GRADING ITEM SITE GRADING FOR MITIGATION	Lump Sum	L.S.	
0020	0248000000-N	SP	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION 70+91.84 -L-	Lump Sum	L.S.	
0021	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	1,250 TON		
0022	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	3,940 SY		
0023	0342000000-E	310	*** SIDE DRAIN PIPE (30")	568 LF		
0024	0342000000-E	310	*** SIDE DRAIN PIPE (36")	764 LF		
0025	0343000000-E	310	15" SIDE DRAIN PIPE	1,904 LF		
0026	0344000000-E	310	18" SIDE DRAIN PIPE	300 LF		
0027	0345000000-E	310	24" SIDE DRAIN PIPE	736 LF		
0028	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	22 EA		
0029	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (18")	10 EA		
0030	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (30")	2 EA		
0031	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	140 LF		
0032	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (54")	28 LF		
0033	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	3,940 LF		
0034	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	1,296 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	368 LF		
0036	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	1,216 LF		
0037	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	332 LF		
0038	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	200 LF		
0039	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	28 LF		
0040	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (18", 0.250")	58 LF		
0041	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (24", 0.375")	54 LF		
0042	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (30", 0.500")	58 LF		
0043	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (66", 0.938")	200 LF		
0044	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (18", 0.250")	58 LF		
0045	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (24", 0.375")	54 LF		
0046	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (30", 0.500")	58 LF		
0047	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (66", 0.938")	200 LF		
0048	0995000000-E	340	PIPE REMOVAL	1,740 LF		
0049	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0050	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	23,950 SY		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	1066000000-E	501	LIME FOR LIME TREATED SOIL	290 TON		
0052	1077000000-E	SP	#57 STONE	225 TON		
0053	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0054	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	1,000 TON		
0055	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0056	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	29,690 SY		
0057	1121000000-E	520	AGGREGATE BASE COURSE	24,000 TON		
0058	1176000000-E	542	SOIL CEMENT BASE	23,950 SY		
0059	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	671 TON		
0060	1209000000-E	543	ASPHALT CURING SEAL	7,190 GAL		
0061	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0062	1275000000-E	600	PRIME COAT	680 GAL		
0063	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	41,100 SY		
0064	1330000000-E	607	INCIDENTAL MILLING	1,010 SY		
0065	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,070 TON		
0066	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	14,560 TON		
0067	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,100 TON		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	7,090 TON		
0069	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,585 TON		
0070	1577000000-E	620	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	415 TON		
0071	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	270 TON		
0072	1841000000-E	665	GENERIC PAVING ITEM MILLED RUMBLE STRIPS (ASPHALT CONCRETE), (16")	7,030 LF		
0073	2000000000-N	806	RIGHT-OF-WAY MARKERS	122 EA		
0074	2020000000-N	806	CONTROL-OF-ACCESS MARKERS	12 EA		
0075	2022000000-E	815	SUBDRAIN EXCAVATION	340 CY		
0076	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	1,000 SY		
0077	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	170 CY		
0078	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0079	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
0080	2077000000-E	815	6" OUTLET PIPE	12 LF		
0081	2099000000-E	816	SHOULDER DRAIN	2,000 LF		
0082	2110000000-E	816	4" SHOULDER DRAIN PIPE	2,000 LF		
0083	2121000000-E	816	4" OUTLET PIPE FOR SHOULDER DRAINS	100 LF		
0084	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	10 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	2143000000-E	818	BLOTTING SAND	20 TON		
0086	2209000000-E	838	ENDWALLS	13 CY		
0087	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
0088	2253000000-E	840	PIPE COLLARS	5 CY		
0089	2264000000-E	840	PIPE PLUGS	1 CY		
0090	2275000000-E	SP	FLOWABLE FILL	212 CY		
0091	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	116 EA		
0092	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	3.833 CY		
0093	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	107.2 LF		
0094	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0095	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	27 EA		
0096	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	18 EA		
0097	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	26 EA		
0098	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
0099	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	22 EA		
0100	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0101	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0102	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	7 EA		
0103	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0104	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	13 EA		
0105	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	930 LF		
0106	2556000000-E	846	SHOULDER BERM GUTTER	5,610 LF		
0107	2619000000-E	850	4" CONCRETE PAVED DITCH	110 SY		
0108	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,860 SY		
0109	3030000000-E	862	STEEL BEAM GUARDRAIL	9,500 LF		
0110	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	400 LF		
0111	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0112	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	6 EA		
0113	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	11 EA		
0114	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	5 EA		
0115	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0116	3347000000-E	864	REMOVE & RESET EXISTING GUIDERAIL	135 LF		
0117	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,755 LF		
0118	3389500000-N	865	ADDITIONAL GUIDERAIL POSTS	5 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0119	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	2 EA		
0120	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	13,810 LF		
0121	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	837 EA		
0122	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	275 EA		
0123	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, ** OPENING (58", 12', 12')	7 EA		
0124	3628000000-E	876	RIP RAP, CLASS I	4,235 TON		
0125	3635000000-E	876	RIP RAP, CLASS II	1,015 TON		
0126	3642000000-E	876	RIP RAP, CLASS A	10 TON		
0127	3649000000-E	876	RIP RAP, CLASS B	1,600 TON		
0128	3651000000-E	SP	BOULDERS	430 TON		
0129	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	17,505 SY		
0130	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	4 CY		
0131	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0132	4057000000-E	SP	OVERHEAD FOOTING	17 CY		
0133	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	4,877 LB		
0134	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,636 LF		
0135	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	4080200000-E	903	SUPPORTS, STEEL SQUARE TUBE	91 LF		
0137	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0138	4102000000-N	904	SIGN ERECTION, TYPE E	56 EA		
0139	4108000000-N	904	SIGN ERECTION, TYPE F	17 EA		
0140	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	2 EA		
0141	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (B)	2 EA		
0142	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	7 EA		
0143	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	5 EA		
0144	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2 EA		
0145	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (A)	1 EA		
0146	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)	1 EA		
0147	4130000000-N	906	SUPPORTS, OVERHEAD SIGN STRUCTURE ***** (31+66 -Y2-)	Lump Sum	L.S.	
0148	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
0149	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	3 EA		
0150	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	14 EA		
0151	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0152	4360000000-N	SP	GENERIC SIGNING ITEM SUPPORTS, OMNI-DIRECTIONAL BREAKAWAY	7 EA		
0153	4402000000-E	SP	HIGH VISIBILITY STATIONARY SIGNS	610 SF		
0154	4407000000-E	SP	HIGH VISIBILITY PORTABLE SIGNS	624 SF		
0155	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	257 SF		
0156	4415000000-N	1115	FLASHING ARROW BOARD	10 EA		
0157	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	150 DAY		
0158	4424000000-N	SP	WORK ZONE PRESENCE LIGHTING	28 EA		
0159	4430000000-N	1130	DRUMS	235 EA		
0160	4432000000-N	SP	HIGH VISIBILITY DRUMS	235 EA		
0161	4434000000-N	1140	SEQUENTIAL FLASHING WARNING LIGHTS	48 EA		
0162	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
0163	4455000000-N	1150	FLAGGER	198 DAY		
0164	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0165	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	4 EA		
0166	4480000000-N	1165	TMA	7 EA		
0167	4485000000-E	1170	PORTABLE CONCRETE BARRIER	3,747 LF		
0168	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	4,651 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0169	4500000000-E	1170	REMOVE AND RESET PORTABLE CONCRETE BARRIER	7,692 LF		
0170	4505000000-E	1170	REMOVE & RESET PORTABLE CONCRETE BARRIER (ANCHORED)	600 LF		
0171	4510000000-N	1190	LAW ENFORCEMENT	160 HR		
0172	4516000000-N	1180	SKINNY DRUM	1,290 EA		
0173	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM CONNECTED LANE CLOSURE DEVICE	2 EA		
0174	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	600 EA		
0175	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	125,980 LF		
0176	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	128,440 LF		
0177	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,095 LF		
0178	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	8,440 LF		
0179	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	430 LF		
0180	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	20 EA		
0181	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	106 EA		
0182	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING LINES, (12", 90 MILS)	4,120 LF		
0183	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING LINES, (24", 90 MILS)	215 LF		
0184	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING LINES, (4", 90 MILS)	45,098 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0185	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING LINES, (6", 90 MILS)	31,990 LF		
0186	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING LINES, (8", 90 MILS)	1,547 LF		
0187	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM INTEGRATED MULTIPOLYMER PAVEMENT MARKING SYMBOLS, (90 MILS)	46 EA		
0188	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	344 EA		
0189	5325800000-E	1510	8" WATER LINE	3,532 LF		
0190	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	4,175 LB		
0191	5536000000-E	1515	2" VALVE	1 EA		
0192	5540000000-E	1515	6" VALVE	4 EA		
0193	5546000000-E	1515	8" VALVE	12 EA		
0194	5590000000-E	1515	*** COMBINATION AIR VALVE (1")	1 EA		
0195	5648000000-N	1515	RELOCATE WATER METER	15 EA		
0196	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0197	5666000000-N	1515	FIRE HYDRANT	4 EA		
0198	5673000000-E	1515	FIRE HYDRANT LEG	29 LF		
0199	5686500000-E	1515	WATER SERVICE LINE	640 LF		
0200	5709100000-E	1520	2" FORCE MAIN SEWER	123 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0201	5709200000-E	1520	4" FORCE MAIN SEWER	919 LF		
0202	5709300000-E	1520	6" FORCE MAIN SEWER	2,296 LF		
0203	5769000000-E	1520	DUCTILE IRON SEWER PIPE FITTINGS	755 LB		
0204	5775000000-E	1525	4' DIA UTILITY MANHOLE	1 EA		
0205	5798000000-E	1530	ABANDON *** UTILITY PIPE (2")	88 LF		
0206	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	784 LF		
0207	5800000000-E	1530	ABANDON 6" UTILITY PIPE	2,283 LF		
0208	5801000000-E	1530	ABANDON 8" UTILITY PIPE	3,493 LF		
0209	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		
0210	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0211	5835400000-E	1540	6" ENCASEMENT PIPE	85 LF		
0212	5835600000-E	1540	12" ENCASEMENT PIPE	86 LF		
0213	5835800000-E	1540	18" ENCASEMENT PIPE	661 LF		
0214	5872500000-E	1550	BORE AND JACK OF *** (18")	202 LF		
0215	5872500000-E	1550	BORE AND JACK OF *** (6")	85 LF		
0216	5882000000-N	SP	GENERIC UTILITY ITEM PRESSURE REGULATING VALVE WITH BYPASS	1 EA		
0217	6000000000-E	1605	TEMPORARY SILT FENCE	40,620 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0218	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,800 TON		
0219	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10,775 TON		
0220	6012000000-E	1610	SEDIMENT CONTROL STONE	6,205 TON		
0221	6015000000-E	1615	TEMPORARY MULCHING	144.5 ACR		
0222	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	6,200 LB		
0223	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	32.5 TON		
0224	6024000000-E	1622	TEMPORARY SLOPE DRAINS	4,000 LF		
0225	6029000000-E	SP	SAFETY FENCE	2,880 LF		
0226	6030000000-E	1630	SILT EXCAVATION	56,000 CY		
0227	6036000000-E	1631	MATting FOR EROSION CONTROL	127,135 SY		
0228	6037000000-E	1629	COIR FIBER MAT	11,575 SY		
0229	6042000000-E	1632	1/4" HARDWARE CLOTH	5,145 LF		
0230	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	900 SY		
0231	6045000000-E	SP	*** TEMPORARY PIPE (24")	290 LF		
0232	6046000000-E	1636	TEMPORARY PIPE FOR STREAM CROSSING	90 LF		
0233	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0234	6071002000-E	1642	FLOCCULANT	3,090 LB		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0235	6071030000-E	1640	COIR FIBER BAFFLE	6,685 LF		
0236	6071050000-E	1644	*** SKIMMER (1-1/2")	8 EA		
0237	6071050000-E	1644	*** SKIMMER (2")	12 EA		
0238	6071050000-E	1644	*** SKIMMER (2-1/2")	4 EA		
0239	6071050000-E	1644	*** SKIMMER (3")	1 EA		
0240	6084000000-E	1660	SEEDING & MULCHING	93 ACR		
0241	6087000000-E	1660	MOWING	96 ACR		
0242	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,500 LB		
0243	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	5 TON		
0244	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,175 LB		
0245	6108000000-E	1665	FERTILIZER TOPDRESSING	66 TON		
0246	6111000000-E	SP	IMPERVIOUS DIKE	508 LF		
0247	6114500000-N	1667	SPECIALIZED HAND MOWING	60 MHR		
0248	6114800000-N	SP	MANUAL LITTER REMOVAL	47 MHR		
0249	6114900000-E	SP	LITTER DISPOSAL	12 TON		
0250	6115000000-E	SP	MECHANICAL LITTER REMOVAL	5 SMI		
0251	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	175 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0252	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	3 EA		
0253	6120000000-E	SP	CULVERT DIVERSION CHANNEL	313 CY		
0254	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	15 EA		
0255	6133000000-N	SP	GENERIC EROSION CONTROL ITEM DIVERSION PUMPING	Lump Sum	L.S.	
0256	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	2.3 ACR		
0257	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	2.3 ACR		
0258	6138000000-E	SP	GENERIC EROSION CONTROL ITEM IMPERVIOUS SELECT MATERIAL	700 CY		
0259	6147000000-E	SP	GENERIC EROSION CONTROL ITEM BRUSH TOE STABILIZATION	604 LF		
0260	6150000000-E	SP	GENERIC EROSION CONTROL ITEM CHANNEL SUBSTRATE MATERIAL	37 TON		
0261	6645000000-N	SP	GENERIC PLANTING ITEM LIVE PLANT MATERIAL - 12" DIAMETER BUNDLES	315 EA		
0262	6900000000-E	SP	TOPSOIL	60 CY		
0263	7060000000-E	1705	SIGNAL CABLE	2,500 LF		
0264	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	5 EA		
0265	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	4 EA		
0266	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3 EA		
0267	7264000000-E	1710	MESSENGER CABLE (3/8")	600 LF		
0268	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	800 LF		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0269	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	50 LF		
0270	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	150 LF		
0271	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11 EA		
0272	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,000 LF		
0273	7456100000-E	1726	LEAD-IN CABLE (14-2)	2,500 LF		
0274	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4 EA		
0275	7613000000-N	SP	SOIL TEST	4 EA		
0276	7614100000-E	SP	DRILLED PIER FOUNDATION	24 CY		
0277	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0278	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0279	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (2070LX, BASE MOUNTED)	1 EA		
0280	7744000000-N	1751	DETECTOR CARD (TYPE 170)	9 EA		
0281	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
CULVERT ITEMS						
0282	8063000000-N	SP	PRECAST REINFORCED CONC BOX CULVERT AT STA ***** (66+15.50 -L-)	Lump Sum	L.S.	
0283	8130000000-N	414	BOX CULVERT EXCAVATION, STA ***** (66+15.50 -L-)	Lump Sum	L.S.	
0284	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	422 TON		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0285	8196000000-E	420	CLASS A CONCRETE (CULVERT)	62.9 CY		
0286	8245000000-E	425	REINFORCING STEEL (CULVERT)	8,210 LB		
0303	8130000000-N	414	BOX CULVERT EXCAVATION, STA ***** (30+32.50 -Y2-)	Lump Sum	L.S.	
WALL ITEMS						
0287	8892000000-E	SP	GENERIC STRUCTURE ITEM ARCHITECTURAL SURFACE TREATMENT (SOUND BARRIER WALL NO 1)	10,686 SF		
0288	8892000000-E	SP	GENERIC STRUCTURE ITEM SOUND BARRIER WALL	6,342 SF		
STRUCTURE ITEMS						
0289	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT NO ** AT STATION ***** (1, 70+91.84 -L-)	Lump Sum	L.S.	
0290	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	12,660 SF		
0291	8161000000-E	420	GROOVING BRIDGE FLOORS	13,740 SF		
0292	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	181.8 CY		
0293	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (70+91.84 -L-)	Lump Sum	L.S.	
0294	8217000000-E	425	REINFORCING STEEL (BRIDGE)	32,220 LB		
0295	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,724 LB		
0296	8278000000-E	430	FIB *** PRESTRESSED CONCRETE GIRDERS (63")	1,332.5 LF		
0297	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 14 X 73)	34 EA		

County: DAVIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0298	8384000000-E	450	HP 14 X 73 STEEL PILES	2,320 LF		
0299	8394000000-N	450	DYNAMIC PILE TESTING	1 EA		
0300	8503000000-E	460	CONCRETE BARRIER RAIL	446.2 LF		
0301	8531000000-E	462	4" SLOPE PROTECTION	580 SY		
0302	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

1259/Oct06/Q1599506.733/D1229238252000/E303

Total Amount Of Bid For Entire Project :

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)

LINE & STATION	OFFSET	STRUCTURE NUMBER		TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	MINIMUM REQUIRED SLOPE	Side Drain Pipe (RCP, CSP, CAAP, HDPE or PVC)																C. S. PIPE				R. C. PIPE CLASS IV				QUANTITIES FOR DRAINAGE STRUCTURES																FRAME, GRATES, AND HOOD				CONCRETE TRANSITIONAL SECTION		C.B. STD. 840.01 OR STD. 840.02																C.B. STD. 840.03				C.B. STD. 840.04 OR STD. 840.05				C.B. STD. 840.06				C.B. STD. 840.07				C.B. STD. 840.08				C.B. STD. 840.09				C.B. STD. 840.10				C.B. STD. 840.11				C.B. STD. 840.12				C.B. STD. 840.13				C.B. STD. 840.14				C.B. STD. 840.15				C.B. STD. 840.16				C.B. STD. 840.17				C.B. STD. 840.18				C.B. STD. 840.19				C.B. STD. 840.20				C.B. STD. 840.21				C.B. STD. 840.22				C.B. STD. 840.23				C.B. STD. 840.24				C.B. STD. 840.25				C.B. STD. 840.26				C.B. STD. 840.27				C.B. STD. 840.28				C.B. STD. 840.29				C.B. STD. 840.30				C.B. STD. 840.31				C.B. STD. 840.32				C.B. STD. 840.33				C.B. STD. 840.34				C.B. STD. 840.35				C.B. STD. 840.36				C.B. STD. 840.37				C.B. STD. 840.38				C.B. STD. 840.39				C.B. STD. 840.40				C.B. STD. 840.41				C.B. STD. 840.42				C.B. STD. 840.43				C.B. STD. 840.44				C.B. STD. 840.45				C.B. STD. 840.46				C.B. STD. 840.47				C.B. STD. 840.48				C.B. STD. 840.49				C.B. STD. 840.50				C.B. STD. 840.51				C.B. STD. 840.52				C.B. STD. 840.53				C.B. STD. 840.54				C.B. STD. 840.55				C.B. STD. 840.56				C.B. STD. 840.57				C.B. STD. 840.58				C.B. STD. 840.59				C.B. STD. 840.60				C.B. STD. 840.61				C.B. STD. 840.62				C.B. STD. 840.63				C.B. STD. 840.64				C.B. STD. 840.65				C.B. STD. 840.66				C.B. STD. 840.67				C.B. STD. 840.68				C.B. STD. 840.69				C.B. STD. 840.70				C.B. STD. 840.71				C.B. STD. 840.72				C.B. STD. 840.73				C.B. STD. 840.74				C.B. STD. 840.75				C.B. STD. 840.76				C.B. STD. 840.77				C.B. STD. 840.78				C.B. STD. 840.79				C.B. STD. 840.80				C.B. STD. 840.81				C.B. STD. 840.82				C.B. STD. 840.83				C.B. STD. 840.84				C.B. STD. 840.85				C.B. STD. 840.86				C.B. STD. 840.87				C.B. STD. 840.88				C.B. STD. 840.89				C.B. STD. 840.90				C.B. STD. 840.91				C.B. STD. 840.92				C.B. STD. 840.93				C.B. STD. 840.94				C.B. STD. 840.95				C.B. STD. 840.96				C.B. STD. 840.97				C.B. STD. 840.98				C.B. STD. 840.99				C.B. STD. 840.100				C.B. STD. 840.101				C.B. STD. 840.102				C.B. STD. 840.103				C.B. STD. 840.104				C.B. STD. 840.105				C.B. STD. 840.106				C.B. STD. 840.107				C.B. STD. 840.108				C.B. STD. 840.109				C.B. STD. 840.110				C.B. STD. 840.111				C.B. STD. 840.112				C.B. STD. 840.113				C.B. STD. 840.114				C.B. STD. 840.115				C.B. STD. 840.116				C.B. STD. 840.117				C.B. STD. 840.118				C.B. STD. 840.119				C.B. STD. 840.120				C.B. STD. 840.121				C.B. STD. 840.122				C.B. STD. 840.123				C.B. STD. 840.124				C.B. STD. 840.125				C.B. STD. 840.126				C.B. STD. 840.127				C.B. STD. 840.128				C.B. STD. 840.129				C.B. STD. 840.130				C.B. STD. 840.131				C.B. STD. 840.132				C.B. STD. 840.133				C.B. STD. 840.134				C.B. STD. 840.135				C.B. STD. 840.136				C.B. STD. 840.137				C.B. STD. 840.138				C.B. STD. 840.139				C.B. STD. 840.140				C.B. STD. 840.141				C.B. STD. 840.142				C.B. STD. 840.143				C.B. STD. 840.144				C.B. STD. 840.145				C.B. STD. 840.146				C.B. STD. 840.147				C.B. STD. 840.148				C.B. STD. 840.149				C.B. STD. 840.150				C.B. STD. 840.151				C.B. STD. 840.152				C.B. STD. 840.153				C.B. STD. 840.154				C.B. STD. 840.155				C.B. STD. 840.156				C.B. STD. 840.157				C.B. STD. 840.158				C.B. STD. 840.159				C.B. STD. 840.160				C.B. STD. 840.161				C.B. STD. 840.162				C.B. STD. 840.163				C.B. STD. 840.164				C.B. STD. 840.165				C.B. STD. 840.166				C.B. STD. 840.167				C.B. STD. 840.168				C.B. STD. 840.169				C.B. STD. 840.170				C.B. STD. 840.171				C.B. STD. 840.172				C.B. STD. 840.173				C.B. STD. 840.174				C.B. STD. 840.175				C.B. STD. 840.176				C.B. STD. 840.177				C.B. STD. 840.178				C.B. STD. 840.179				C.B. STD. 840.180				C.B. STD. 840.181				C.B. STD. 840.182				C.B. STD. 840.183				C.B. STD. 840.184				C.B. STD. 840.185				C.B. STD. 840.186				C.B. STD. 840.187				C.B. STD. 840.188				C.B. STD. 840.189				C.B. STD. 840.190				C.B. STD. 840.191</			
----------------	--------	------------------	--	---------------	------------------	------------------	------------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	------------	--	--	--	------------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----------------------------	--	--	--	-------------------------------------	--	---------------------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	------------------	--	--	--	---------------------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	-------------------	--	--	--	---------------------	--	--	--

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)

[illegible]

SHEET TOTALS (48" or Less)																																																						
PROJECT TOTALS (48" or Less)																																																						
1904	300	736	568	764						28	3840	1296	368	1216	332	200	140	58	58	54	54	58	58	13	116	89	14	9	1	1	7	13	27	27	49		18	26	2	7	22	5	26		5	22	10	2	44	62	212	2	1	1604