STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

November 13, 2026

Addendum No. 2
RE: Contract # C204976
WBS # 44691.3.1
STATE FUNDED
Wilkes County (R-5759)
NC-115/US-421 BUSINESS (STATESVILLE RD) FROM US-421 TO NC-18 (2ND STREET)

November 17, 2026 Letting

To Whom It May Concern:

Reference is made to the plans and proposal furnished to you on this project.

The following revisions have been made to the Roadway plans.

Sheet No.	Revision
3B-2	Revised Pavement Removal Summary as reflected in quantity change below.

Please void the above listed sheet in your plans and staple the revised sheet thereto.

The following revisions have been made to the proposal.

Page No.	Revision
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 11-13-2026".

Please void the above listed existing page in your proposal and staple the revised and new page thereto.

On the item sheets the following pay item revision has been made:

Item	Description	Old Quantity	New Quantity
0009- 0156000000-E 250	REMOVAL OF EXISTING ASPHALT PAVEMENT	151,310 SY	39,710 SY

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

The Contractor's bid must include this pay item revision.

The electronic bidding form has been updated on Bid Express to reflect this revision.

The contract will be prepared accordingly.

Sincerely,

Signed by:
Jon Weathersbee
E45DA45396074A0...

Jon Weathersbee, PE
State Contract Officer

JHW/jjr
Attachments

cc: Mr. Troy B. Brooks, PE
Michael L. Poe, PE
Mr. Josh Sellers, PE
Project File (2)
Mr. Forrest Dungan, PE
Ms. Jaci Kincaid
Mr. Malcolm Bell

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No. 2 DATED 11-13-2026

DATE AND TIME OF BID OPENING: **Nov 17, 2026 AT 02:00 PM**

CONTRACT ID	C204976
WBS	44691.3.1

FEDERAL-AID NO.	STATE FUNDED
COUNTY	WILKES
T.I.P NO.	R-5759
MILES	3.017
ROUTE NO.	NC-115
LOCATION	NC-115/US-421 BUSINESS (STATESVILLE RD) FROM US-421 TO NC-18 (2ND STREET).
TYPE OF WORK	GRADING, DRAINAGE, PAVING, SIGNALS, AND STRUCTURES.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS $40,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY & STRUCTURE PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
			ROADWAY ITEMS			
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	286,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	3,200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,808 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	680 LF		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	39,710 SY		
0010	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	100 SY		
0011	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	1,000 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	2,450 CY		
0013	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	3,500 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	4,698 SF		
0015	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	250 TON		
0016	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	7,983 TON		
0017	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	25,100 SY		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0335200000-E	305	15" DRAINAGE PIPE	1,396 LF		
0019	0335300000-E	305	18" DRAINAGE PIPE	280 LF		
0020	0335400000-E	305	24" DRAINAGE PIPE	20 LF		
0021	0448000000-E	310	****" RC PIPE CULVERTS, CLASS IV (48")	192 LF		
0022	0448000000-E	310	****" RC PIPE CULVERTS, CLASS IV (60")	268 LF		
0023	0448000000-E	310	****" RC PIPE CULVERTS, CLASS IV (66")	60 LF		
0024	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	17,288 LF		
0025	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	4,680 LF		
0026	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	2,560 LF		
0027	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	616 LF		
0028	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	216 LF		
0029	0449000000-E	310	**" RC PIPE CULVERTS, CLASS V (15")	36 LF		
0030	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	136 LF		
0031	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	272 LF		
0032	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	600 LF		
0033	0600000000-E	310	30" CS PIPE CULVERTS, 0.079" THICK	68 LF		
0034	0636000000-E	310	**" CS PIPE ELBOWS, *****" THICK (15", 0.064")	4 EA		

County: **WILKES**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0636000000-E	310	**" CS PIPE ELBOWS, *****" THICK (18", 0.064")	6 EA		
0036	0636000000-E	310	**" CS PIPE ELBOWS, *****" THICK (24", 0.064")	10 EA		
0037	0636000000-E	310	**" CS PIPE ELBOWS, *****" THICK (30", 0.079")	2 EA		
0038	0973100000-E	330	**" WELDED STEEL PIPE, ****" THICK, GRADE B IN SOIL (54", 0.875")	86 LF		
0039	0973300000-E	330	**" WELDED STEEL PIPE, ****" THICK, GRADE B NOT IN SOIL (54", 0.875")	86 LF		
0040	0995000000-E	340	PIPE REMOVAL	3,829 LF		
0041	0996000000-N	350	PIPE CLEAN OUT	3 EA		
0042	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0043	1077000000-E	SP	#57 STONE	1 TON		
0044	1099500000-E	505	SHALLOW UNDERCUT	5,500 CY		
0045	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	13,650 TON		
0046	1110000000-E	510	STABILIZER AGGREGATE	250 TON		
0047	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	27,265 SY		
0048	1121000000-E	520	AGGREGATE BASE COURSE	20,270 TON		
0049	1220000000-E	545	INCIDENTAL STONE BASE	1,500 TON		
0050	1231000000-E	560	SHOULDER BORROW	625 CY		
0051	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***" DEPTH (3")	1,990 SY		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1330000000-E	607	INCIDENTAL MILLING	1,800 SY		
0053	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	15,620 TON		
0054	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	22,250 TON		
0055	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	23,970 TON		
0056	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3,190 TON		
0057	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	700 TON		
0058	2022000000-E	815	SUBDRAIN EXCAVATION	806.4 CY		
0059	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	3,600 SY		
0060	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	604.8 CY		
0061	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	3,600 LF		
0062	2070000000-N	815	SUBDRAIN PIPE OUTLET	8 EA		
0063	2077000000-E	815	6" OUTLET PIPE	48 LF		
0064	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	52 EA		
0065	2209000000-E	838	ENDWALLS	9.4 CY		
0066	2220000000-E	838	REINFORCED ENDWALLS	17.1 CY		
0067	2275000000-E	SP	FLOWABLE FILL	114 CY		
0068	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	341 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	7.244 CY		
0070	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	166.7 LF		
0071	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
0072	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	22 EA		
0073	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	6 EA		
0074	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	21 EA		
0075	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	32 EA		
0076	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	25 EA		
0077	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	101 EA		
0078	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	92 EA		
0079	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
0080	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	35 EA		
0081	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	2 EA		
0082	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	49 EA		
0083	2535000000-E	846	**" X **" CONCRETE CURB (8" X 18")	1,050 LF		
0084	2535000000-E	846	**" X **" CONCRETE CURB (9" X 18")	1,980 LF		
0085	2538000000-E	846	**'-**" CONCRETE CURB & GUTTER (2'-0")	120 LF		

County: **WILKES**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	2538000000-E	846	**'-**" CONCRETE CURB & GUTTER (2'-9")	2,700 LF		
0087	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	9,300 LF		
0088	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	35,600 LF		
0089	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,635 LF		
0090	2591000000-E	848	4" CONCRETE SIDEWALK	14,050 SY		
0091	2605000000-N	848	CONCRETE CURB RAMPS	213 EA		
0092	2612000000-E	848	6" CONCRETE DRIVEWAY	430 SY		
0093	2619000000-E	850	4" CONCRETE PAVED DITCH	155 SY		
0094	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	5,550 SY		
0095	2738000000-E	SP	GENERIC PAVING ITEM 12" CONCRETE TRUCK APRON	2,930 SY		
0096	2738000000-E	SP	GENERIC PAVING ITEM 8" JOINTED CONCRETE DRIVEWAY	200 SY		
0097	2759000000-N	SP	GENERIC PAVING ITEM EMERGENCY VEHICLE ACCESS FOR CONCRETE ISLAND	1 EA		
0098	2830000000-N	858	ADJUSTMENT OF MANHOLES	15 EA		
0099	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	2 EA		
0100	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	5 EA		
0101	3030000000-E	862	STEEL BEAM GUARDRAIL	4,500 LF		
0102	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	437.5 LF		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	3145000000-E	862	EXTRA LENGTH GUARDRAIL POST (**' STEEL) (8')	75 EA		
0104	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0105	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	5 EA		
0106	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	14 EA		
0107	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0108	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0109	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	12 EA		
0110	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	5 EA		
0111	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,400 LF		
0112	3420000000-E	SP	GENERIC GUARDRAIL ITEM WOOD RUB RAIL	2,325 LF		
0113	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	630 LF		
0114	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	29 EA		
0115	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	28 EA		
0116	3572000000-E	867	CHAIN LINK FENCE RESET	10 LF		
0117	3575000000-E	SP	GENERIC FENCING ITEM PEDESTRIAN SAFETY RAIL	3,925 LF		
0118	3628000000-E	876	RIP RAP, CLASS I	995 TON		
0119	3649000000-E	876	RIP RAP, CLASS B	1,200 TON		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0120	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	7,661 SY		
0121	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0122	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	617 LB		
0123	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4,191 LF		
0124	4096000000-N	904	SIGN ERECTION, TYPE D	13 EA		
0125	4102000000-N	904	SIGN ERECTION, TYPE E	295 EA		
0126	4108000000-N	904	SIGN ERECTION, TYPE F	35 EA		
0127	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2 EA		
0128	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (B)	1 EA		
0129	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)	5 EA		
0130	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (E)	2 EA		
0131	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	2 EA		
0132	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	131 EA		
0133	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	8 EA		
0134	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	4 EA		
0135	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	2 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,019 SF		
0137	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,671 SF		
0138	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	780 SF		
0139	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0140	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	3 EA		
0141	4430000000-N	1130	DRUMS	1,441 EA		
0142	4435000000-N	1135	CONES	187 EA		
0143	4445000000-E	1145	BARRICADES (TYPE III)	2,336 LF		
0144	4447000000-E	SP	PEDESTRIAN CHANNELIZING DEVICES	135 LF		
0145	4455000000-N	1150	FLAGGER	1,104 DAY		
0146	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	7 EA		
0147	4480000000-N	1165	TMA	3 EA		
0148	4485000000-E	1170	PORTABLE CONCRETE BARRIER	630 LF		
0149	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	4,872 LF		
0150	4505000000-E	1170	REMOVE & RESET PORTABLE CONCRETE BARRIER (ANCHORED)	390 LF		
0151	4510000000-N	1190	LAW ENFORCEMENT	100 HR		
0152	4516000000-N	1180	SKINNY DRUM	26 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0153	4520000000-N	1266	TUBULAR MARKERS (FIXED)	9 EA		
0154	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES	27 EA		
0155	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY CURB RAMPS	3 EA		
0156	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,242 EA		
0157	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	72,810 LF		
0158	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	1,637 LF		
0159	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	5,439 LF		
0160	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	422 LF		
0161	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	1,552 LF		
0162	4720000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	24 EA		
0163	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	100 EA		
0164	4726110000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	70 EA		
0165	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,943 LF		
0166	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,163 LF		
0167	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	115 LF		
0168	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	314,280 LF		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0169	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	13,556 LF		
0170	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	12,452 LF		
0171	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	916 LF		
0172	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,508 LF		
0173	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	28 EA		
0174	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	166 EA		
0175	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	39,253 LF		
0176	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	3,774 LF		
0177	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,321 LF		
0178	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	217 LF		
0179	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	29 EA		
0180	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM YIELD LINE PAINT PAVEMENT MARKING (24")	408 LF		
0181	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM YIELD LINE THERMOPLASTIC PAVEMENT MARKING (24", 90 MILS)	358 LF		
0182	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	1,863 EA		
0183	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	35 EA		
0184	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0185	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		

County: **WILKES**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0186	5325200000-E	1510	2" WATER LINE	387 LF		
0187	5325400000-E	1510	4" WATER LINE	114 LF		
0188	5325600000-E	1510	6" WATER LINE	2,925 LF		
0189	5325800000-E	1510	8" WATER LINE	25 LF		
0190	5326200000-E	1510	12" WATER LINE	16,770 LF		
0191	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	40,835 LB		
0192	5536000000-E	1515	2" VALVE	5 EA		
0193	5538000000-E	1515	4" VALVE	3 EA		
0194	5540000000-E	1515	6" VALVE	31 EA		
0195	5558000000-E	1515	12" VALVE	25 EA		
0196	5590000000-E	1515	**" COMBINATION AIR VALVE (2")	2 EA		
0197	5606000000-E	1515	2" BLOW OFF	4 EA		
0198	5643100000-E	1515	3/4" WATER METER	1 EA		
0199	5648000000-N	1515	RELOCATE WATER METER	93 EA		
0200	5649000000-N	1515	RECONNECT WATER METER	19 EA		
0201	5666000000-N	1515	FIRE HYDRANT	10 EA		
0202	5672000000-N	1515	RELOCATE FIRE HYDRANT	13 EA		

County: **WILKES**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0203	5673000000-E	1515	FIRE HYDRANT LEG	492 LF		
0204	5684200000-E	1515	4" LINE STOP WITH BYPASS	2 EA		
0205	5686500000-E	1515	WATER SERVICE LINE	4,032 LF		
0206	5691200000-E	1520	6" SANITARY GRAVITY SEWER	159 LF		
0207	5691300000-E	1520	8" SANITARY GRAVITY SEWER	7,088 LF		
0208	5691500000-E	1520	12" SANITARY GRAVITY SEWER	2,522 LF		
0209	5709000000-E	1520	**" FORCE MAIN SEWER (3")	600 LF		
0210	5709200000-E	1520	4" FORCE MAIN SEWER	549 LF		
0211	5709400000-E	1520	8" FORCE MAIN SEWER	10,625 LF		
0212	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	5 EA		
0213	5768500000-E	1520	SEWER SERVICE LINE	145 LF		
0214	5769000000-E	1520	DUCTILE IRON SEWER PIPE FITTINGS	7,610 LB		
0215	5775000000-E	1525	4' DIA UTILITY MANHOLE	50 EA		
0216	5776000000-E	1525	5' DIA UTILITY MANHOLE	9 EA		
0217	5781000000-E	1525	UTILITY MANHOLE WALL 4' DIA	266.3 LF		
0218	5782000000-E	1525	UTILITY MANHOLE WALL 5' DIA	77 LF		
0219	5798000000-E	1530	ABANDON **" UTILITY PIPE (2")	1,792 LF		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0220	5798000000-E	1530	ABANDON **" UTILITY PIPE (3")	3,128 LF		
0221	5798000000-E	1530	ABANDON **" UTILITY PIPE (4")	6,620 LF		
0222	5800000000-E	1530	ABANDON 6" UTILITY PIPE	8,587 LF		
0223	5801000000-E	1530	ABANDON 8" UTILITY PIPE	13,779 LF		
0224	5804000000-E	1530	ABANDON 12" UTILITY PIPE	699 LF		
0225	5815000000-N	1530	REMOVE WATER METER	1 EA		
0226	5816000000-N	1530	ABANDON UTILITY MANHOLE	26 EA		
0227	5828000000-N	1530	REMOVE UTILITY MANHOLE	18 EA		
0228	5835600000-E	1540	12" ENCASEMENT PIPE	174 LF		
0229	5835700000-E	1540	16" ENCASEMENT PIPE	856 LF		
0230	5836000000-E	1540	24" ENCASEMENT PIPE	823 LF		
0231	5872500000-E	1550	BORE AND JACK OF **" (12")	114 LF		
0232	5872500000-E	1550	BORE AND JACK OF **" (16")	363 LF		
0233	5872500000-E	1550	BORE AND JACK OF **" (24")	481 LF		
0234	5912000000-N	SP	GENERIC UTILITY ITEM WATER PUMP STATION VAULT, 4"	Lump Sum	L.S.	
0235	6000000000-E	1605	TEMPORARY SILT FENCE	55,010 LF		
0236	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,360 TON		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0237	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	6,995 TON		
0238	6012000000-E	1610	SEDIMENT CONTROL STONE	4,395 TON		
0239	6015000000-E	1615	TEMPORARY MULCHING	72 ACR		
0240	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,500 LB		
0241	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	19 TON		
0242	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,900 LF		
0243	6029000000-E	SP	SAFETY FENCE	3,160 LF		
0244	6030000000-E	1630	SILT EXCAVATION	22,330 CY		
0245	6036000000-E	1631	MATTING FOR EROSION CONTROL	160,000 SY		
0246	6037000000-E	1629	COIR FIBER MAT	599 SY		
0247	6042000000-E	1632	1/4" HARDWARE CLOTH	6,015 LF		
0248	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	1,000 SY		
0249	6045000000-E	SP	**" TEMPORARY PIPE (24")	322 LF		
0250	6045000000-E	SP	**" TEMPORARY PIPE (36")	665 LF		
0251	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0252	6071002000-E	1642	FLOCCULANT	1,990 LB		
0253	6071012000-E	1642	COIR FIBER WATTLE	1,700 LF		

County: **WILKES**

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0254	6071030000-E	1640	COIR FIBER BAFFLE	3,865 LF		
0255	6071050000-E	1644	**" SKIMMER (1-1/2")	30 EA		
0256	6071050000-E	1644	**" SKIMMER (2")	4 EA		
0257	6084000000-E	1660	SEEDING & MULCHING	57 ACR		
0258	6087000000-E	1660	MOWING	51 ACR		
0259	6090000000-E	1661	SEED FOR REPAIR SEEDING	750 LB		
0260	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.25 TON		
0261	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,350 LB		
0262	6108000000-E	1665	FERTILIZER TOPDRESSING	40.5 TON		
0263	6111000000-E	SP	IMPERVIOUS DIKE	319 LF		
0264	6114500000-N	1667	SPECIALIZED HAND MOWING	25 MHR		
0265	6114800000-N	SP	MANUAL LITTER REMOVAL	29 MHR		
0266	6114900000-E	SP	LITTER DISPOSAL	5 TON		
0267	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	100 EA		
0268	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	6 EA		
0269	6123000000-E	1670	REFORESTATION	5 ACR		
0270	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT	1,800 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0271	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION, TYPE 1	600 EA		
0272	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	33 EA		
0273	6141000000-E	SP	GENERIC EROSION CONTROL ITEM PERMANENT SOIL REINFORCEMENT MAT, TYPE 3	40 SY		
0274	6141000000-E	SP	GENERIC EROSION CONTROL ITEM PERMANENT SOIL REINFORCEMENT MAT, TYPE 5	70 SY		
0275	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	4 EA		
0276	7060000000-E	1705	SIGNAL CABLE	7,065 LF		
0277	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	22 EA		
0278	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	7 EA		
0279	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3 EA		
0280	7264000000-E	1710	MESSENGER CABLE (3/8")	1,400 LF		
0281	7300000000-E	1715	UNPAVED TRENCHING (**********) (1, 2")	95 LF		
0282	7300000000-E	1715	UNPAVED TRENCHING (**********) (2, 2")	55 LF		
0283	7300000000-E	1715	UNPAVED TRENCHING (**********) (4, 2")	10 LF		
0284	7301000000-E	1715	DIRECTIONAL DRILL (**********) (1, 2")	150 LF		
0285	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0286	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	1 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0287	7360000000-N	1720	WOOD POLE	3 EA		
0288	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0289	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3 EA		
0290	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,165 LF		
0291	7456100000-E	1726	LEAD-IN CABLE (14-2)	5,395 LF		
0292	7481000000-N	SP	SITE SURVEY	1 EA		
0293	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	4 EA		
0294	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	4 EA		
0295	7576000000-N	SP	METAL STRAIN SIGNAL POLE	7 EA		
0296	7613000000-N	SP	SOIL TEST	7 EA		
0297	7614100000-E	SP	DRILLED PIER FOUNDATION	42 CY		
0298	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0299	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	3 EA		
0300	7696000000-N	1751	CONTROLLERS WITH CABINET (**********) (2070LX, BASE MOUNTED)	1 EA		
0301	7696000000-N	1751	CONTROLLERS WITH CABINET (**********) (2070LX, POLE MOUNTED)	1 EA		
0302	7744000000-N	1751	DETECTOR CARD (TYPE 170)	9 EA		
0303	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0304	7980000000-N	SP	GENERIC SIGNAL ITEM NON-INTRUSIVE DETECTION SYSTEM PROCESSOR	1 EA		
0305	7980000000-N	SP	GENERIC SIGNAL ITEM VIDEO CAMERA ASSEMBLY	1 EA		
			CULVERT ITEMS			
0306	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ********** (11+21.00 -Y4-)	Lump Sum	L.S.	
0307	8063000000-N	SP	PRECAST REINFORCED CONC BOX CULVERT AT STA ********** (11+21.00 -Y4-)	Lump Sum	L.S.	
0308	8130000000-N	414	BOX CULVERT EXCAVATION, STA ******** (11+21.00 -Y4-)	Lump Sum	L.S.	
0309	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	152.4 TON		
			WALL ITEMS			
0310	8801000000-E	SP	MSE RETAINING WALL NO **** (3)	800 SF		
0311	8801000000-E	SP	MSE RETAINING WALL NO **** (4)	7,750 SF		
0312	8801000000-E	SP	MSE RETAINING WALL NO **** (6)	1,710 SF		
0313	8802010000-E	SP	SOIL NAIL RETAINING WALLS	600 SF		
0314	8802015100-N	SP	SOIL NAIL VERIFICATION TESTS	2 EA		
0315	8802015110-N	SP	SOIL NAIL PROOF TESTS	7 EA		
			STRUCTURE ITEMS			
0316	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ********** (173+24.00 -L-)	Lump Sum	L.S.	
0317	8482000000-E	460	THREE BAR METAL RAIL	421.5 LF		

County: WILKES

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0318	8867000000-E	SP	GENERIC STRUCTURE ITEM FOAM JOINT SEALS FOR PRESERVATION	405.5 LF		
0319	8882000000-E	SP	GENERIC STRUCTURE ITEM ELASTOMERIC CONCRETE FOR PRESERVATION	90.6 CF		
0320	8892000000-E	SP	GENERIC STRUCTURE ITEM BRIDGE JOINT DEMOLITION	402.7 SF		
0321	8892000000-E	SP	GENERIC STRUCTURE ITEM REINFORCED CONCRETE SIDEWALK	3,078 SF		

1055/Nov13/Q1602590.894/D1393723994210/E321 **Total Amount Of Bid For Entire Project :**

COMPUTED BY:	JLE	DATE:	11/9/2023
CHECKED BY:	DMW	DATE:	11/13/2026

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT NO.	SHEET NO.
R-5759	3B-2

GUARDRAIL SUMMARY

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL

IN LINEAR FEET

G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL WIDTH	FLARE LENGTH		W		ANCHORS								IMPACT ATTENUATOR		WOODEN RUB RAIL	REMOVE EXISTING GUARDRAIL	DEEPER 8' POSTS NEEDED	REMARKS
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	Type III	B-77	GREU, TL-3	GREU, TL-2	CAT-1	AT-1	Type III SC	B-77 SC	G	NG				
-L-	18+49.60	20+50.60	RT	210.38			19+25	BRIDGE	2.16	7.16						1		1								162.5		
-L-	19+46.66	20+47.28	LT	110.38				BRIDGE	2.84	7.84						1		1								87.5		
-L-	22+33.36	23+33.36	RT	110.38				BRIDGE	1.74	6.74						1		1								87.5		
-L-	22+32.44	23+92.81	LT	160.38			BRIDGE		1.29	6.29						1		1								162.5		
-Y2-	15+83.75	25+21.61	LT	775	200		24+75	16+50										1	1									
-L-	38+50.00	42+65.96	RT	416.75			39+50	42+75	7.5	19	50		1				1		1						360.50			
-Y4A-	10+65.28	11+05.35	RT/LT	31.25	125		10+75	11+00	4	7								1		1								
-Y4-	10+30.00	11+81.07	RT	143.75			10+50	11+75	12	15								1	1									
-Y4-	10+85.00	11+38.71	LT	50	25		11+25	10+85	8	11									1	1								
-L-	85+88.88	87+91.05	RT	206.25			85+89	87+85	7.5	19	50		1				1		1						150.00			
-L-	92+44.25	95+00.50	RT	256.25			93+25	94+95	7.5	19	50		1				1		1						200.00			
-L-	95+75.00	96+56.25	RT	81.25			96+00	96+50	7.5	19	50		1				1		1						25.00			
-L-	108+28.73		LT	100				108+35	20	21									1								16	
DRW9		11+60.80	RT	6.25	25		11+50				12.5		4							1							5	
-L-	114+98.75		LT	281.25				115+00	20	21									1								45	
DRW10		10+69.33	RT	6.25	37.5		11+00				12.5		4							1							7	
-L-	129+78.75	135+95.25	LT	631.25			135+45	130+25	7.5	19								1	1						600.00	326		
-L-	133+84.34	137+16.25	RT	350			134+50	137+15	7.5	19								1	1						318.75	304		
-Y13-	10+47.82	11+86.25	RT	125	25		10+70	11+75	2.5	11	33		5						1	1								
-L-	140+27.56	146+94.74	RT	681.25			140+50	146+50	7.5	19								1	1						650.00	728		
-L-	168+25.77	171+11.14	RT	285.38			168+50	BRIDGE	3.63	8	285			t		1		1								291		
-L-	169+60.93	171+11.14	LT	150			BRIDGE	169+75	9.9	14		154			1				1							137		
-L-	175+40.38	176+37.74	LT	93.75				BRIDGE	7.25	12	25				1			1								88		
			Subtotal	5,262.38	437.5																							
		LESS ANCHOR DEDUCTIONS																										
	TYPE III	(2@18.75)	=	37.50																								
	B-77	(5 @22.875)	=	114.38																								
	GREU_TL3	(4@ 50)	=	200																								
	GREU_TL2	(12@25)	=	300																								
	CAT-1	(14@6.25)	=	87.50																								
	AT-1	(5@6.25)	=	31.25																								
TOTAL				4,491.75	437.5										2	5	4	12	14	5					2,304.25	2,374	73	
SAY				**4,500.00**	**437.5**										**2**	**5**	**4**	**12**	**14**	**5**					**2,325**	**2,400**	**75**	
ADDITIONAL GUARDRAIL POSTS: SAY 10																												

PAVEMENT REMOVAL SUMMARY

IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL
-L-	1191	1663	RT	542.95
-L-	15+52	17+08	LT/RT	579.39
-L-	2464	2555	RT	41.71
-L-	25+76	26+65	LT/RT	665.22
-L-	2731	2938	LT	143.44
-L-	2889	2952	RT	660.75
-L-	3082	3143	LT	217.02
-L-	3180	3303	LT	237.15
-L-	3139.04	3900.48	RT	1,378.60
-L-	4210	4259	LT	274.16
-L-	4400.35	4910.05	RT	553.48
-L-	4445	4537	LT/RT	542.09
-L-	4640	5314	LT/RT	760.61
-L-	4925	5449.37	RT	113.95
-L-	5465.37	5754.83	RT	11.85
-L-	5893	6352	RT	452.90
-L-	6625	6823	LT	262.74
-L-	6904	74+83	LT/RT	1,269.67
-L-	6974	7050	RT	159.85
-L-	6996.75	7017	LT	35.80
-L-	7046	7062	LT	27.76
-L-	7123	7135	RT	5.92
-L-	7119.53	7160.86	LT	55.53
-L-	7122.6	7151.23	RT	39.42
-L-	7195.078	7302	RT	220.59
-L-	7332	7488	RT	383.30
-L-	7621	7723	RT	193.10
-L-	7996	8006	RT	11.51
-L-	8047	8132	RT	122.01
-L-	8172	8196	RT	34.35
-L-	8716	8918	LT	398.99
-L-	88+00	90+44	LT/RT	514.85
-L-	8947	8956	LT	13.17
-L-	8958	8982	LT	43.74
	COLUMN 1 TOTAL:			10,967.58

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL
-L-	91+33	102+60	LT/RT	2,427.87
-L-	9647.87	9675.07	RT	63.64
-L-	9697.87	9809.17	RT	148.03
-L-	9850	10029	RT	290.74
-L-	9969.2	10093.5	LT	182.77
-L-	10240	10377	LT	116.43
-L-	10365	10453	LT/RT	275.12
-L-	10388	10778	LT	1,686.45
-L-	105+60	116+31	LT/RT	1,576.21
-L-	11830	11845	LT	49.46
-L-	12557	12575	LT	22.23
-L-	12728	14240	LT/RT	2,564.28
-L-	12872	12957	RT	177.15
-L-	14094	14925	RT	727.03
-L-	15030	15144	RT	316.48
-L-	15948.96	16036.88	RT	153.76
-L-	15992	16055	LT	35.83
-L-	16095	16199	LT	193.63
-L-	16238	16255	LT	16.57
RPB	1553	1777	RT	262.85
RPD	1150	1511	RT/LT	697.97
Y1	1095	1325	RT	79.95
DRW3	1213	1286	LT	49.26
Y3	1222	1243	RT	5.05
Y3	1256	1301	RT	84.26
Y4	1129	1144	LT	16.17
Y6REV	1722	1770	LT	61.39
Y7	1030	1088	LT	95.59
Y7	1155	1259	RT	216.76
DRW8	1042	1112	RT	101.09
Y9	1317	1355	LT	5.21
		COLUMN 2 TOTAL:		12,699.24

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL
Y9	1366	1470	LT	177.61
Y11	1080	1360	RT	654.41
Y14	1185	1695	RT	846.96
Y15	1075	1155	LT	279.02
Removal of Temporary Pavement				13,881.33
	COLUMN 1 TOTAL:			10,967.58
	COLUMN 2 TOTAL:			12,699.24
	COLUMN 3 TOTAL:			15,839.33
		TOTAL:		39,506.15
		SAY:		**39,710**

CONCRETE REMOVAL SUMMARY

IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	CONCRETE REMOVAL
-L-	71+20	71+61	LT	50.67
-L-	12+503	125+61	LT	31.80
		TOTAL:		82.46
		SAY:		**100**

WOVEN WIRE FENCE, 47" FABRIC

IN LINEAR FEET

STATION TO STATION LINE	LT. or RT.	FABRIC LF	4" POSTS EA	5" POSTS EA
-L- 14+05.00 LT TO -RPB- 17+74.81 RT	LT	137	6	7
-L- 17+50.00 RT TO -DRW1- 11+09.97 LT	RT	124	5	7
-L- 24+70 LT TO -Y1- 12+12.44 RT	LT	180	9	7
-L- 27+66.63 LT TO -Y1- 12+49.39 LT	LT	185	9	7
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE	**TOTAL:**	**626**	**29**	**28**
	SAY:	**630**	**29**	**28**

ASPHALT BREAKING SUMMARY

IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT BREAKING
-Y6REV-	15+25	17+57	RT/LT	332.78
-Y12-	10+32	11+50	RT/LT	368.81
-DRW1-	10+00	11+50	RT/LT	163.54
-DRW12-	10+41	10+94	RT/LT	105.27
		TOTAL:		970.40
		SAY:		**1,000**