

## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER GOVERNOR J.R. "JOEY" HOPKINS Secretary

November 9, 2023

## Addendum No. 1

RE: Contract # C204902 WBS # 15BPR.102.3 STATE FUNDED New Hanover County CAPE FEAR MEMORIAL BRIDGE.

## November 21, 2023 Letting

To Whom It May Concern:

Reference is made to the proposal and plans furnished to you on this project.

The following revisions have been made to the Traffic Management Plans.

Sheet No.	Revision
TMP-1, TMP-3, TMP-6	TMP plans revised to close the Eastbound side of the bridge
thru TMP-10	first.

Please void the above listed Sheets in your Plans and staple the revised Sheets thereto.

The following revisions have been made to the Structures Plans.

Sheet No. Revision		
S-5, S-6, S-15, S-17	Revised to indicate that the eastbound side of the bridge grid deck and structural steel is to be done first and to indicate that temporary bracing must be installed to facilitate opening the bridge while Stringers S2, S13, S7, and S8 are removed.	

Please void the above listed Sheets in your Plans and staple the revised Sheets thereto.

Page No.	Revision		
Proposal Cover	Note added that reads		
	"Includes Addendum No. 1 Dated 11-09-2023".		
Table of Contents	Updated to reflect changes below.		
	The Project Special Provision entitled CONTRACT TIME		
G-3 thru G-5	AND LIQUIDATED DAMAGES has been replaced with		
0-5 till 0-5	new Project Special Provision entitled CONTRACT TIME,		
	LIQUIDATED DAMAGES AND BONUS CLAUSE.		
DD 27	The Unit Project Special Provision entitled NOTES TO		
BP-37	<b>CONTRACTOR</b> has been added to the Structures Unit		
(New)	Project Special Provisions.		

The following revisions have been made to the proposal.

Please void the above listed existing Pages in your proposal and staple the revised Pages thereto.

Staple New Page BP-37 after existing Page BP-27 in your proposal.

On the item sheets the following pay item revisions have been made:

<u>Item</u>	<b>Description</b>	<u>Old Quantity</u>	<u>New Quantity</u>
0009-4465000000-N 1160	TEMPORARY CRASH CUSHIONS	1 EA	2 EA
0012-4485000000-E 1170	PORTABLE CONCRETE BARRIER	60 LF	120 LF

The Contractor's bid must include these pay item revisions.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

Forald Elton Davenport, Jr. F81B6038A47A442...

Ronald E. Davenport, Jr., PE State Contract Officer

RED/cms

Attachments

cc: Mr. Boyd Tharrington, PE Mr. D. Chad Kimes, PE Mr. Ken Kennedy, PE Mr. Malcolm Bell Project File (2) Mr. Forrest Dungan, PE Ms. Jaci Kincaid Mr. Jon Weathersbee, PE

## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH, N.C.

## **PROPOSAL**

## **INCLUDES ADDENDUM No. 1 DATED 11-09-2023**

DATE AND TIME OF BID OPENING: Nov 21, 2023 AT 02:00 PM

CONTRACT ID C204902

WBS 15BPR.102.3

FEDERAL-AID NO.	STATE FUNDED
COUNTY	NEW HANOVER
T.I.P NO.	
MILES	0.575
ROUTE NO.	
LOCATION	CAPE FEAR MEMORIAL BRIDGE.

TYPE OF WORK BRIDGE PRESERVATION

### NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY & STRUCTURE PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

## TABLE OF CONTENTS

## COVER SHEET PROPOSAL SHEET

## **PROJECT SPECIAL PROVISIONS**

CONTRACTOR PREQUALIFICATION:
INTERESTED PARTIES LIST:
LIABILITY INSURANCE:
CONTRACT TIME, LIQUIDATED DAMAGES AND BONUS CLAUSE:
INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES: G-4
INTERMEDIATE CONTRACT TIME NUMBER 2 AND LIQUIDATED DAMAGES: G-5
INTERMEDIATE CONTRACT TIME NUMBER 3 AND LIQUIDATED DAMAGES: G-5
INTERMEDIATE CONTRACT TIME NUMBER 4 AND LIQUIDATED DAMAGES: G-6
INTERMEDIATE CONTRACT TIME NUMBER 5 AND LIQUIDATED DAMAGES: G-6
NO MAJOR CONTRACT ITEMS:
SPECIALTY ITEMS:
FUEL PRICE ADJUSTMENT:
SCHEDULE OF ESTIMATED COMPLETION PROGRESS:
MINORITY BUSINESS ENTERPRISE AND WOMEN BUSINESS ENTERPRISE:
RESTRICTIONS ON ITS EQUIPMENT AND SERVICES:
USE OF UNMANNED AIRCRAFT SYSTEM (UAS):
EQUIPMENT IDLING GUIDELINES:
MAINTENANCE OF THE PROJECT:
ELECTRONIC BIDDING:
AWARD LIMITS:
TWELVE MONTH GUARANTEE:
OUTSOURCING OUTSIDE THE USA:
ROADWAYR-1

## STANDARD SPECIAL PROVISIONS

AVAILABILITY FUNDS – TERMINATION OF CONTRACTS	SSP-1
ERRATA	SSP-2
PLANT AND PEST QUARANTINES	SSP-10
MINIMUM WAGES	
TITLE VI AND NONDISCRIMINATION	SSP-12
ON-THE-JOB TRAINING	SSP-20

## **UNIT PROJECT SPECIAL PROVISIONS**

TRAFFIC CONTROL	TC-1
STRUCTURE / CULVERTS	BP-3

## PROPOSAL ITEM SHEET

ITEM SHEET(S)

**Page 1-14, Article 102-8 PREPARATION AND SUBMISSION OF BIDS**, lines 30-31, delete and replace the first paragraph with the following:

Prior to submitting a bid on a project, the bidder shall sign up on the *Interested Parties List* in conformance with Article 102-3. The bidder shall submit a unit or lump sum price for every item in the proposal other than items that are authorized alternates to those items for which a bid price has been submitted.

## **LIABILITY INSURANCE:**

(5-16-23)

107

SP1 G05

Revise the 2018 Standard Specifications as follows:

Page 1-64, Article 107-15 LIABILITY INSURANCE, replace the first sentence with the following:

The Contractor shall at its sole cost and expense obtain and furnish to the Department an original standard Association for Cooperative Operations Research and Development (ACORD) certificate of liability insurance evidencing commercial general liability with a limit for bodily injury and property damage in the amount of \$5,000,000 per occurrence and \$5,000,000 general aggregate, covering the Contractor from claims or damages for bodily injury, personal injury, or for property damages that may arise from operating under the contract by the employees and agents of the Contractor.

## **CONTRACT TIME, LIQUIDATED DAMAGES AND BONUS CLAUSE:**

(7-20-99) (Rev. 11-07-23)

08

SP1 G06

The date of availability for this contract is **January 3**, **2024**, except that work in jurisdictional waters and wetlands shall not begin until a meeting between the DOT, Regulatory Agencies, and the Contractor is held as stipulated in the permits contained elsewhere in this proposal. This delay in availability has been considered in determining the contract time for this project.

The completion date for this contract is **June 28, 2024**.

Except where otherwise provided by the contract, observation periods required by the contract will not be a part of the work to be completed by the completion date and/or intermediate contract times stated in the contract. The acceptable completion of the observation periods that extend beyond the final completion date shall be a part of the work covered by the performance and payment bonds.

The liquidated damages for this contract are **Six Thousand Dollars (\$ 6,000.00)** per calendar day.

The Department desires that this contract be completed by the completion date of **June 28, 2024** and that the Contractor pursue the work with such labor, equipment and materials as necessary to ensure that this completion date will be met without regard to time extensions and time reliefs provided for in the Specifications. Therefore, as full compensation for all extra costs involved, the Department agrees to pay as a bonus, the sum of **Two Hundred Thousand Dollars (\$ 200,000.00)** to the Contractor for satisfactorily completing this contract on or prior to **June 28, 2024**. Should

the Contractor fail to complete this contract by the completion date, then normal time extension and time reliefs provided in the Specifications will apply and no bonus will be allowed.

In addition to the bonus listed above, the Department desires that this contract be completed by the earlier date of May 23, 2024 and that the Contractor pursue the work with such labor, equipment and materials as necessary to ensure that this earlier completion date will be met without regard to time extensions and time reliefs provided for in the Specifications. Therefore, as full compensation for all extra costs involved, the Department agrees to pay as an additional bonus, the sum of Three Hundred Thousand Dollars (\$ 300,000.00) to the Contractor for satisfactorily completing this contract on or prior to May 23, 2024. Bonus payment shall be limited to Five Hundred Thousand (\$ 500,000.00) maximum for this project.

### INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES: (2-20-07) 108 SP1 G14 A

The Contractor shall complete the required work of installing, maintaining, and removing the traffic control devices for lane closures and restoring traffic to the existing traffic pattern. The Contractor shall not close or narrow a lane of traffic on -L- (US 76, US 421, BUS 17) during the following time restrictions:

## DAY AND TIME RESTRICTIONS

## Monday thru Sunday, 5:00 AM to 7:00 PM

In addition, the Contractor shall not close or narrow a lane of traffic on **-L- (US 76, US 421, BUS 17)**, detain and/or alter the traffic flow on or during holidays, holiday weekends, special events, or any other time when traffic is unusually heavy, including the following schedules:

## HOLIDAY AND HOLIDAY WEEKEND LANE CLOSURE RESTRICTIONS

- 1. For **unexpected occurrence** that creates unusually high traffic volumes, as directed by the Engineer.
- 2. For New Year's Day, between the hours of **5:00** AM December 31<sup>st</sup> and **7:00** PM January 2<sup>nd</sup>. If New Year's Day is on a Friday, Saturday, Sunday or Monday, then until **7:00** PM the following Tuesday.
- 3. For **Memorial Day**, between the hours of **5:00 AM** Friday and **7:00 PM** Tuesday.
- 4. For **Independence Day**, between the hours of **5:00 AM** the day before Independence Day and **7:00 PM** the day after Independence Day.

If **Independence Day** is on a Friday, Saturday, Sunday or Monday, then between the hours of **5:00 AM** the Thursday before Independence Day and **7:00 PM** the Tuesday after Independence Day.

- 5. For Labor Day, between the hours of **5:00** AM Friday and **7:00** PM Tuesday.
- 6. For **Thanksgiving**, between the hours of **5:00 AM** Tuesday and **7:00 PM** Monday.
- 7. For **Christmas**, between the hours of **5:00 AM** the Friday before the week of Christmas Day and **7:00 PM** the following Tuesday after the week of Christmas Day.

- 8. For North Carolina Azalea Festival Event, between the hours of 5:00 AM the Tuesday before the Azalea Festival and 7:00 PM the Monday after the Azalea Festival.
- 9. For Wilmington NC Riverfest, between the hours of 5:00 AM the Friday before the weekend of the Wilmington NC Riverfest and 7:00 PM the Monday after the weekend of the Wilmington NC Riverfest.

Holidays and holiday weekends shall include New Year's, Easter, Memorial Day, Independence Day, Labor Day, Thanksgiving, and Christmas. The Contractor shall schedule his work so that lane closures will not be required during these periods, unless otherwise directed by the Engineer.

The time of availability for this intermediate contract work shall be the time the Contractor begins to install all traffic control devices for lane closures according to the time restrictions listed herein.

The completion time for this intermediate contract work shall be the time the Contractor is required to complete the removal of all traffic control devices for lane closures according to the time restrictions stated above and place traffic in the existing traffic pattern.

The liquidated damages are **Two Thousand Five Hundred Dollars (\$ 2,500.00)** per fifteen (15) minute time period. The liquidated damages associated with Day and Time Restrictions will not apply to -L- (US 76, US 421, BUS 17) when lane closures are required by Steps #4 thru #10 of the Phasing, as shown on Sheet TMP-3. The liquidated damages associated with Holiday and Holiday Weekend Lane Closure Restrictions shall apply throughout the entire duration of the project.

## INTERMEDIATE CONTRACT TIME NUMBER 2 AND LIQUIDATED DAMAGES: (6-18-13) 108 SP1 G14 L

The Contractor shall complete the work required of **Steps #4 thru #7** as shown on Sheet **TMP-3** and shall place and maintain traffic on same.

The date of availability for this intermediate contract time is **the date the Contractor elects to begin work**.

The completion date for this intermediate contract time is April 1, 2024.

The liquidated damages are **Five Thousand Dollars (\$ 5,000.00)** per calendar day.

### INTERMEDIATE CONTRACT TIME NUMBER 3 AND LIQUIDATED DAMAGES: (2-20-07) (Rev. 6-18-13) 108 SP1

SP1 G14 F

The Contractor shall complete the work required of **Step #5A** as shown on Sheet **TMP-3** and shall place and maintain traffic on same.

The time of availability for this intermediate contract time is the **Friday** at **7:00 PM** that the Contractor elects to begin the work.

The completion time for this intermediate contract time is the following **Monday** at **5:00** AM after the time of availability.

The liquidated damages are Five Thousand Dollars (\$ 5,000.00) per fifteen (15) minute time period.

**BP-37** 

Project 15BPR.102.3

## **NOTES TO CONTRACTOR**

(SPECIAL)

Not all structural steel and grid deck materials will be completed and delivered at the same time. Deliveries will be made as fabrication of portions of the materials is completed. Delivery of structural steel is currently scheduled to begin approximately January 22, 2024, with the final delivery approximately 10 weeks later. Deliveries for steel grid deck are on a similar schedule. It is anticipated that the first deliveries of the structural steel and grid deck will occur no later than January 29, 2024, and the final deliveries will be made no later than April 15, 2024.

In general, structural steel and grid deck are expected to be delivered to the bridge site. Some temporary storage of material can be allowed on the fixed bridge approach spans when those locations are subject to lane and directional closures. Depending on the planned schedule of work and analysis of the approach spans, limits on the amount of storage will be required. The Contractor must submit for review and approval his anticipated work schedule and anticipated staging of materials on the fixed bridge approach spans prior to storing any materials on the bridge deck. If additional off-bridge storage or lay down area is required, some capacity is available beneath the bridge on the east side and at the NCDOT Bridge Maintenance yard in Leland, NC. Depending on the schedule of work, available storage capacity, and storage weight limits on the approach spans at the time of a particular delivery, the Contractor shall coordinate with the structural steel or grid deck fabricators to determine the exact delivery location. For materials delivered to the lay down and storage area beneath the east end of the bridge and the NCDOT Bridge Maintenance yard in Leland, NC, the Contractor is required to transport materials from those locations to the bridge site as needed.

Working Drawings are required for any Structural Steel provided by the Contractor, which includes the finger plate shims and may include the floorbeam stiffeners, if the Contractor chooses to remove a different height of the stiffeners than is shown in the suggested details. Working Drawings are required for span balancing plates to be used by the Contractor.

### Nov 08, 2023 1:54 PM


### ITEMIZED PROPOSAL FOR CONTRACT NO. C204902

County:	NEW HANOVER					
Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
			ROADWAY ITEMS			
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	440000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,291 SF		
0003	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	124 SF		
0004	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	102 SF		
0005	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0006	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	13 EA		
0007	443000000-N	1130	DRUMS	150 EA		
0008	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0009	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0010	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	1 EA		
0011	4480000000-N	1165	ТМА	4 EA		

0011	448000000-N	1165	ТМА	4 EA		
0012	4485000000-E	1170	PORTABLE CONCRETE BARRIER	120 LF		 
0013	4500000000-E	1170	REMOVE AND RESET PORTABLE CONCRETE BARRIER	60 LF		 
0014	451000000-N	1190	LAW ENFORCEMENT	240 HR		 
0015	451600000-N	1180	SKINNY DRUM	7 EA		 
0016	458900000-N	SP	GENERIC TRAFFIC CONTROL ITEM STEEL TEMPORARY BARRIER RAIL	Lump Sum	L.S.	 
0017	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	800 LF		 

County: NEW HANOVER

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	481000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,000 LF		
0019	4815000000-Е	1205	PAINT PAVEMENT MARKING LINES (6")	800 LF		
0020	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200 LF		
0021	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0022	525500000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
			STRUCTURE ITEMS			
0023	886000000-N	SP	GENERIC STRUCTURE ITEM REPLACEMENT OF STEEL GRID DECK	Lump Sum	L.S.	
0024	886000000-N	SP	GENERIC STRUCTURE ITEM REPLACEMENT OF STRUCTURAL STEEL	Lump Sum	L.S.	
0025	886000000-N	SP	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM	Lump Sum	L.S.	
0026	886000000-N	SP	GENERIC STRUCTURE ITEM WIRE ROPE CLEANING AND RELUBRICATION	Lump Sum	L.S.	
1354/N	ov08/Q6015/D13178510	0000/E26	Total Amount Of Bid For	r Entire Project :		



WORK ZONE SAFETY & MOBILITY

"from the MOUNTAINS to the COAST"

**PROJECT DESIGN ENGINEER** 



## SHEET NO.

TMP - 1	TITLE SHEET, VICINITY MAP, AND
TMP-1A	LIST OF APPLICABLE ROADWAY STA AND LEGEND
TMP-2	GENERAL NOTES
TMP-3	TEMPORARY TRAFFIC CONTROL PHAS
TMP-4	WORK ZONE ADVANCE WARNING SIGN
TMP-4A	TRAFFIC SHIFT DETAILS
TMP-5	DETOUR SIGNS AND CMS MESSAGES
TMP-6	EASTBOUND BRIDGE CLOSURE DETOU
TMP - 7	EASTBOUND ROAD CLOSURE DETAIL
TMP-8	WESTBOUND LANE CLOSURES
TMP-9	WESTBOUND BRIDGE CLOSURE DETOU
TMP - 10	WESTBOUND ROAD CLOSURE DETAIL



License No. F-0672

# **INDEX OF SHEETS**

## TITLE

TLE SHEET, VICINITY MAP, AND INDEX OF SHEETS ST OF APPLICABLE ROADWAY STANDARD DRAWINGS, D LEGEND NERAL NOTES MPORARY TRAFFIC CONTROL PHASING RK ZONE ADVANCE WARNING SIGNS AFFIC SHIFT DETAILS TOUR SIGNS AND CMS MESSAGES STBOUND BRIDGE CLOSURE DETOUR ROUTE STBOUND ROAD CLOSURE DETAIL STBOUND LANE CLOSURES STBOUND BRIDGE CLOSURE DETOUR ROUTE


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED J.W. Woolard, Jr. 19862 11/3/2023

> DOCUMENT NOT CONSIDERED FINAL **UNLESS ALL SIGNATURES COMPLETED**

SHEET NO. TMP-1

 $\frown$ 

••




мΨ 

# TRAFFIC CONTROL PHASING


IG USING LANE CLOSURES OR ROAD	COMPLETE THE WORK OF STEPS 8 - 10 BETWEEN 7 2024. (SEE SPECIAL PROVISIONS)
CTIONS.	STEP 7: UNCOVER DETOUR SIGNS INSTALLED IN S BUS 17 AND PLACE TRAFFIC ON THE OFF-SITE D
DRAWING 1101.02, SHEET 3 FOR 8 FOR LEFT OR RIGHT LANE	STEP 8: REMOVE TEMPORARAY STEEL BARRIER FRO BEGIN GRID DECK REPLACEMENT ON WEST STRUCTURE PLANS. COMPLETE THE WORK OF STEP 8A BETWEEN 7:00 P MONDAY (58 CONSECUTIVE HOURS). (SEE SPECIA STEP 8A: INSTALL OFF-SITE DETOUR SIGNS FOR
LOSE BOTH INBOUND AND	SHOWN ON TMP-6,7 AND SHIFT TRAFFIC WELD STIFFENERS BACK ONTO THE FLO THE BRIDGE. COVER OFF-SITE DETOUR SIGNS FOR E
13 IN ACCORDANCE WITH SHEET DRAWING 1101.03, SHEET 7. IO.13 IN ACCORDANCE WITH SHEET	OPEN EASTBOUND TRAFFIC ON THE CAPE STEP 9: COMPLETE THE GRID DECK REPLACEMENT SHOWN IN THE STRUCTURE PLANS. INSTA PLACE FINAL MARKINGS ON WESTBOUND PAVEMENT MARKING PLANS.
SEE TCP-4) ON PROJECT NO MORE NING WORK.	STEP 10: REMOVE ALL TRAFFIC CONTROL DEVICES BUS 17 TO TRAFFIC IN THE FINAL PAT
FOR EASTBOUND US 76, 421, BUS 73, INSTALL PCB AND TEMPORARY VICES, AND TEMPORARY STEEL SEE TMP-4A)	STEP 11: USING LANE CLOSURES PER ROADWAY STE TEMPORARY STEEL BARRIER AND ALL TRA ON EASTBOUND US 76, 421, BUS 17 AS AND OPEN EASTBOUND TO FINAL PATTERN STEP 12: USING LANE CLOSURES, RSD 1101.01, S REMAINING STRUCTURE REPAIRS AS SHOW
(SEE SPECIAL PROVISIONS)	STEP 13: REMOVE ALL TRAFFIC CONTROL DEVICES
IR SIGNS AND SHIFT TRAFFIC	
AND BEGIN GRID DECK REPLACEMENT ON THE STRUCTURE PLANS.	
Y AND 5:00 AM THE FOLLOWING SIONS)	
IND US 76, 421, BUS 17 AS THE DETOUR.	
IS ON THE EASTBOUND SIDE OF	
ID US 76, 421, AND BUS 17 AND EMORIAL BRIDGE TO TRAFFIC.	
STBOUND US 76, 421, BUS 17 AS	
TBOUND SIDE OF THE BRIDGE AS	

Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27606 Tel. 919.851.6866 Fax 919.851.7024 www.stantec.com License No. F-0672


**Stantec** 



	PROJ. REFERENCE NO. 15BPR.102.3	SHEET NO.
		•
7:00PM APRIL 8, 2024 AND MAY 23,		
STEP 4A, CLOSE WESTBOUND US 76, 421, DETOUR. (SEE TMP-9,10)		
OM WESTBOUND SIDE OF THE BRIDGE. STBOUND US 76, 421, BUS 17 AS SHOWN IN THE		
PM FRIDAY AND 5:00 AM THE FOLLOWING AL PROVISIONS)		
EASTBOUND US 76, 421, BUS 17 AS C ONTO THE DETOUR.		
OOR BEAMS ON THE WESTBOUND SIDE OF		
EASTBOUND US 76, 421, AND BUS 17 AND E FEAR MEMORIAL BRIDGE TO TRAFFIC.		
ON WESTBOUND US 76, 421, BUS 17 AS FALL THE PERMANENT MEDAIN BARRIER RAIL.		
US 76, 421, BUS 17 AS SHOWN IN THE FINAL		
S AND REOPEN WESTBOUND US 76, 421, TTERN.		
TD. DRAWING 1101.02, SHEET 3, REMOVE AFFIC CONTROL DEVICES, PLACE FINAL MARKING S SHOWN IN THE FINAL PAVEMENT MARKING PLANS		
SHEET 3, AND TMP-8, COMPLETE WN IN THE STRUCTURE PLANS		
S AND OPEN TRAFFIC TO FINAL PATTERN.		












DocuSign Envelope ID: C23607D6-2FCE-472E-B45C-DFB0FF5A5486










2023 raffic\Transportation Management Plan\TCP\PLAN SHEETS\I5BPR.I02.3\_TMP\_08\_WESTBOUND\_LANE\_CLOSURE\_DETAIL.dgn






+









	.102_SMU_CS1_5.d	
2023	9_15BPR.102	
/2(	600	

PR			
15B	DESIGNED BY:	M.NIFONG	DATE : JUL 2023
	DRAWN BY:	R. JOHNSON	DATE : JUL 2023
00.00	CHECKED BY:	B.LOFLIN	DATE : <u>AUG 2023</u>
401-	DESIGNED BY: DRAWN BY: CHECKED BY: DESIGN ENGINEE OF RECORD:	ER B.LOFLIN	DATE : <u>SEP 2023</u>

+

# STAGE I CONSTRUCTION

(INSTALL TEMPORARY BARRIER ON WESTBOUND DIRECTION.)

# STAGE II CONSTRUCTION

(PERFORM EASTBOUND WORK.REMOVE AND STORE MEDIAN AND EASTBOUND EXTERIOR RAILINGS,CURBS,AND RAILING SUPPORTS.REPLACE STRINGERS AND GRID DECK. REINSTALL EXTERIOR EASTBOUND RAILING, CURB, AND RAILING SUPPORTS.)


333 FAYETTEVILLE STREET, SUITE 500 RALEIGH, NC 27601 NC LICENSE NO. C-2979


**DOCUMENT NOT CONSIDERED FINAL** UNLESS ALL SIGNATURES COMPLETED


## NOTES:


REFER TO TRAFFIC MANAGEMENT PLANS FOR TRAFFIC PHASING AND WORK ZONE INFORMATION.

CONTRACTOR SHALL HAVE NO MORE THAN TWO ADJACENT BAYS OF STRINGERS AND GRID DECK REMOVED AT ONE TIME.









BPR.102			
11/6/2023 401_011_15BF	DESIGNED BY: DRAWN BY: CHECKED BY:	M.NIFONG R.JOHNSON B.LOFLIN	_ DATE : <u>JUL 2023</u> _ DATE : <u>JUL 2023</u> _ DATE : <u>AUG 2023</u>
11/( 401	DESIGN ENGINER OF RECORD:	ER <u>B.LOFLIN</u>	_ DATE : <u>SEP 2023</u>

+

+

# STAGE IV CONSTRUCTION

(PERFORM WESTBOUND WORK.REMOVE AND STORE WESTBOUND EXTERIOR RAILING, CURBS,AND RAILING SUPPORTS.REPLACE STRINGERS AND GRID DECK.REINSTALL EXTERIOR WESTBOUND RAILING, CURB, AND RAILING SUPPORTS)

# STAGE V CONSTRUCTION

(REINSTALL EXISTING MEDIAN RAILING, CURBS, AND RAILING SUPPORT.)


333 FAYETTEVILLE STREET, SUITE 500 RALEIGH, NC 27601 NC LICENSE NO. C-2979


## **DOCUMENT NOT CONSIDERED FINAL** UNLESS ALL SIGNATURES COMPLETED

## NOTES:

FOR TEMPORARY BARRIER ANCHOR DETAILS, SEE SHEET NO. S-5.

REFER TO TRAFFIC MANAGEMENT PLANS FOR TRAFFIC PHASING AND WORK ZONE INFORMATION.






ALL BOLTS ARE 7/8" DIAMETER ASTM F3125 GRADE A325 GALVANIZED HIGH STRENGTH BOLTS UNLESS

\* FIELD VERIFY LOCATION OF EXISTING STRINGERS


THE CONTRACTOR'S ATTENTION IS CALLED TO STRINGER CONNECTIONS AT THE END FLOORBEAMS

SEE OPEN GRID DECK DRAWINGS FOR STRINGER

		NEV	V HA	. <u>15</u> BI NOVEF	r	2.3 UNTY
		BRIDGE	- NO	0-10	5015	
		SHEET 2 C	PF 4			
STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					TION	
ASTERS great bridges. ITE 500	CAROLINI CAROLINI CAROLINI CAROLINI CAROLINI CONSERVICE	STRUCTURAL STEEL END STRINGERS				
	DocuSigned by:	REVISIONS SHEET NO.				
	96975AE68AD44DB	NO. BY:	DATE:	NO. BY:	DATE:	S-15 total
OMPLETED		1		<u>৩</u> 4		total sheets 21




\* \* \* TO FACILITATE OPERATION OF THE LIFT SPAN, TEMPORARY BRACING SHALL BE INSTALLED IMMEDIATELY AFTER THE REMOVAL OF THE EXISTING CENTERING DEVICE BRACING. CONTRACTOR SHALL SUBMIT TEMPORARY BRACING FOR APPROVAL.COST OF TEMPORARY BRACING SHALL BE INCLUDED IN THE COST OF THE STRUCTURAL STEEL.



\*\* FIELD VERIFY THIS DIMENSION AS THIS DIMENSION IS APPROXIMATED ASSUMING THAT THE LIFT SPAN FINGER JOINT WILL NEED TO BE RAISED  $\frac{3}{4}$ " ± AT EACH SOUTHWEST END STRINGER LOCATION (S8-S14). (FIELD DRILLED BOLTS THROUGH STRINGER TOP FLANGE NOT SHOWN IN THIS VIEW.)

## BOLT LEGEND:

- O EXISTING BOLT
- NEW BOLT IN EXISTING HOLE OR IN HOLE FIELD DRILLED TO MATCH EXISTING HOLE
- NEW BOLT IN NEW HOLE



# PROPOSED STRINGER S8 AT FBO

## NOTES:

ALL BOLTS ARE  $\frac{7}{8}$ " DIAMETER ASTM F3125 GRADE A325 GALVANIZED HIGH STRENGTH BOLTS UNLESS OTHERWISE SHOWN.

\* FIELD VERIFY LOCATION OF EXISTING STRINGERS BEFORE SUBMITTING SHOP DRAWINGS.

ANY BOLTS LOOSENED FROM ANY CONNECTION DURING CONSTRUCTION SHALL BE REPLACED WITH NEW BOLTS TIGHTENED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT A FEW OF THE EXISTING STRINGER CONNECTIONS AT THE END FLOORBEAMS CONTAIN RIVETS.

SEE OPEN GRID DECK DRAWINGS FOR STRINGER TO DECK CONNECTION DETAILS.