



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

JOSH STEIN  
GOVERNOR

J.R. "JOEY" HOPKINS  
SECRETARY

January 16, 2025

**Addendum No. 2**

RE: Contract # C204835

WBS # 46976.3.2

FEDERAL AID # 4697601

**Bertie County (R-5809A)**

NC-45 FROM WASHINGTON COUNTY LINE TO US-17.

**January 21, 2025 Letting**

To Whom It May Concern:

Reference is made to the proposal furnished to you on this project.

The following revisions have been made to the proposal.

<b>Page No.</b>	<b>Revision</b>
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 01-16-2025".
G-5	The Project Special Provision entitled <b>MAJOR CONTRACT ITEMS</b> has been updated.
R-1	The Project Special Provision entitled <b>LUMP SUM GRADING</b> has been added.

Please void the above listed Pages in your proposal and staple the revised Pages thereto.

On the item sheets the following pay item revisions have been made:

<b><u>Item</u></b>	<b><u>Description</u></b>	<b><u>Old Quantity</u></b>	<b><u>New Quantity</u></b>
0003-0043000000-N 226	GRADING	LUMP SUM	DELETED
0121-0063000000-N SP	GRADING	NEW ITEM	LUMP SUM
0122-0106000000-E 230	BORROW EXCAVATION	NEW ITEM	9,000 CY

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
CONTRACT STANDARDS AND DEVELOPMENT  
1591 MAIL SERVICE CENTER  
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900  
Fax: (919) 250-4127  
Customer Service: 1-877-368-4968

Location:  
1020 BIRCH RIDGE DR.  
RALEIGH, NC 27610

Website: [www.ncdot.gov](http://www.ncdot.gov)

The Contractor's bid must include these pay item revisions.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

Signed by:  
  
52C46046381F443...

Ronald E. Davenport, Jr., PE  
State Contract Officer

RED/cms  
Attachments

cc: Mr. Wiley W. Jones III, PE  
Mr. C. W. "Win" Bridgers, PE  
Mr. Ken Kennedy, PE  
Mr. Malcolm Bell  
Mr. Forrest Dungan, PE  
Ms. Jaci Kincaid  
Mr. Jon Weathersbee, PE  
Project File (2)

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH, N.C.

PROPOSAL

**INCLUDES ADDENDUM No. 2 DATED 01-16-2025**

DATE AND TIME OF BID OPENING: **Jan 21, 2025 AT 02:00 PM**

CONTRACT ID        C204835  
WBS                    46976.3.2

FEDERAL-AID NO.    4697601  
COUNTY             BERTIE  
T.I.P NO.             R-5809A  
MILES                 8.096  
ROUTE NO.            NC-45  
LOCATION                NC-45 FROM WASHINGTON COUNTY LINE TO US-17.

TYPE OF WORK        GRADING, DRAINAGE, PAVING, AND CULVERT.

**NOTICE:**

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

**BIDS WILL BE RECEIVED AS SHOWN BELOW:**

**THIS IS A ROADWAY & CULVERT PROPOSAL**

**5% BID BOND OR BID DEPOSIT REQUIRED**

---

**CONSTRUCTION MORATORIUM:**

(7-15-14)

SP1 G18B

No in-water work will be allowed from **February 15<sup>th</sup>** through **June 30<sup>th</sup>** of any year.

**CONSTRUCTION MORATORIUM:**

(1-19-16) (Rev. 5-21-21)

SP1 G18C

At individual project sites where a total of 1.0 acre or more of tree clearing will occur, no tree clearing will occur during the portion of the day that the air temperature is less than 40 degrees Fahrenheit in order to protect NLEBs that may be in torpor.

**MAJOR CONTRACT ITEMS:**

(2-19-02)(Rev. 1-16-24)

104

SP1 G28

The following listed items are the major contract items for this contract (see Article 104-5 of the *Standard Specifications*):

<b>Line #</b>	<b>Description</b>
26	Aggregate Base Course
30	Asphalt Concrete Surface Course, Type S9.5B
119	Class A Concrete (Culvert)
122	Borrow Excavation

**SPECIALTY ITEMS:**

(7-1-95)(Rev. 1-16-24)

108-6

SP1 G37

Items listed below will be the specialty items for this contract (see Article 108-6 of the *Standard Specifications*).

<b>Line #</b>	<b>Description</b>
41-45	Guardrail
50-60	Signing
72	Long-Life Pavement Markings
75	Permanent Pavement Markers
76-86	Utility Construction
87-116	Erosion Control

**FUEL PRICE ADJUSTMENT:**

(11-15-05)(Rev. 1-16-24)

109-8

SP1 G43

**Page 1-82, Article 109-8, FUEL PRICE ADJUSTMENTS**, add the following:

The base index price for DIESEL #2 FUEL is \$ **2.3274** per gallon. Where any of the following are included as pay items in the contract, they will be eligible for fuel price adjustment.

**PROJECT SPECIAL PROVISIONS****ROADWAY****CLEARING AND GRUBBING - METHOD II:**

(9-17-02)(Rev. 3-19-24)

200

SP2 R02A

Perform clearing on this project to the limits established by Method - II shown on Standard Drawing No. 200.02 of the *Roadway Standard Drawings*. Conventional clearing methods may be used except where permit drawings or conditions have been included in the proposal which require certain areas to be cleared by hand methods.

**TEMPORARY PAVEMENT:**

(8-15-00) (Rev. 4-21-15)

1101

SP2 R30A(Rev)

Construct the temporary pavement required on this project in accordance with the plans or as directed by the Engineer.

After the temporary pavement has served its purpose, remove the portions deemed unsuitable for use as a permanent part of the project as directed by the Engineer. Salvage and stockpile the aggregate base course removed from the temporary pavement at locations within the right of way, as directed by the Engineer, for removal by State Forces. Place pavement and earth material removed from the temporary pavement locations in embankments or dispose of in waste areas furnished by the Contractor.

Pipe culverts removed from the temporary pavement locations remain the property of the Contractor. Pipe culverts that are removed will be measured and will be paid at the contract unit price per linear foot for *Pipe Removal*. Payment for the construction of the temporary pavement will be made at the contract unit prices for the various items involved.

No direct payment will be made for removing the aggregate base course, earth material and pavement, as the cost of same shall be included in the lump sum price bid for *Grading*. Such prices and payments will be full compensation for the work of removing, salvaging, and stockpiling aggregate base course; and for placing earth material and pavement in embankments or disposing of earth material and pavement in waste areas.

**LUMP SUM GRADING:**

(8-17-10)(Rev. 1-16-24)

226

SP2 R16

Lump sum grading shall be performed in accordance with Section 226 Comprehensive Grading of the *Standard Specifications* except as follows:

Delete all references to **Section 230 Borrow Excavation (Item 0106)**.

**SHOULDER AND FILL SLOPE MATERIAL:**

(5-21-02)(Rev. 1-16-24)

235, 560

SP2 R45 A

**Description**

Perform the required shoulder and slope construction for this project in accordance with the applicable requirements of Section 560 and Section 235 of the *Standard Specifications*.

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,000 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	16,000 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	533 TON		
0011	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	985 SY		
0012	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (54")	224 LF		
0013	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	244 LF		
0014	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	636 LF		
0015	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	344 LF		
0016	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	160 LF		
0017	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	64 LF		
0018	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (18")	172 LF		

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (24")	60 LF		
0020	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (30")	84 LF		
0021	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (36")	60 LF		
0022	0449000000-E	310	*** RC PIPE CULVERTS, CLASS V (66")	56 LF		
0023	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0024	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	950 TON		
0025	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	1,500 SY		
0026	1121000000-E	520	AGGREGATE BASE COURSE	13,000 TON		
0027	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0028	1275000000-E	600	PRIME COAT	3,445 GAL		
0029	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	109,240 SY		
0030	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	14,800 TON		
0031	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	965 TON		
0032	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	240 TON		
0033	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0034	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	500 SY		
0035	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	112 CY		

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0037	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0038	2077000000-E	815	6" OUTLET PIPE	6 LF		
0039	2209000000-E	838	ENDWALLS	17.8 CY		
0040	2220000000-E	838	REINFORCED ENDWALLS	18.2 CY		
0041	3030000000-E	862	STEEL BEAM GUARDRAIL	5,250 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0043	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	6 EA		
0044	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	24 EA		
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,800 LF		
0046	3628000000-E	876	RIP RAP, CLASS I	222 TON		
0047	3635000000-E	876	RIP RAP, CLASS II	160 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	80 TON		
0049	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,170 SY		
0050	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	62 SF		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	268 SF		
0052	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	129 SF		



County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	3 EA		
0054	4082000000-E	903	SUPPORTS, WOOD	468 LF		
0055	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (D)	4 EA		
0056	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (E)	34 EA		
0057	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (F)	15 EA		
0058	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	3 EA		
0059	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	39 EA		
0060	4237000000-N	907	STOCKPILE SIGN, D, E OR F	1 EA		
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	112 SF		
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0064	4430000000-N	1130	DRUMS	95 EA		
0065	4445000000-E	1145	BARRICADES (TYPE III)	24 LF		
0066	4455000000-N	1150	FLAGGER	690 DAY		
0067	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0068	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	4 EA		
0069	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	2,796 LF		

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	4505000000-E	1170	REMOVE & RESET PORTABLE CONCRETE BARRIER (ANCHORED)	712 LF		
0071	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	34 EA		
0072	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	148,582 LF		
0073	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	70,010 LF		
0074	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	46,130 LF		
0075	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	530 EA		
0076	5319000000-E	1505	CLASS B CONCRETE FOR ENCASING UTILITY LINES	24 CY		
0077	5325600000-E	1510	6" WATER LINE	1,236 LF		
0078	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	10,070 LB		
0079	5562000000-E	1515	*** INSERTION VALVE (6")	2 EA		
0080	5571600000-E	1515	6" TAPPING SLEEVE & VALVE	2 EA		
0081	5800000000-E	1530	ABANDON 6" UTILITY PIPE	196 LF		
0082	5835700000-E	1540	16" ENCASEMENT PIPE	88 LF		
0083	5872500000-E	1550	BORE AND JACK OF *** (16")	88 LF		
0084	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (6")	366 LF		
0085	5882000000-N	SP	GENERIC UTILITY ITEM CONNECT TO EXISTING 6" WATER LINE	46 EA		
0086	5888000000-E	SP	GENERIC UTILITY ITEM 6" BYPASS WATER LINE	624 LF		

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	6000000000-E	1605	TEMPORARY SILT FENCE	10,500 LF		
0088	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	540 TON		
0089	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	710 TON		
0090	6012000000-E	1610	SEDIMENT CONTROL STONE	375 TON		
0091	6015000000-E	1615	TEMPORARY MULCHING	19 ACR		
0092	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	900 LB		
0093	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	4.5 TON		
0094	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0095	6029000000-E	SP	SAFETY FENCE	520 LF		
0096	6030000000-E	1630	SILT EXCAVATION	1,320 CY		
0097	6036000000-E	1631	MATTING FOR EROSION CONTROL	18,110 SY		
0098	6037000000-E	1629	COIR FIBER MAT	100 SY		
0099	6042000000-E	1632	1/4" HARDWARE CLOTH	65 LF		
0100	6045000000-E	SP	*** TEMPORARY PIPE (36")	115 LF		
0101	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0102	6071002000-E	1642	FLOCCULANT	3,235 LB		
0103	6071012000-E	1642	COIR FIBER WATTLE	7,080 LF		

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	6071030000-E	1640	COIR FIBER BAFFLE	55 LF		
0105	6084000000-E	1660	SEEDING & MULCHING	15 ACR		
0106	6087000000-E	1660	MOWING	12 ACR		
0107	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0108	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0109	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	325 LB		
0110	6108000000-E	1665	FERTILIZER TOPDRESSING	9.75 TON		
0111	6111000000-E	SP	IMPERVIOUS DIKE	44 LF		
0112	6114500000-N	1667	SPECIALIZED HAND MOWING	25 MHR		
0113	6114800000-N	SP	MANUAL LITTER REMOVAL	7 MHR		
0114	6114900000-E	SP	LITTER DISPOSAL	12 TON		
0115	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	100 EA		
0116	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0121	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0122	0106000000-E	230	BORROW EXCAVATION	9,000 CY		
<b>CULVERT ITEMS</b>						
0117	8130000000-N	414	BOX CULVERT EXCAVATION, STA ***** (398+84.00 -L-)	Lump Sum	L.S.	

County: BERTIE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0118	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	323 TON		
0119	8196000000-E	420	CLASS A CONCRETE (CULVERT)	635.7 CY		
0120	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	101,738 LB		

0936/Jan16/Q619412.7/D457202944000/E121

Total Amount Of Bid For Entire Project :