



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

August 09, 2022

Addendum No. 2

RE: Contract # C204376

WBS # 38222.3.3

FEDERAL-AID NO. 0013069

Pitt County (B-4786)

BRIDGE #38 OVER THE TAR RIVER ON US-13 IN GREENVILLE.

August 16, 2022 Letting

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the proposal.

Page No.	Revision
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 08-09-2022".
G-2	The Project Special Provision entitled INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES was revised with updated liquidated damages

Please void the above listed Pages in your proposal and staple the revised Pages thereto.

On the item sheets the following pay item revision has been made:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0134-4465000000-N-1160	TEMPORARY CRASH CUSHIONS	NEW ITEM	1 EA

The Contractor's bid must include this pay item revision.

The electronic bidding file has been updated to reflect this revision. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591


Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

Website: www.ncdot.gov

The contract will be prepared accordingly.

Sincerely,

DocuSigned by:

F81B6038A47A442...

Ronald E. Davenport, Jr., PE
State Contract Officer

RED/jjr

Attachments

cc: Mr. Boyd Tharrington, PE
Mr. Jeff Cabaniss, PE
Mr. Jon Weathersbee, PE
Mr. Ken Kennedy, PE
Mr. Mike Gwyn
Project File (2)

Mr. Forrest Dungan, PE
Ms. Jaci Kincaid
Mr. Kyle Kempf
Ms. Lori Strickland
Ms. Penny Higgins

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No.2 DATED 08-09-2022

DATE AND TIME OF BID OPENING: **Aug 16, 2022 AT 02:00 PM**

CONTRACT ID C204376

WBS 38222.3.3

FEDERAL-AID NO. 0013069

COUNTY PITT

T.I.P NO. B-4786

MILES 0.237

ROUTE NO. US-13

LOCATION BRIDGE #38 OVER THE TAR RIVER ON US-13 IN GREENVILLE.

TYPE OF WORK GRADING, DRAINAGE, PAVING, AND STRUCTURE.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY & STRUCTURE PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

the final completion date shall be a part of the work covered by the performance and payment bonds.

The liquidated damages for this contract are **Two Hundred Dollars (\$ 200.00)** per calendar day. These liquidated damages will not be cumulative with any liquidated damages which may become chargeable under Intermediate Contract Time Number 1. At the preconstruction conference the Contractor shall declare his expected date for beginning work. Should the Contractor desire to revise this date after the preconstruction conference, he shall notify the Engineer in writing at least thirty (30) days prior to the revised date.

INTERMEDIATE CONTRACT TIME NUMBER 1 AND LIQUIDATED DAMAGES:

(12-18-07) (Rev. 2-21-12)

108

SP1 G13 B

Except for that work required under the Project Special Provisions entitled *Planting, Reforestation* and/or *Permanent Vegetation Establishment*, included elsewhere in this proposal, the Contractor will be required to complete all work included in this contract and shall place and maintain traffic on same.

The date of availability for this intermediate contract time is the date of availability of the contract.

The completion date for this intermediate contract time is the date which is Eight Hundred Twenty-Five (**825**) consecutive calendar days after the date of availability.

The liquidated damages for this intermediate contract time are **Two Thousand Dollars (\$ 2,000.00)** per calendar day.

Upon apparent completion of all the work required to be completed by this intermediate date, a final inspection will be held in accordance with Article 105-17 and upon acceptance, the Department will assume responsibility for the maintenance of all work except *Planting, Reforestation* and/or *Permanent Vegetation Establishment*. The Contractor will be responsible for and shall make corrections of all damages to the completed roadway caused by his planting operations, whether occurring prior to or after placing traffic through the project.

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12) (Rev. 10-15-13)

104

SP1 G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *2018 Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Department will be responsible for preparing the required National Pollutant Discharge Elimination System (NPDES) inspection records.

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0028000000-N	SP	TYPE I STANDARD APPROACH FILL STATION ***** (28+03.00 -L-)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	600 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	600 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,100 SY		
0009	0223000000-E	275	ROCK PLATING	1,150 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	154 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	820 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	48 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	522 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	84 LF		
0015	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	63 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	3,030 SY		
0019	1330000000-E	607	INCIDENTAL MILLING	540 SY		
0020	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	585 TON		
0021	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	465 TON		
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	810 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	100 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0026	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	500 SY		
0027	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	84 CY		
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0029	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE	6 LF		
0031	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	1 EA		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0033	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2 EA		
0034	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0036	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	20 LF		
0038	2556000000-E	846	SHOULDER BERM GUTTER	480 LF		
0039	3030000000-E	862	STEEL BEAM GUARDRAIL	887.5 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0041	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	5 EA		
0042	3317000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE B- 77	4 EA		
0043	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,350 LF		
0044	3389150000-N	SP	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TL-3)	2 EA		
0045	3595000000-E	869	RELAPPING GUARDRAIL	262.5 LF		
0046	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0047	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,775 SY		
0048	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	65 SF		
0049	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	15 LF		
0050	4082000000-E	903	SUPPORTS, WOOD	155 LF		
0051	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)	8 EA		
0053	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	4 EA		
0054	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	6 EA		
0055	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0056	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0057	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0058	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0059	4430000000-N	1130	DRUMS	343 EA		
0060	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0061	4480000000-N	1165	TMA	2 EA		
0062	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,747 LF		
0063	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6,020 LF		
0064	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	60 LF		
0065	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12 EA		
0066	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,775 LF		
0067	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM POLYUREA PAVEMENT MARKING LINES (4", 20 MILS) (STANDARD GLASS BEADS)	2,580 LF		
0068	4905100000-N	SP	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER	105 EA		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	5325800000-E	1510	8" WATER LINE	793 LF		
0070	5326200000-E	1510	12" WATER LINE	838 LF		
0071	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	4,300 LB		
0072	5546000000-E	1515	8" VALVE	2 EA		
0073	5558000000-E	1515	12" VALVE	2 EA		
0074	5801000000-E	1530	ABANDON 8" UTILITY PIPE	535 LF		
0075	5804000000-E	1530	ABANDON 12" UTILITY PIPE	882 LF		
0076	5912000000-N	SP	GENERIC UTILITY ITEM 12" PIPE HANGER SYSTEM	Lump Sum	L.S.	
0077	5912000000-N	SP	GENERIC UTILITY ITEM 8" PIPE HANGER SYSTEM	Lump Sum	L.S.	
0078	6000000000-E	1605	TEMPORARY SILT FENCE	1,445 LF		
0079	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0080	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0081	6012000000-E	1610	SEDIMENT CONTROL STONE	640 TON		
0082	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0083	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0084	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0085	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6029000000-E	SP	SAFETY FENCE	1,320 LF		
0087	6030000000-E	1630	SILT EXCAVATION	70 CY		
0088	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,260 SY		
0089	6037000000-E	SP	COIR FIBER MAT	1,200 SY		
0090	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0091	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	755 SY		
0092	6070000000-N	1639	SPECIAL STILLING BASINS	28 EA		
0093	6071012000-E	SP	COIR FIBER WATTLE	300 LF		
0094	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0095	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0096	6087000000-E	1660	MOWING	3 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0101	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0102	6114800000-N	SP	MANUAL LITTER REMOVAL	2 MHR		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	6114900000-E	SP	LITTER DISPOSAL	1 TON		
0104	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0105	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0106	6123000000-E	1670	REFORESTATION	0.1 ACR		
0134	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
STRUCTURE ITEMS						
0107	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (28+03.00-L-)	Lump Sum	L.S.	
0108	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (28+03.00-L-)	Lump Sum	L.S.	
0109	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0110	8105500000-E	411	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	1,966.25 LF		
0111	8111000000-E	411	PERMANENT STEEL CASING FOR ***- *** DIA DRILLED PIER (4'-6")	441.15 LF		
0112	8112730000-N	450	PDA TESTING	2 EA		
0113	8113000000-N	411	SID INSPECTIONS	7 EA		
0114	8114000000-N	411	SPT TESTING	7 EA		
0115	8115000000-N	411	CSL TESTING	7 EA		
0116	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (28+03.00-L-)	Lump Sum	L.S.	

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0117	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	22,585 SF		
0118	8161000000-E	420	GROOVING BRIDGE FLOORS	20,835 SF		
0119	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	482.1 CY		
0120	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (28+03.00-L-)	Lump Sum	L.S.	
0121	8217000000-E	425	REINFORCING STEEL (BRIDGE)	220,030 LB		
0122	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	67,749 LB		
0123	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	2,700.83 LF		
0124	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)	19 EA		
0125	8364000000-E	450	HP 12 X 53 STEEL PILES	1,425 LF		
0126	8393000000-N	450	PILE REDRIVES	10 EA		
0127	8503000000-E	460	CONCRETE BARRIER RAIL	1,136.77 LF		
0128	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	330 TON		
0129	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	370 SY		
0130	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0131	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0132	8727000000-N	SP	ELECTRICAL CONDUIT SYSTEM FOR SIGNALS AT STA ***** (28+03.00-L-)	Lump Sum	L.S.	
0133	8897000000-N	SP	GENERIC STRUCTURE ITEM THERMAL INTEGRITY PROFILER TESTING	7 EA		

County: PITT

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

0902/Aug09/Q389735.45/D625594612000/E134

Total Amount Of Bid For Entire Project :
