



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

December 14, 2022

Addendum No. 2

RE: Contract # C204656

WBS # 47954.3.1

FEDERAL-AID NO. 0540046

Wake County (I-5999)

I-540 FROM US-70 (GLENWOOD AVE) TO EAST OF TRIANGLE TOWN BLVD.

December 20, 2022 Letting

To Whom It May Concern:

Reference is made to the plans and proposal form furnished to you on this project.

The following revision has been made to the Roadway plans.

Sheet No.	Revision
16	Revised to reflect quantity change shown below.

Please void the above listed Sheet in your plans and staple the revised Sheet thereto.

The following revisions have been made to the proposal.

Page No.	Revision
Proposal Cover	Note added that reads "Includes Addendum No. 2 Dated 12-14-2022".

Please void the above listed Page in your proposal and staple the revised Page thereto.

On the item sheets the following pay item revision has been made:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0081-756600000-N-1733	DELINEATOR MARKER	3,893 EA	DELETED

The Contractor's bid must include this pay item revision.

The electronic bidding file has been updated to reflect this revision. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

DocuSigned by:

F81B6038A47A442...

Ronald E. Davenport, Jr., PE
State Contract Officer

RED/cms
Attachments

cc: Mr. Boyd Tharrington, PE
Mr. Brandon H. Jones, PE
Mr. Ken Kennedy, PE
Mr. Jon Weathersbee, PE
Mr. Mike Gwyn
Project File (2)

Mr. Forrest Dungan, PE
Ms. Jaci Kincaid
Ms. Penny Higgins
Ms. Lori Strickland

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No.2 DATED 12-14-2022

DATE AND TIME OF BID OPENING: **Dec 20, 2022 AT 02:00 PM**

CONTRACT ID C204656
WBS 47954.3.1

FEDERAL-AID NO. 0540046
COUNTY WAKE
T.I.P NO. I-5999
MILES 12.288
ROUTE NO. I-540
LOCATION I-540 FROM US-70 (GLENWOOD AVE) TO EAST OF TRIANGLE TOWN BLVD.

TYPE OF WORK PAVEMENT REHABILITATION.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	150 CY		
0003	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER GRADING	1 SMI		
0004	1260000000-E	SP	AGGREGATE SHOULDER BORROW	27 TON		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	180,479 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	12,059 SY		
0007	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	611 TON		
0008	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	20,722 TON		
0009	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	55 TON		
0010	1577000000-E	620	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	2,194 TON		
0011	1702000000-E	657	SEALING EXISTING PAVEMENT CRACKS & JOINTS	500 LB		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	102 TON		
0013	1820000000-E	SP	ASPHALT SURFACE TREATMENT, FOG SEAL	253,400 SY		
0014	1838000000-E	660	EMULSION FOR ASPHALT SURFACE TREATMENT	30,408 GAL		
0015	1839140000-E	661	ULTRA-THIN BONDED WEARING COURSE	17,725 TON		
0016	2473000000-N	SP	GENERIC DRAINAGE ITEM DRAINAGE STRUCTURE CLEAN-OUT	10 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2484000000-E	SP	GENERIC DRAINAGE ITEM CLEAR EXISTING SHOULDER BERM GUTTER	500 LF		
0018	2600000000-N	848	RETROFIT EXISTING CURB RAMPS	1 EA		
0019	3030000000-E	862	STEEL BEAM GUARDRAIL	2,675 LF		
0020	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0021	3210000000-N	862	GUARDRAIL END UNITS, TYPE CAT-1	1 EA		
0022	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	1 EA		
0023	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,675 LF		
0024	3435000000-N	SP	GENERIC GUARDRAIL ITEM GUARDRAIL AND BARRIER DELINEATORS	3,893 EA		
0025	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	3 CY		
0026	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	3,313 LB		
0027	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	408 LF		
0028	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	50 EA		
0029	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (B)	41 EA		
0030	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	16 EA		
0031	4114000000-N	904	SIGN ERECTION, MILEMARKERS	32 EA		
0032	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	16 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	13 EA		
0034	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	91 EA		
0035	4251000000-N	907	DISPOSAL OF LIGHTING SYSTEM	31 EA		
0036	4263000000-N	907	DISPOSAL OF WALKWAY	33 EA		
0037	4360000000-N	SP	GENERIC SIGNING ITEM CUTTING OF SIGN HANGERS, OVERHEAD	158 EA		
0038	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	704 SF		
0039	4423000000-N	SP	WORK ZONE DIGITAL SPEED LIMIT SIGNS	5 EA		
0040	4424000000-N	SP	WORK ZONE PRESENCE LIGHTING	14 EA		
0041	4434000000-N	SP	SEQUENTIAL FLASHING WARNING LIGHTS	12 EA		
0042	4447000000-E	SP	PEDESTRIAN CHANNELIZING DEVICES	24 LF		
0043	4510000000-N	1190	LAW ENFORCEMENT	5,149 HR		
0044	4520000000-N	1266	TUBULAR MARKERS (FIXED)	70 EA		
0045	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM CONNECTED LANE CLOSURE DEVICE	2 EA		
0046	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM DOUBLE LANE CLOSURE	182 EA		
0047	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM RAMP/LOOP CLOSURES	28 EA		
0048	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM RAMP/LOOP TRAFFIC CONTROL	11 EA		
0049	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM SINGLE LANE CLOSURE	77 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0050	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8,200 LF		
0051	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	467,750 LF		
0052	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,040 LF		
0053	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	23,980 LF		
0054	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	710 LF		
0055	4720000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	12 EA		
0056	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	204 EA		
0057	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (II)	21,750 LF		
0058	4785000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (12") (II)	280 LF		
0059	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (II)	80 LF		
0060	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (II)	8 EA		
0061	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (II)	9 EA		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,400 LF		
0063	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	866,870 LF		
0064	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	6,080 LF		
0065	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	43,300 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0066	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	790 LF		
0067	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24 EA		
0068	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	268 EA		
0069	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	395,312 LF		
0070	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	411 LF		
0071	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	533 LF		
0072	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	52 EA		
0073	4905100000-N	SP	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKER	7,410 EA		
0074	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0075	6000000000-E	1605	TEMPORARY SILT FENCE	300 LF		
0076	6029000000-E	SP	SAFETY FENCE	40 LF		
0077	6084000000-E	1660	SEEDING & MULCHING	0.75 ACR		
0078	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0079	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,567 LF		
0080	7552000000-N	1731	INTERCONNECT CENTER	4 EA		
0082	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV WOOD POLE	3 EA		
0083	7980000000-N	SP	GENERIC SIGNAL ITEM DIGITAL CCTV CAMERA	5 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	7980000000-N	SP	GENERIC SIGNAL ITEM DIGITAL CCTV CAMERA ASSEMBLY	8 EA		
0085	7980000000-N	SP	GENERIC SIGNAL ITEM DMS WALKWAY	1 EA		
0086	7980000000-N	SP	GENERIC SIGNAL ITEM DYNAMIC MESSAGE SIGN (TYPE-2C)	2 EA		
0087	7980000000-N	SP	GENERIC SIGNAL ITEM FIELD EQUIPMENT CABINET	9 EA		
0088	7980000000-N	SP	GENERIC SIGNAL ITEM METER BASE/DISCONNECT COMBINATION PANEL	3 EA		
0089	7980000000-N	SP	GENERIC SIGNAL ITEM MODIFY EXISTING ELECTRICAL SERVICE	5 EA		
0090	7980000000-N	SP	GENERIC SIGNAL ITEM REMOVAL AND DISPOSAL OF EXISTING DMS COMPONENTS	2 EA		
0091	7980000000-N	SP	GENERIC SIGNAL ITEM WIRELESS ETHERNET REPEATER SYSTEM	7 EA		
0092	7980000000-N	SP	GENERIC SIGNAL ITEM WIRELESS ETHERNET SYSTEM	10 EA		
0093	7990000000-E	SP	GENERIC SIGNAL ITEM 3-WIRE COPPER FEEDER CONDUCTORS	15 LF		

1145/Dec14/Q2404139.75/D409864040000/E92

Total Amount Of Bid For Entire Project :

