

Interstate Maintenance Project Synopsis

Project Description and Purpose:

- The project will include management and performance of routine maintenance activities on interstates in Mecklenburg and Cabarrus Counties. The interstate routes include I-77, I-85, I-485, and I-277, for a total, approximate length of 135 centerline miles. The Contractor shall manage and perform maintenance activities associated with roadways, drainage, structures, roadside, vegetation and aesthetics, and traffic services.

Bridge and Structure Maintenance:

- The Contractor shall perform bridge, culvert, over head sign structure, and retaining wall routine maintenance, including collision damage repair.

Roadside Maintenance:

- The Contractor shall perform landscaping and plant bed maintenance, litter and debris removal, brush and tree control, and clean up mowing, on the state right of way.

Pavement Maintenance:

- The Contractor shall perform paved shoulder maintenance, concrete and asphalt pavement repair, and other routine and preventive maintenance activities such as crack sealing.

Traffic Maintenance:

- The Contractor shall perform all routine sign and sign structure maintenance on the state right of way, except for the variable message signs.
- The Contractor shall maintain and install if necessary pavement markers and markings.

Roadway Maintenance:

- The Contractor shall perform all routine roadway maintenance activities on the state right of way, except where it is otherwise stated. This includes but is not limited to all drainage features, slopes, barriers, guardrails, guiderails, end treatments and unpaved shoulder maintenance.

Emergency Maintenance Repairs:

- The Contractor shall be prepared to respond and deploy resources to assist NCDOT forces if necessary.
- The Contractor shall initiate maintenance repairs upon notification or discovery.

Rest Area Roadways:

- The Contractor shall only perform routine maintenance on all paved areas within the rest area facility. Grounds and facilities are not included in this project.

The areas of interstate maintenance outlined above are not all inclusive for this project.