

**Synopsis**  
**Multiple Bridge Replacements Division 6**  
**October 1, 2018**

**General**

Two individual contracts will be used to replace 7 bridges. Neither of these contracts include the construction of culverts.

As development work is ongoing, it is possible that a few of these advertised bridges as shown in the interactive maps on the project website will be deleted or replaced with other sites. These substitutions may or may not occur prior to shortlisting.

Currently, the two contracts include the following number of bridges:

<b>Division</b>	<b>Number of Bridges to be Constructed</b>
<b>6 Set A</b>	<b>3</b>
<b>6 Set B</b>	<b>4</b>

All of the bridges in Division 6 contracts are less than one hundred feet.

Many of these bridges are also located on the Subregional or Regional Tier, in such case, a general overview of the Roadway, Hydraulics, Geotechnical, and Structures Scope of Work is specified in the Sub Regional Tier Design Guidelines for Bridge Projects dated February 2008. An electronic copy of these documents is located at:

<https://connect.ncdot.gov/resources/Structures/Pages/Structure-Resources.aspx>

**Planning**

The Department is currently preparing the environmental documents for the bridges. The Design-Build Team will be responsible for providing impact quantities to complete this environmental document.

**Roadway**

Roadway plans will be the responsibility of the Design-Build Team. Pavement designs will be provided by the Department.

**Hydraulics**

The Design-Build Team shall be responsible for all hydraulic designs and shall provide signed and sealed Bridge Reports for all bridge replacements. The Design-Build Team shall be responsible for all storm drainage design, permit drawings and construction and shall obtain FEMA compliance for the regulated floodways.

The Department will provide information prior to issuance of the Final Request for Proposals to establish the type and size of bridge to be bid.

## **Permitting**

The Design-Build Team shall be responsible for preparing design plan sheets and providing all data necessary for the Department to obtain the environmental permit for each bridge replacement. These will often include a Nationwide Permit 3 or 14 and a Water Quality Certificate.

## **Structures**

The Design-Build Team will be responsible for the design and construction of all structures necessary to complete the projects. Standard bridge plans will be made available and may be used at certain sites; however, the design must be signed and sealed by the Design-Build Team.

Certain structure types will be disallowed or prescribed within each individual contract.

## **Geotechnical**

The Department will provide 2 to 4 borings per bridge to the Design-Build Teams. The Design-Build Team shall be responsible for all geotechnical recommendations, as well as any necessary supplemental borings, roadway and structural investigations.

## **Traffic Management**

Most bridge sites will be conducive to off-site detours, but some will require an on-site detour, staged construction or new alignment. The Design-Build Team will be responsible for Traffic Control Plans as appropriate for the bridge site as will be detailed in the Requests for Proposals.

A list of parameters, such as lane closures, time restrictions and general guidelines will be provided in the Request for Proposals.

## **Erosion and Sedimentation Control**

The Design-Build Team shall be responsible for all erosion control designs and implementation.

## **Signing and Pavement Markings**

Pavement marking plans will be the responsibility of the Design-Build Team. Permanent signing on these projects will be minimal and will be the responsibility of the Design-Build Team.

## **Right-of-Way and Utilities**

In general, the Design-Build Team will be responsible for acquisition of additional right of way, as necessary, to construct the projects in Division 6.

The Design-Build Team will be responsible for the coordination of all utility relocations necessary for construction. It is anticipated that the cost of utility relocations will be paid by the utility owners or the Department.

## **Surveys**

The Department will provide initial survey information pre-bid. The Design-Build Team shall be responsible for any supplemental location and construction surveys.

## **Construction Engineering Inspection**

CEI on all contracts will be performed by the Department or its agent.

## **Provided Materials**

The Department will provide surveys, including property ties, geotechnical borings, pavement designs, pre-design hydraulic reports, and environmental document or minimum criteria checklists, bridge inspection reports, and field scoping meeting minutes.

## **Contract Completion Date**

As these are Express Design-Build projects without a Technical Proposal, an overall contract completion date will be set in the contract, with associated liquidated damages. The date will be established to allow for greater flexibility in the Design-Build Team scheduling and completion of the work.

Intermediate contract times for road closures or for early completion of certain bridges, with associated liquidated damages, will be as outlined in the Request for Proposals.

## **Compensation**

To reduce the amount of work necessary to be performed pre-bid by the Design-Build Teams, and to ensure to the greatest extent possible that all Design-Build Teams are bidding on similar designs, the Department will include an estimated bridge length, bridge width, and assumed geotechnical design parameter (e.g., embedment, bearing elevation) in the Requests for Proposals. The Design-Build Team will bid a unit price for these high level pay item quantities. However, the Department will allow the Design-Build Team to bid a lump sum for all work at certain bridge site to enhance the opportunity for innovation in the procurement.

It is likely that the bridge length, etc. will change from that estimated in the contract. In such event, a supplemental agreement will be entered into for the additional (or lesser) bridge length, foundation depth, etc. from those quantities placed in the Request for Proposals.

A lump sum item will most likely be included to provide for all design work and other ancillary construction work including but not limited to minor approach work, approach slabs, supplemental investigations, drainage, erosion control, traffic control, etc.