

# STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

April 29, 2014

#### Addendum No. 1

Contract No.: C 203528
WBS No.: 17BP.12.R.103
Counties: Alexander & Iredell

Project Description: Express Design-Build Bridge Replacements

RE: Addendum No. 1 to Final RFP

#### **May 20, 2014 Letting**

To Whom It May Concern:

Reference is made to the Final Request for Proposals dated April 17, 2014 recently furnished to you on the above project. We have since incorporated changes, and have attached a copy of Addendum No. 1 for your information. Please note that all revisions have been highlighted in gray and are as follows:

The second page of the *Table of Contents* has been revised. Please void the second page in your proposal and staple the revised second page thereto.

Page No. 89 of the Standard Special Provisions has been revised. Please void Page No. 89 in your proposal and staple the revised Page No. 89 thereto.

If you have any questions or need additional information, I can be reached by telephone at (919) 707-6900.

Sincerery

R.A. Garris, P.E. Contract Officer

cc: Ms. Teresa Bruton, PE

Mr. Rodger Rochelle, PE Mr. Reuben Chandler, PE Ms. Virginia Mabry

File

RALEIGH NC

FAX: 919-250-4119

Website: www.NCDOT.ORG

TELEPHONE: 919-707-6900

Environmental Permits	. 64
Erosion and Sedimentation Control	. 67
Right of Way	
Utilities Coordination	
STANDARD SPECIAL PROVISIONS	
Plant and Pest Quarantines	. 82
Gifts from Vendors and Contractors	. 82
Liability Insurance	. 83
State Highway Administrator Title Change	. 83
Select Granular Material	. 83
Bridge Approach Fills	. 84
Asphalt Pavements-Superpave	. 86
Asphalt Binder Content of Asphalt Plant Mixes	. 88
Asphalt Plant Mixtures	. 88
Subsurface Drainage	. 89
Guardrail Anchor Units, Type 350	. 89
Preformed Scour Hole with Level Spreader Apron	. 90
Street Signs and Markers and Route Markers	. 91
Materials	
Select Material, Class III, Type 3	
Shoulder and Slope Borrow	. 101
Temporary Shoring	. 102
On-the-Job Training	
Availability of Funds – Termination of Contracts	. 116
NCDOT General Seed Specifications for Seed Quality	. 117
Errata	. 120
Minimum Wages	. 122
Division One	. 123

# PROPOSAL FORMS - ITEMIZED SHEET, ETC.

**Itemized Proposal Sheet** 

Fuel Usage Factor Chart and Estimate of Quantities

Listing of MBE / WBE Subcontractors

Execution of Bid, Non-Collusion Affidavit, Debarment Certification and Gift Ban Certification Signature Sheet

C 203528 (17BP.12.R.103)

Standard Special Provision Alexander and Iredell Counties

## **SUBSURFACE DRAINAGE**

(9-1-11) DB8 R05

Revise the 2012 Standard Specifications for Roads and Structures as follows:

### Page 8-11, Article 815-1, Delete the first sentence and replace with the following:

The Design-Build Team shall construct subsurface drains, underdrains, blind drains and other types of drains where groundwater is within 6 feet of subgrade.

#### **GUARDRAIL ANCHOR UNITS, TYPE 350**

(4-22-14) DB8 R65

#### **Description**

Furnish and install guardrail anchor units in accordance with the details in the plans as developed by the Design-Build Team, the applicable requirements of Section 862 of the 2012 *Standard Specifications for Roads and Structures*, and at locations shown in the plans.

#### **Materials**

The Design-Build Team may at his option, furnish any one of the guardrail anchor units or approved equal.

# Guardrail anchor unit (ET-Plus) as manufactured by:

TRINITY INDUSTRIES, INC. 2525 N. STEMMONS FREEWAY DALLAS, TEXAS 75207 TELEPHONE: 800-644-7976

The guardrail anchor unit (SKT 350) as manufactured by:

ROAD SYSTEMS, INC. 3616 OLD HOWARD COUNTY AIRPORT BIG SPRING, TEXAS 79720 TELEPHONE: 915 263-2435

Prior to installation the Design-Build Team shall submit to the Engineer:

- 1. FHWA acceptance letter for each guardrail anchor unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Section 106-2 of 2012 *Standard Specifications for Roads and Structures*.
- 2. Certified working drawings and assembling instructions from the manufacturer for each guardrail anchor unit in accordance with Section 105-2 of the 2012 *Standard Specifications for Roads and Structures*.