

PROJECT: 38868.1.1 ID: R-3601

CONTENTS

SHEET	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5-10	BORE LOGS & CORE REPORT
11	CORE PHOTOGRAPH

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 38868.1.1 (R-3601) F.A. PROJ. NHS-0017(68)
COUNTY BRUNSWICK
PROJECT DESCRIPTION BRIDGE NO. 108 ON US 17 S / NC 133 S /
NC 74 / 76 W OVER ALLIGATOR CREEK AT -LLT- STA. 110 + 23.33

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-3601	1	11

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU UN-PLACED TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

C.M. WRIKE

SOME PERSONNEL

INVESTIGATED BY T.C. BOTTOMS
CHECKED BY D.N. ARGENBRIGHT
SUBMITTED BY D.N. ARGENBRIGHT
DATE MARCH 2012

DRAWN BY: C.P. TURNER

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.



SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

REVISÉ 09/23/09



WBS 38868.1.1			TIP R-3601			COUNTY BRUNSWICK			GEOLOGIST Brandsen, J.				
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK									GROUND WTR (ft)				
BORING NO. EB1-B			STATION 108+95			OFFSET 23 ft RT			ALIGNMENT -LLT-		0 HR. N/A		
COLLAR ELEV. 6.8 ft			TOTAL DEPTH 85.0 ft			NORTHING 177,930			EASTING 2,311,307		24 HR. 7.9		
DRILL RIG/HAMMER EFF/DATE SME3193 CME-550X 80% 06/07/2011						DRILL METHOD Mud Rotary			HAMMER TYPE Automatic				
DRILLER Contract Driller			START DATE 01/13/12			COMP. DATE 01/13/12			SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		MOI	
-70						Match Line							COASTAL PLAIN GRAY AND GREEN SILT, WET (PEEDEE FORMATION) (continued)
	-71.7	78.5	20	32	28								



WBS 38868.1.1			TIP R-3601		COUNTY BRUNSWICK		GEOLOGIST Wrike, C. M.								
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK							GROUND WTR (ft)								
BORING NO. B2-B			STATION 109+99		OFFSET 29 ft RT		ALIGNMENT -LLT-								
COLLAR ELEV. -11.1 ft			TOTAL DEPTH 65.5 ft		NORTHING 177,934		EASTING 2,311,411								
							0 HR. N/A								
							24 HR. N/A								
DRILL RIG/HAMMER EFF./DATE SUM3359 CME-450 87% 07/22/2011					DRILL METHOD Mud Rotary			HAMMER TYPE Automatic							
DRILLER Contract Driller			START DATE 02/08/12		COMP. DATE 02/08/12		SURFACE WATER DEPTH 13.2ft								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-10	-11.1	0.0	2	2	1									-11.1	GROUND SURFACE 0.0
-15	-15.4	4.3	1	1	1										ALLUVIAL TAN SAND WITH WOOD FRAGMENTS, SATURATED
-20	-20.2	9.1	1	2	3										
-25	-25.3	14.2	5	5	13										
-30	-30.1	19.0	14	30	48									-28.1	COASTAL PLAIN 17.0
-35	-34.9	23.8	20	100/0.3										-32.3	GRAY AND GREEN SAND WITH CALCAREOUS SANDSTONE LAYERS, SATURATED (PEEDEE FORMATION)
-40	-39.9	28.8	27	100/0.4										-32.9	21.2
-45	-44.7	33.6	47	100/0.5											21.8
-50	-49.7	38.6	100/0.4											-44.7	
-55	-54.7	43.6	37	31	43									-46.0	33.6
-60	-59.7	48.6	12	9	8										34.9
-65	-64.9	53.8	31	20	31									-62.5	
-70	-69.9	58.8	100/0.2											-63.0	51.4
-75	-75.1	64.0	23	11	8									-69.6	58.5
														-70.7	59.6
															COASTAL PLAIN GRAY AND GREEN SILT, WET (PEEDEE FORMATION)
														-76.6	65.5
															Boring Terminated at Elevation -76.6 ft in Very Stiff Silt

[illegible]



WBS 38868.1.1		TIP R-3601		COUNTY BRUNSWICK		GEOLOGIST Wrike, C. M.							
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK								GROUND WTR (ft)					
BORING NO. B3-B		STATION 110+50		OFFSET 32 ft RT		ALIGNMENT -LLT-		0 HR. N/A					
COLLAR ELEV. -12.3 ft		TOTAL DEPTH 63.5 ft		NORTHING 177,935		EASTING 2,311,462		24 HR. N/A					
DRILL RIG/HAMMER EFF/DATE SUM3359 CME-450 87% 07/22/2011				DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic						
DRILLER Contract Driller		START DATE 02/08/12		COMP. DATE 02/08/12		SURFACE WATER DEPTH 12.6ft							
CORE SIZE NX-NQ		TOTAL RUN 15.8 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		LOG	ELEV. (ft)	DESCRIPTION AND REMARKS	DEPTH (ft)
-28.7	-28.7	16.4	5.3		(0.7)	(0.0)		(0.2)	(0.0)		-29.3	Begin Coring @ 16.4 ft	17.0
-30					13%	0%		100%	0%		-29.5	GRAY AND GREEN SAND WITH CALCAREOUS SANDSTONE LAYERS, SATURATED (PEEDEE FORMATION) (continued)	17.2
								(0.4)	(0.0)		-30.8		18.5
	-34.0	21.7						100%	0%		-31.2		18.9
-35			5.2		(0.7)	(0.0)		(0.2)	(0.0)		-32.3		20.0
					13%	0%		100%	0%		-32.5		20.2
								(0.3)	(0.0)		-34.3		22.0
	-39.2	26.9			(0.4)	(0.0)		(0.2)	(0.0)		-34.6		22.3
-40			5.3		8%	0%		100%	0%		-35.8		23.5
								(0.3)	(0.0)		-36.0		23.7
								(0.2)	(0.0)		-37.3		25.0
	-44.5	32.2						(0.3)	(0.0)		-37.6		25.3
								100%	0%		-40.3		28.0
-45							RS-1	(0.2)	(0.0)		-40.5		28.2
								100%	0%		-42.3		30.0
								(0.2)	(0.0)		-42.5		30.2
								100%	0%				
-50								(0.2)	(0.0)				
								100%	0%				
-55								(0.2)	(0.0)				
								100%	0%				
-60								(0.2)	(0.0)				
								100%	0%				
-65								(0.2)	(0.0)		-62.3	COASTAL PLAIN	50.0
								100%	0%			GRAY AND GREEN SILT WITH CALCAREOUS SANDSTONE LAYERS, WET (PEEDEE FORMATION)	
-70								(0.2)	(0.0)		-69.1		56.8
								100%	0%		-69.9		57.6
-75								(0.2)	(0.0)				
								100%	0%		-75.8	Boring Terminated at Elevation -75.8 ft in Hard Silt	63.5
								(0.2)	(0.0)			RS-1 Tested for Point Load Strength Indices	



WBS 38868.1.1		TIP R-3601		COUNTY BRUNSWICK		GEOLOGIST Wrike, C. M.								
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK							GROUND WTR (ft)							
BORING NO. B5-B		STATION 111+43		OFFSET 28 ft RT		ALIGNMENT -LLT-		0 HR. N/A						
COLLAR ELEV. -2.6 ft		TOTAL DEPTH 70.9 ft		NORTHING 177,947		EASTING 2,311,554		24 HR. N/A						
DRILL RIG/HAMMER EFF./DATE SUM3359 CME-450 87% 07/22/2011				DRILL METHOD Mud Rotary			HAMMER TYPE Automatic							
DRILLER Contract Driller		START DATE 02/07/12		COMP. DATE 02/07/12		SURFACE WATER DEPTH 8.0ft								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
0														
	-2.6	0.0	WOH	WOH	WOH									
-5														
	-7.1	4.5	2	1	1									
-10														
	-12.1	9.5	1	1	1									
-15														
	-17.1	14.5	4	5	6									
-20														
	-22.1	19.5	2	2	3									
-25														
	-26.8	24.2	24	28	44									
-30														
	-31.8	29.2	39	100/0.3										
-35														
	-36.8	34.2	75	60/0.1										
-40														
	-41.8	39.2	75	100/0.5										
-45														
	-46.8	44.2	23	30	27									
-50														
	-51.8	49.2	24	38	46									
-55														
	-56.8	54.2	8	8	9									
-60														
	-61.8	59.2	14	16	22									
-65														
	-67.0	64.4	5	5	26									
-70														
	-72.0	69.4	7	12	37									

WBS 38868.1.1		TIP R-3601		COUNTY BRUNSWICK		GEOLOGIST Brandsen, J.							
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK							GROUND WTR (ft)						
BORING NO. EB2-B		STATION 111+93		OFFSET 31 ft RT		ALIGNMENT -LLT-		0 HR. N/A					
COLLAR ELEV. 5.1 ft		TOTAL DEPTH 105.0 ft		NORTHING 177,948		EASTING 2,311,604		24 HR. 4.7					
DRILL RIG/HAMMER EFF./DATE SME3193 CME-550X 80% 06/07/2011				DRILL METHOD Mud Rotary			HAMMER TYPE Automatic						
DRILLER Contract Driller		START DATE 01/10/12		COMP. DATE 01/11/12		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
10													
5													
0	1.6	3.5	WOH	1	1	2						5.1	GROUND SURFACE
													ROADWAY EMBANKMENT
													GRAY SILT, MOIST TO WET
-5	-3.4	8.5	WOH	WOH	WOH	0							
-10	-8.4	13.5	WOH	WOH	WOH	0							
-15	-13.4	18.5	WOH	WOH	WOH	0							
-20	-18.4	23.5	2	3	4	7						-10.9	ALLUVIAL
													GRAY SILT WITH MODERATE ORGANIC
													MATERIAL, WET
-25	-23.4	28.5	1	1	2	3						-16.9	ALLUVIAL
													BROWN AND GRAY SAND, SATURATED
-30	-28.4	33.5	1	1	1	2							
-35	-33.4	38.5	60	40/0.2						100/0.7		-32.9	COASTAL PLAIN
													GRAY AND GREEN SAND WITH
-40	-38.4	43.5	100/0.5							100/0.5		-36.9	CALCAREOUS SANDSTONE LAYERS,
													SATURATED (PEEDEE FORMATION)
-45	-43.4	48.5	100/0.4							100/0.4		-39.4	
												-40.9	
-50	-48.4	53.5	21	54	46/0.3					100/0.8		-44.4	
												-48.4	
-55	-53.4	58.5	55	45/0.3						100/0.8		-50.4	
												-51.4	
-60	-58.4	63.5	12	34	45	79						-54.9	
-65	-63.4	68.5	20	24	26	50						-61.4	
												-62.4	
-70	-68.4	73.5	44	23	22	45							

WBS 38868.1.1			TIP R-3601			COUNTY BRUNSWICK			GEOLOGIST Brandsen, J.					
SITE DESCRIPTION BRIDGE NO. 108 ON -LLT- (US17S-NC133S-US74W-US76W) OVER ALLIGATOR CREEK									GROUND WTR (ft)					
BORING NO. EB2-B			STATION 111+93			OFFSET 31 ft RT			ALIGNMENT -LLT-			0 HR. N/A		
COLLAR ELEV. 5.1 ft			TOTAL DEPTH 105.0 ft			NORTHING 177,948			EASTING 2,311,604			24 HR. 4.7		
DRILL RIG/HAMMER EFF./DATE SME3193 CME-550X 80% 06/07/2011						DRILL METHOD Mud Rotary			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 01/10/12			COMP. DATE 01/11/12			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		MOI		
-70						Match Line								
-73.4	78.5		8	12	15	27							-71.9	77.0
-75						35							COASTAL PLAIN GRAY AND GREEN SILT, WET (PEEDEE FORMATION)	
-78.4	83.5		9	17	18	35								
-80						35								
-83.4	88.5		11	15	20	47								
-85						31								
-88.4	93.5		9	17	30	32								
-90														
-93.4	98.5		9	17	14									
-95														
-98.4	103.5		10	16	16								-99.9	105.0
Boring Terminated at Elevation -99.9 ft in Hard Silt														

NCDOT BORE DOUBLE R-3601 GEO BRDG 108.GPJ NC_DOT.GDT 3/14/12

CORE PHOTOGRAPH B3-B

Box 1 of 1 (16.4' to 21.7', 21.7' to 26.9', and 26.9' to 32.2')

