



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

January 21, 2025

Addendum No. 1

Contract No.: DA00641

WBS Element: Various

(IDIQ) Traffic Signal Construction and Maintenance, Upon Request in Division One Counties

To Whom It May Concern:


Reference is made to the proposal and plans previously furnished for this project.

The following revisions have been made to the proposal:

Page No. 32 & 33 Roadway Special Provisions for "Sign for Signals", "Controller with Cabinet", "Cabinet Base Extender and Adapter" and "Beacon Controller Assemblies" have been revised to change the pay item numbers referenced in the special provision. Please replace the original Pages No. 32 & 33 Roadway Special Provisions for "Sign for Signals", "Controller with Cabinet", "Cabinet Base Extender and Adapter" and "Beacon Controller Assemblies" with the attached revised Pages No. 32 & 33 Roadway Special Provisions for "Sign for Signals", "Controller with Cabinet", "Cabinet Base Extender and Adapter" and "Beacon Controller Assemblies".

https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=1&let_status=Advertised

Sincerely,

DocuSigned by:

37ED002D8DDF4B4...

Mark S. Winslow
Division Contract Engineer

Cc: C. W. Bridgers, Jr., PE
R. K. Sawyer, PE
R. W. Midgett, PE
M. B. Gill, PE
B. N. Braswell, PE
D. B. Otts, PE

J. G. Davidson
M. R. Phillips

ROADWAY SPECIAL PROVISIONS

TRAFFIC CONTROL AND WORK ZONE SAFETY:

The Contractor shall maintain traffic during construction and provide, install, and maintain all traffic control devices in accordance with these project guidelines, Project Special Provisions, North Carolina Department of Transportation Standard Specifications, 2024 Roadway Standard Drawings and the current edition of the Manual of Uniform Traffic Control Devices (MUTCD).

The Contractor shall utilize complete and proper traffic control and traffic control devices during all operations. All traffic control and traffic control devices required for any operation shall be functional and in place prior to the commencement of that operation. Signs for temporary operations shall be removed during periods of inactivity. The contractor is required to leave the project in a manner that will be safe to the traveling public and which will not impede motorists.

The Contractor shall install necessary shoulder closures as shown in Standard Drawing No. 1101.04 or as directed by the Engineer.

Traffic movements through lane closures on roads with two way traffic shall be controlled by flaggers stationed at each end of the work zone. In situations where sight distance is limited, the Contractor shall provide additional means of controlling traffic, including, but not limited to, two-way radios, pilot vehicles, or additional flaggers. Flaggers shall be competent personnel, adequately trained in flagging procedures, and furnished with proper safety devices and equipment, including, but not limited to, safety vests and stop/slow paddles.

The Contractor will only be required to provide traffic control on two lane roadways.

**All Traffic Control is considered incidental to various other items in the contract.
There will be no direct payment for any Traffic Control items.**

SIGN FOR SIGNALS:

For Pay Item ~~#34~~ ~~#40~~, the Standard Specifications, Section 1745-1 "Description" is amended to say "Division 1 Traffic Services will supply signs for signals. The contractor will be responsible for installing NCDOT supplied signs, furnishing cable hangers, rigid sign mounting brackets, U-channel posts, and all necessary hardware."

CONTROLLER WITH CABINET:

For Pay Item ~~#39~~, ~~#40~~ ~~#45~~, ~~#46~~, the Standard Specifications, Section 1751-1 "Description" is amended to say "Division 1 Traffic Services will supply all flasher cabinets, 2070 cabinets, 2070 controllers, detector cards, 2010 conflict monitors and AC/DC isolator cards. The contractor will be responsible for grounding systems, mounting hardware for all types of cabinets and all necessary hardware."

CABINET BASE EXTENDER AND ADAPTER:

For Pay Item ~~#41~~, ~~#42~~ ~~#47~~, ~~#48~~, the Standard Specifications, Section 1753-1 "Description" is amended to say "Division 1 Traffic Services will supply base adapters and extenders with all necessary hardware for 170 cabinets. The contractor will be responsible for the installation."

BEACON CONTROLLER ASSEMBLIES:

For Pay Item ~~#43, #44, #45~~ #49, #50, #51, the Standard Specifications, Section 1755-1 “Description” is amended to say “Division 1 Traffic Services will supply cabinets, surge protection, and solid-state flashers. The contractor will be responsible for furnishing pole mounted hardware, grounding system, all necessary hardware, and installation of the Beacon Controller Assemblies.