DocuSign Envelope ID: A35E8836-B8AB-4330-8668-49321DC7CCA7

T.I.P.: B-2500C

CONTRACT: DA00522

PROJECT REFERENCE NO.	SHEET NO.
B-2500C	SIGN-1

DocuSign Envelope ID: 408381E4-8E7F-4A0A-A7A1-A4A4A4A4A4A4

NORTH CAROLINA PROFESSIONAL SEAL 048322 ENGINEER CAROLINE E. OWINGS

10/19/2021

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Michael Baker INTERNATIONAL

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
DARE COUNTY

DIVISION 1

LOCATION: IMPROVEMENTS TO NC 12 AT INTERSECTION WITH COQUINA BEACH RD. AND BODIE ISLAND LIGHTHOUSE RD.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.20	WOOD SIGN POST
904.10	ORIENTATION OF GROUND MOUNTED SIGNS

GENERAL NOTES

. SIGNS FURNISHED BY CONTRACTOR.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.

. ALL EXISTING SIGNS ON WOOD POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4082000000	903	SUPPORTS, WOOD	64	LF
4102000000	904	SIGN ERECTION, TYPE E	4	EA
4116100000	904	SIGN ERECTION, RELOCATE, TYPE D	2	EA
4141000000	907	DISPOSAL OF SUPPORT, WOOD	4	EA
4158000000	907	DISPOSAL OF SIGN SYSTEM, WOOD	4	EA

SIGN NUMBERING

NEW SIGNS

TYPE E SIGNS.....400 SERIES

EXISTING SIGNS

GROUND MOUNTED SIGNS RELOCATED TO NEW SUPPORTS.....900 SERIES

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	TYPE 'E' SIGNS & RELOCATED SIGNS
SIGN-3	EXISTING & PROPOSED SIGNING

PROJECT CONTACTS:

CHRISTOPHER H. LEE, PE — PROJECT ENGINEER

ROHAM R. LAHIJI — DIVISION 1 PROJECT MANAGER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN PREPARED BY: MICHAEL BAKER INTERNATIONAL

GEORGE M. KARAGEORGE, PE — TRAFFIC ENGINEER-NC OPERATIONS

CAROLINE E. OWINGS, PE — TRAFFIC ENGINEER

Michael Baker INTERNATIONAL
8000 Regency Parkway, Suite 600,
Cary, NC 27518
Phone: (919) 463-5488
MBAKERINTL.COM
PROFESSIONAL CORPORATION
LICENSE NO. F-1084

10/18/2021
pw://mb-us-pw.bentley.com:mb-us-pw-07/Documents/Cary_NC/01_Projects/NCDOT/B-2500 32635.L4 184006/Traffic/Signing/DESIGN & PLAN SHEETS/PLAN SHEETS/B-2500 SIGN_psh_01.dgn
User:Caroline.Owings