PROJECT REFERENCE NO.	SHEET NO.
B-2500	BP-1

BONNER PIER PARKING LOT

PAVEMENT SCHEDULE (BONNER PIER PARKING LOT)	
C4	PROP. APPROX. 1" ASPHALT CONCRETE SURFACE COURSE, TYPE S4.75A, AT AN AVERAGE RATE OF 100 LBS. PER SQ. YD.

NOTE: PAVEMENT EDGE SLOPE ARE 1:1 UNLESS SHOWN OTHERWISE.

GENERAL NOTES

THE CONTRACTOR SHALL PROVIDE THE ENGINEER A MINIMUM TWO WEEKS NOTICE PRIOR TO RESURFACING PARKING LOT.

RESURFACE EXISTING PAVED LIMITS OF PARKING LOT.
APPROXIMATE AREA = 5,620 SY

COORDINATE LAYOUT OF PAVEMENT MARKINGS WITH THE ENGINEER.

APPROXIMATE PAVEMENT MARKING QUANTITIES:
- 4", 90 MIL WHITE THERMOPLASTIC - 2,900 LF
- 4", 90 MIL YELLOW THERMOPLASTIC - 360 LF
- THERMOPLASTIC SYMBOLS, 90 MIL, STRAIGHT ARROW - 6 EA
- THERMOPLASTIC SYMBOLS, 90 MIL, HANDICAP PARKING - 3 EA

8/17/99
J:\Parking Lot\Bonner Pier Parking Lot_psh.dgn
15-OCT-2021 16:07
J:\STIP (Division Managed)\B-2500C (Coquina Beach_Bodie Island Light Turn Lanes)\Bonner Pier Parking Lot.dgn
$$$$USERNAME$$$$