PROJ. REFERENCE NO.	SHEET NO.
B-2500C	X1-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

APPROXIMATE QUANTITIES ONLY. CLEARING AND GRUBBING, UNCLASSIFIED EXCAVATION, SHOULDER BORROW, & FINE GRADING WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+30.00	10	0
12+50.00	51	1
13+00.00	73	2
13+50.00	60	9
14+00.00	49	21
14+50.00	45	35
15+00.00	45	50
15+50.00	54	57
16+00.00	66	57
16+50.00	88	48
17+00.00	113	36
17+50.00	115	37
18+00.00	99	45
18+50.00	92	51
19+00.00	113	48
19+50.00	132	34
20+00.00	125	29
20+50.00	96	33
21+00.00	39	27
21+50.00	0	22
22+00.00	0	24
22+50.00	39	35
23+00.00	67	54
23+50.00	80	66
24+00.00	82	65
24+50.00	69	51
25+00.00	75	37
25+50.00	60	38
26+00.00	38	53
26+50.00	26	73
27+00.00	26	91
27+50.00	21	89
28+00.00	13	79
28+50.00	38	44
29+00.00	37	32
29+50.00	9	52
30+00.00	8	41
30+50.00	10	23
31+00.00	12	11
31+50.00	4	3
31+70.00	0	0

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00	0	0
10+50.00	36	7
11+00.00	23	3
11+50.00	14	3
12+00.00	11	2
12+38.00	0	0