



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

March 18, 2024

Addendum No. 1

Contract No.: DA00597

WBS Element: BP1.R009.3

Replacement of Bridge #18 on SR 1510 (Jenkins Mill Rd) over Paddy's Delight Creek in Northampton County

To Whom It May Concern:

Reference is made to the proposal previously furnished for this project.

The following revisions have been made to the proposal:

Pages No. 114 - 119 "Bid Form" have been revised to include a line item for "*Construction Surveying*". Please replace the original pages No. 114 - 119 "Bid Form" with the attached revised pages No. 114 - 119 "Bid Form".

Sincerely,

DocuSigned by:
Mark S. Winslow
37ED002D8DDF4B4...

M. S. Winslow
Division Contract Engineer

Cc: C. W. Bridgers, Jr., PE
R. K. Sawyer, PE
R. W. Midgett, PE
M. B Gill, PE
B. N. Braswell, PE
D. B. Otts, PE
M. R. Hill, PE
J. S. Morris

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0003	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	100 SY		
0007	0222000000-E	SP	GEOTEXTILE FOR ROCK EMBANKMENTS	230 SY		
0008	0248000000-N	SP	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION (14+15 -L-)	Lump Sum	L.S.	
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	15 TON		
0010	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	50 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	56 LF		
0014	0995000000-E	340	PIPE REMOVAL	30 LF		
0015	1077000000-E	SP	#57 STONE	120 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	250 SY		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	410 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	270 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0022	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0023	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	68 LF		
0030	3030000000-E	862	STEEL BEAM GUARDRAIL	100 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	4 EA		
0034	3635000000-E	876	RIP RAP, CLASS II	750 TON		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3642000000-E	876	RIP RAP, CLASS A	120 TON		
0036	3649000000-E	876	RIP RAP, CLASS B	135 TON		
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	870 SY		
0038	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 EA		
0039	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0040	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	161 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0042	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0043	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,736 LF		
0045	5325600000-E	1510	6" WATER LINE	275 LF		
0046	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	490 LB		
0047	5540000000-E	1515	6" VALVE	2 EA		
0048	5800000000-E	1530	ABANDON 6" UTILITY PIPE	585 LF		
0049	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (8" WATER LINE)	310 LF		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	670 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0054	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0058	6029000000-E	SP	SAFETY FENCE	320 LF		
0059	6030000000-E	1630	SILT EXCAVATION	80 CY		
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,700 SY		
0061	6037000000-E	1629	COIR FIBER MAT	100 SY		
0062	6042000000-E	1632	1/4" HARDWARE CLOTH	55 LF		
0063	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	695 SY		
0064	6071002000-E	1642	FLOCCULANT	25 LB		
0065	6071012000-E	1642	COIR FIBER WATTLE	200 LF		
0066	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0067	6087000000-E	1660	MOWING	3 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0072	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0073	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	4 EA		
0074	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0089	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
STRUCTURE ITEMS						
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+14.50 -L-)	Lump Sum	L.S.	
0076	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+14.50 -L-)	Lump Sum	L.S.	
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+14.50 -L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,898 LB		
0080	8328400000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** GALVANIZED STEEL PILES (HP12X53)	10 EA		
0081	8365000000-E	450	HP 12 X 53 GALVANIZED STEEL PILES	675 LF		
0082	8393000000-N	450	PILE REDRIVES	5 EA		
0083	8394000000-N	450	DYNAMIC PILE TESTING	1 EA		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140 LF		
0085	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	190 TON		
0086	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	210 SY		
0087	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0088	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	700 LF		

1332/Mar18/Q21022.5/D386024514000/E89

Total Amount Of Bid For Entire Project :