



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

March 24, 2017

**Addendum No. 1**

Contract No.: DA00352

WBS Element: 51214.01T

*Dune Reconstruction and Sand Fence Installation in Dare County*

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.

The following revisions have been made to the proposal:

Page. No. 27, "**Borrow Excavation**" has been revised to include the sentence, "**There will be no deduction for shrinkage on this contract.**" Please void existing Page No. 27 and replace with revised Page No. 27.

If you choose the "Electronic Bid Preparation with Manual Delivery Method" or "Traditional Paper Bid Method," please acknowledge receipt of Addendum #1 in the space provided on the Addendum Acknowledgement Form.

If you choose the "Electronic Bid Preparation with Manual Delivery Method," place DA00352.001 in the same folder with DA00352.EBS, so that Expedite Bid will properly apply the addendum.

Sincerely,

DocuSigned by:

A handwritten signature in black ink that reads "W. B. Hobbs".

99A5A272ED6A447...

W. B. Hobbs, PE  
Division Project Manager

WBH/ces  
Attachment

Cc: C. W. Bridgers Jr., PE  
C. S. Mebane, PE  
R. W. Midgett, PE

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION ONE  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

Telephone: (252) 482-1850  
Fax: (252) 482-8722  
Customer Service: 1-877-368-4968

Location:  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

Website: [www.ncdot.gov](http://www.ncdot.gov)

## ROADWAY SPECIAL PROVISIONS

### **NOTE TO CONTRACTOR:**

This Contract is to place beach quality sand along NC 12 in Kitty Hawk. The sand will be placed upon existing sandbags. The placement should be done so to keep from damaging the existing sand bags and shall be placed within the area staked out by NCDOT. The sand must come from an approved source and by of like kind related to size and color of the existing beach sand. The approval must be given by a member of the Division of Coastal Management. Should the sand source have noticeable changes in color and size during the project a different source or location of the pit may be required before resuming the hauling of sand.

### **LUMP SUM GRADING:**

(8-17-10)

226

SP2 R16

Lump sum grading shall be performed in accordance with Section 226 Comprehensive Grading of the *2012 Standard Specifications* except as follows:

### **SHOULDER AND FILL SLOPE MATERIAL:**

(5-21-02)

235, 560

SP2 R45 A

#### **Description**

Perform the required shoulder and slope construction for this project in accordance with the applicable requirements of Section 560 and Section 235 of the *2012 Standard Specifications*.

#### **Measurement and Payment**

Where the material has been obtained from an authorized stockpile or from a borrow source and *Borrow Excavation* is not included in the contract, no direct payment will be made for this work, as the cost of this work will be part of the work being paid at the contract lump sum price for *Grading*. If *Borrow Excavation* is included in this contract and the material has been obtained from an authorized stockpile or from a borrow source, measurement and payment will be as provided in Section 230 of the *2012 Standard Specifications* for *Borrow Excavation*.

### **BORROW EXCAVATION (Truck Measurement):**

(7-1-95)

230

SP2 R57

The borrow material used on this project will be measured for payment by truck measurement as provided in Article 230-5 of the *2012 Standard Specifications*. **There will be no deduction for shrinkage on this contract.**

### **EROSION AND SEDIMENT CONTROL/STORMWATER CERTIFICATION:**

(1-16-07) (Rev 11-22-16)

105-16, 225-2, 16

SP1 G180

#### **General**

Schedule and conduct construction activities in a manner that will minimize soil erosion and the resulting sedimentation and turbidity of surface waters. Comply with the requirements herein regardless of whether or not a National Pollution discharge Elimination System (NPDES) permit for the work is required.