



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

April 28, 2023

Addendum No. 3

Contract No.: DA00569

WBS Element: 16.33001

Work Barge Skyco Drydock, in Craven County

To Whom It May Concern:


Reference is made to the proposal and plans previously furnished for this project.

The following revisions have been made to the proposal and plans:

Page 72, "Install Concrete Work Pad – 10.4 Requirements" has been revised to increase the number of beams detailed in the special provision, from "One" to "Three". Please replace the original Page 72, "Install Concrete Work Pad – 10.4 Requirements" with the attached revised Page 72, "Install Concrete Work Pad – 10.4 Requirements".

We apologize for the inconvenience.

Sincerely,

DocuSigned by:

CDAEAC77A6394FB...

C. E. Slachta
Division Contract Engineer

Cc: C. W. Bridgers, Jr., PE
R. W. Midgett, PE
R. K. Sawyer, PE
M. B. Gill, PE
W. B. Hobbs, PE
D. B. Otts, PE
J. J. Remme

10.4 Requirements

The Contractor shall fabricate and install steel containment in accordance with DWG NC-140-03B. Containment perimeter will be formed with 6"x4"x1/2" angle double continuous welded to the deck. **Three** W6x12# I beams will be double continuous welded to the deck to act as intermediate structure.

Care must be taken when scheduling this item to ensure that the deck blasting, and repairs, and painting are all complete before installing containment structure. Containment must also be prepped, primed and painted in accordance to Blasting and Painting –All Decks before pouring the concrete base. Any disturbed paint on the underside of the deck to be cleaned, prepped and panted in accordance to Prep and Paint Voids, Ballast, And Machinery Room Bilges.

Concrete base to be made from 6" thick 3000# Fiberglass reinforced concrete mix. Concrete to be leveled and sealed after pouring. Sealant to be approved by NCDOT representative and on the NCDOT approved product list for Concrete Waterproofing and Sealing before application. Concrete shall be placed in accordance with NCDOT 2018 Standard Specification for Roads and Structures – Section 700.

10.5 Tests, Trials and Documentation

Dye Penetration Tests on containment welds before pouring concrete. Two concrete cylinder samples to be prepared and cured in accordance with AASHTO T-23 and Section 700 of the NCDOT 2018 Standard Specifications for Roads and Structures for each load of concrete. All cylinders to be tested by NCDOT. Any failed tests will be addressed in accordance with NCDOT 2018 Standard Specifications for Roads and Structures – Section 700.

10.6 Payment:

The lump sum contract bid price for *Generic Ferry Item (Sewage System – Install Concrete Work Pad)* shall be the total compensation for installing steel containment pouring and placing concrete, all labor, equipment, tools and new materials to accomplish the work detailed in these Special Provisions, including testing and trials. No further compensation will be made.