



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

May 9, 2019

Addendum No. 1

Contract No.: DA00463

WBS Element: 50213.3.2 & 47664.3.1

TIP No.: R-5717A

*Grading, Drainage and Paving Along SR 1224 Old Swamp Rd, located in
Camden County*

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.

The following revision has been made to the proposal:


Page 33, "Clearing and Grubbing – Method II" has been revised to include a note concerning an existing tree stump on Parcel 5S and the "Automated Fine Grading" special provision has been removed from the proposal. Please replace the original Page 33, "Clearing and Grubbing – Method II" with the attached revised Page 33, "Clearing and Grubbing – Method II".

Pages 48-49, "Concrete Washout Structure" has been removed from the proposal. Please replace the original Pages 48-49, with the attached revised Pages 48-49.

Pages 76-78, "Bid Form" has been revised to include a line item for "Asphalt Plant Mix Pavement Repair" and to remove the line item for "Concrete Washout Structure". Please replace the original Pages 76-78, "Bid Form" with the attached revised Pages 76-78, "Bid Form".

The amended EBS File (DA00463.001) has been uploaded to Bid Express. We apologize for any inconvenience.

Sincerely,

DocuSigned by:

CDAEAC77A6394FB...

C. E. Slachta
Division Proposals Engineer

Cc: J. D. Jennings, PE
C. W. Bridgers Jr., PE
G. A. Byrum, PE
R. W. Midgett, PE
D. B. Otts, PE
W. G. Cooke

REVISED 05/09/19

ROADWAY SPECIAL PROVISIONS**CLEARING AND GRUBBING - METHOD II:**

(9-17-02) (Rev.8-18-15)

200

SP2 R02A

Perform clearing on this project to the limits established by Method "II" shown on Standard Drawing No. 200.02 of the *2018 Roadway Standard Drawings*. Conventional clearing methods may be used except where permit drawings or conditions have been included in the proposal which require certain areas to be cleared by hand methods.

Note:

On Parcel 5S, remove large tree and stump near STA 195+70 RT. Stump near STA 196+10 RT may remain.

INCIDENTAL STONE BASE:

(7-1-95) (Rev.8-21-12)

545

SP5 R28R

Description

Place incidental stone base on driveways, mailboxes, etc. immediately after paving and do not have the paving operations exceed stone base placement by more than one week without written permission of the Engineer.

Materials and Construction

Provide and place incidental stone base in accordance with Section 545 of the *2018 Standard Specifications*.

Measurement and Payment

Incidental Stone Base will be measured and paid in accordance with Article 545-6 of the *2018 Standard Specifications*.

REVISED 05/09/19

Construction Methods

Provide an approved subcontractor who performs an erosion control action as described in the NPDES Inspection Form SPPP30. Each erosion control action may include one or more of the above work items.

Measurement and Payment

Response for Erosion Control will be measured and paid for by counting the actual number of times the subcontractor moves onto the project, including borrow and waste sites, and satisfactorily completes an erosion control action described in Form 1675. The provisions of Article 104-5 of the *Standard Specifications* will not apply to this item of work.

Payment will be made under:

Pay Item

Response for Erosion Control

Pay Unit

Each

REVISED 05/09/19

[PAGE INTENTIONALLY LEFT BLANK]

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	30 TON		
0005	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	90 SY		
0006	0344000000-E	310	18" SIDE DRAIN PIPE	48 LF		
0007	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	144 LF		
0008	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	68 LF		
0009	0995000000-E	340	PIPE REMOVAL	230 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0011	1330000000-E	607	INCIDENTAL MILLING	210 SY		
0012	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	730 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,200 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	105 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	60 TON		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4 EA		
0017	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0018	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	194 SY		
0019	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	72 SF		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0021	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8,250 LF		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,250 LF		
0023	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM THERMO PVT MKG LINES (24", 90 MILS)	12 LF		
0024	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	50 EA		
0025	5325600000-E	1510	6" WATER LINE	2,395 LF		
0026	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	1,295 LB		
0027	5538000000-E	1515	4" VALVE	1 EA		
0028	5540000000-E	1515	6" VALVE	6 EA		
0029	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0030	5666000000-N	1515	FIRE HYDRANT	1 EA		
0031	5673000000-E	1515	FIRE HYDRANT LEG	12 LF		
0032	5686500000-E	1515	WATER SERVICE LINE	5 LF		
0033	5798000000-E	1530	ABANDON *** UTILITY PIPE 4"	2,330 LF		
0034	5800000000-E	1530	ABANDON 6" UTILITY PIPE	65 LF		
0035	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	310 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		

County : Camden

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6030000000-E	1630	SILT EXCAVATION	150 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,125 SY		
0046	6071012000-E	SP	COIR FIBER WATTLE	30 LF		
0047	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0048	6087000000-E	1660	MOWING	3 ACR		
0049	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0050	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0053	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0054	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		