



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

JOSH STEIN  
GOVERNOR

DANIEL H. JOHNSON  
SECRETARY

April 24, 2026

**NOTICE TO PROSPECTIVE BIDDERS**

The North Carolina Department of Transportation is requesting bids for the following project in Division One:

**DA00680 – Replacement of Bridge #17 on SR 1508 (Doolittle Mill Rd) over Paddys Delight Creek in Northampton County**

**WBS Element: BP1.R018.3**

**The Date of Availability for this Contract is June 22, 2026**

**The Completion Date for this Contract is March 17, 2027**

**There is NO MBE/WBE Goal for this project.**

Any firm that wishes to bid as a prime contractor shall be prequalified as a Bidder or PO Prime Contractor prior to submitting a bid. Information regarding prequalification can be found at:

<https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>

If you are unsure as to whether your firm is currently prequalified by the Department by the Contractual Services Unit, a search of the Directory of Transportation Firms can be performed at the website below:

<https://apps.dot.state.nc.us/vendor/directory/>

**Bid Opening will be at 2:00 pm on Wednesday May 20, 2026**

**Prospective Bidders shall utilize the Division One Conference Call Phone Number (866) 590-5055 access code (2659015) to join the May 20, 2026 Virtual Bid Opening. Prospective Bidders are encouraged to join the Bid Opening Conference Call approximately five minutes prior to the Bid Opening, as the bids will be read promptly at 2:00 pm. If you are unable to attend the Bid Opening Conference Call, bid results will also be posted on the Division One Webpage following the 2:00 pm Bid Opening. Feel free to contact me if you have any questions or need any additional information. Feel free to contact me if you have any questions or need any additional information.**

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION ONE  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

*Telephone:* (252) 482-1850  
*Fax:* (252) 482-8722  
*Customer Service:* 1-877-368-4968

*Location:*  
113 AIRPORT DRIVE, SUITE 100  
EDENTON, NC 27932

*Website:* www.ncdot.gov

**CONTACT INFORMATION**

Contract proposal packages are available on the Division 1 website:


[https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=1&let\\_status=Advertised](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=1&let_status=Advertised)

DBE\_NC.bin file can be found on the Connect.ncdot.gov website:

[https://connect.ncdot.gov/letting/DBE%20Files/DBE\\_NC.bin](https://connect.ncdot.gov/letting/DBE%20Files/DBE_NC.bin)

If you have any questions or need additional information concerning this project, please contact Mark Winslow at (252) 482-1866.

Sincerely,

DocuSigned by:  
  
37ED002D8DDF4B4...

Mark S. Winslow  
Division Contract Engineer

Cc: R. K. Sawyer, PE  
M. B. Gill, PE  
B. N. Braswell, PE  
D. B. Otts, PE  
C. B. Johnson, PE  
E. W. Rose  
J. Morris

STATE FUNDED PROPOSAL, CONTRACTOR LICENSE REQUIRED TO BID

L260520A 002

CONTRACT ID : DA00680 BP1.R018.3

DIV OFFICE EDENTON

LENGTH = 0.158 MI

COUNTY : NORTHAMPTON

GRADING, DRAINAGE, PAVING, AND STRUCTURES

DBE GOAL COMPLETION DATE : SEE SPECIAL PROVISIONS

BRIDGE NO. 650017 ON SR-1508 (DOOLITTLE MILL RD) OVER PADDYS DELIGHT CREEK

ROADWAY ITEMS					
			3,340	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
Lump Sum	LS	MOBILIZATION	100	LF	10" WATER LINE
Lump Sum	LS	CONSTRUCTION SURVEYING	480	LB	DUCTILE IRON WATER PIPE FITTINGS
300	CY	UNDERCUT EXCAVATION	2	EA	10" VALVE
Lump Sum	LS	GRADING	100	LF	ABANDON 10" UTILITY PIPE
1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	845	LF	TEMPORARY SILT FENCE
5	CY	DRAINAGE DITCH EXCAVATION	75	TON	STONE FOR EROSION CONTROL, CLASS A
300	CY	SELECT GRANULAR MATERIAL	65	TON	STONE FOR EROSION CONTROL, CLASS B
300	SY	GEOTEXTILE FOR SOIL STABILIZATION	30	TON	SEDIMENT CONTROL STONE
570	SY	ROCK PLATING	0.5	ACR	TEMPORARY MULCHING
Lump Sum	LS	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION 15+22.50 -L-	100	LB	SEED FOR TEMPORARY SEEDING
20	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
60	SY	FOUNDATION CONDITIONING GEOTEXTILE	200	LF	TEMPORARY SLOPE DRAINS
52	LF	15" DRAINAGE PIPE	260	LF	SAFETY FENCE
52	LF	18" DRAINAGE PIPE	100	CY	SILT EXCAVATION
48	LF	24" DRAINAGE PIPE	2,030	SY	MATTING FOR EROSION CONTROL
2	EA	*** DRAINAGE PIPE ELBOWS (15")	100	SY	COIR FIBER MAT
24	LF	15" RC PIPE CULVERTS, CLASS IV	55	LF	1/4" HARDWARE CLOTH
160	LF	PIPE REMOVAL	340	SY	FLOATING TURBIDITY CURTAIN
20	TON	INCIDENTAL STONE BASE	20	LB	FLOCCULANT
290	SY	INCIDENTAL MILLING	130	LF	COIR FIBER WATTLE
650	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	0.5	ACR	SEEDING & MULCHING
310	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	0.5	ACR	MOWING
50	TON	ASPHALT BINDER FOR PLANT MIX	50	LB	SEED FOR REPAIR SEEDING
45	CY	SUBDRAIN EXCAVATION	0.25	TON	FERTILIZER FOR REPAIR SEEDING
200	SY	GEOTEXTILE FOR SUBSURFACE DRAINS	50	LB	SEED FOR SUPPLEMENTAL SEEDING
33.6	CY	SUBDRAIN COARSE AGGREGATE	0.25	TON	FERTILIZER TOPDRESSING
200	LF	6" PERFORATED SUBDRAIN PIPE	10	MHR	SPECIALIZED HAND MOWING
1	EA	SUBDRAIN PIPE OUTLET	13	EA	RESPONSE FOR EROSION CONTROL
6	LF	6" OUTLET PIPE	1	EA	CONCRETE WASHOUT STRUCTURE
1	CY	PIPE PLUGS	3	EA	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT
2	EA	MASONRY DRAINAGE STRUCTURES			<b>STRUCTURE ITEMS</b>
2	EA	FRAME WITH GRATE, STD 840.29	Lump Sum	LS	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+22.50 -L-)
26	LF	SHOULDER BERM GUTTER	Lump Sum	LS	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+22.50 -L-)
200	LF	STEEL BEAM GUARDRAIL	26	CY	CLASS A CONCRETE (BRIDGE)
4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	Lump Sum	LS	BRIDGE APPROACH SLABS, STATION ***** (15+22.50 -L-)
4	EA	GUARDRAIL END UNITS, TYPE TL-3	3,930	LB	REINFORCING STEEL (BRIDGE)
5	EA	ADDITIONAL GUIDERAIL POSTS	10	EA	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (10)
8	TON	RIP RAP, CLASS I	850	LF	HP 12 X 53 STEEL PILES
2	TON	RIP RAP, CLASS B	6	EA	PILE REDRIVES
207	SY	GEOTEXTILE FOR DRAINAGE	1	EA	DYNAMIC PILE TESTING
40	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	110.25	LF	VERTICAL CONCRETE BARRIER RAIL
3	EA	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (E)	47	SY	4" SLOPE PROTECTION
1	EA	DISPOSAL OF SUPPORT, WOOD	Lump Sum	LS	ELASTOMERIC BEARINGS
2	EA	DISPOSAL OF SIGN SYSTEM, WOOD	550	LF	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS
2	EA	DISPOSAL OF SUPPORT, U-CHANNEL			
309	SF	WORK ZONE SIGNS (STATIONARY)			
94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)			
64	LF	BARRICADES (TYPE III)			

## Notice Regarding Upcoming Buy America Changes

On January 14, 2025, the Federal Highway Administration (FHWA) terminated its General Waiver for Manufactured Products and established specific Buy America requirements for their use on Federal-aid highway projects.

This means that as of the following dates, materials defined as manufactured products permanently incorporated into Federal-aid highway projects will have to be manufactured in the United States.

### Key Implementation Dates

- Phase 1: contracts obligated on or after **October 1, 2025**
    - Final assembly of all manufactured products permanently incorporated into Federal-aid highway projects must occur in the United States.
  - Phase 2: contracts obligated on or after **October 1, 2026**
    - Final assembly of all manufactured products permanently incorporated into Federal-aid highway projects must occur in the United States.
- AND
- The cost of U.S.-produced components in manufactured products must be greater than 55% of the total cost of all components.

### Definition of Manufactured Products

Manufactured Products are defined as articles, materials, or supplies that:

- Have been processed into a specific form and shape, or
- Have been combined with other articles or supplies to create a product with different properties than the individual articles, materials, or supplies.

This places greater emphasis on using domestically produced materials on these projects and is consistent with the Build America, Buy America Act (BABA) under the Bipartisan Infrastructure Law (BIL).