DocuSign Envelope ID: C3C7D983-3B91-476F-AAFC-595E5DD30DEC

NOTES

SHEET PILING SHALL BE DRIVEN AT AN EVEN OFFSET OF 17'-5"(RADIAL) FROM -L- TO THE ℄ OF THE SHEET PILE OR AS DIRECTED BY THE ENGINEER.

INSTALL SHEET PILING SHOWN ON THIS SHEET STARTING AT THE END BENT AND WORK DOWNSTATION TOWARD STA. 18+74.37 -L- OR AS DIRECTED BY THE ENGINEER.

✳ TOP OF COPING SHALL BE APPROXIMATELY 4" ABOVE PROPOSED SHOULDER OR AS DIRECTED BY THE ENGINEER.

GROOVED CONTRACTION JOINTS, ½" DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE COPING AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINTS SHALL BE LOCATED AT 10'-0" ± INTERVALS FOR THE FULL LENGTH OF COPING.



PLAN OF WING (W2)



SECTION B-B



W2 ELEVATION OF WING



PLAN OF WING DETAILS (W2)

PROJECT NO. 17BP.1.R.87

TYRRELL COUNTY

STATION: 20+28.50 -L-

SHEET 3 OF 4

ENGINEER OF RECORD
8/21/2019

NORTH CAROLINA PROFESSIONAL SEAL 14091 ENGINEER BUCK CHARLES HUNT

DocuSigned by: Buck Charles Hunt
2F15C8C8D...

WETHERILL ENGINEERING
1223 Jones Franklin Rd.
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
LICENSE NO. F-0377

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
END BENT No. 1

REVISIONS							
NO.	BY:	DATE:	NO.	BY:	DATE:		
1			3				
2			4				

SHEET NO. S-13
TOTAL SHEETS 22

DRAWN BY : B.C. HUNT DATE : 4-19
CHECKED BY : D. HODGE DATE : 4-19

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

P:\2018\18161.01_Tyrrell 17\Structures\DGN\17BP.1.R.87_SMU_EBT.dgn
8/20/2019 2:52:50 PM