PERMANENT EASEMENT CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
17BP.1.R.87	RW03E-1

Location and Surveys

ENTER CONSULTANT'S NAME
IN THIS BOX

PROJECT SURVEYOR

NORTH CAROLINA PROFESSIONAL SEAL L-4457 LAND SURVEYOR JIMMY E. LIVERMAN, JR.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

I, Jimmy e. Liverman Jr, a Professional Land Surveyor in the state of North Carolina hereby certify to the best of my knowledge and belief that the following work item(s) (Base map Compilation, Planimetrics, R/W Staking) performed under my responsible charge meet NCDOT Survey Standards as directed in the NCDOT Location & Surveys guidelines and procedures.

I further certify that the data compiled came from available surveys/mapping performed by others and provided to me by NCDOT and do not certify to the accuracy or quality of the individual data sources.

I further certify that the right of way and permanent easement points shown herein and outlined in the tables shown hereon (localized coordinates, station/offset) have been checked and are accurate representations of the right of way and permanent easement points depicted on the corresponding highway plans. I also certify that the right of way and permanent easement points shown herein have been field monumented under my supervision from existing survey control provided by others; that the depicted property data shown herein were surveyed by others; and these monuments denote the right of way and easement boundaries at the time of staking which may be subject to change due to right of way revisions (See deeds for final determination).

Witness my original signature, registration number and seal this 30th day of December, 2019.

DocuSigned by:
Jimmy Liverman, Jr.
C782A59719E7430...

---------- L-4457
Professional Land Surveyor PLS #

NORTH CAROLINA PROFESSIONAL SEAL L-4457 LAND SURVEYOR JIMMY E. LIVERMAN, JR.

ROW MARKER PERMANENT EASEMENT-E

ALIGN	STATION	OFFSET	NORTH	EAST
L	17+90.00	-43.00	792955.5291	2815371.6764
L	17+90.00	-30.00	792950.9677	2815383.8498
L	18+10.00	-43.00	792972.5023	2815377.5842
L	18+10.00	-30.00	792968.5195	2815389.9586
L	21+45.00	-30.00	793287.7393	2815392.9790
L	21+45.00	-45.00	793285.8573	2815378.1000
L	21+65.00	-30.00	793306.9309	2815390.3471
L	21+65.00	-45.00	793304.7378	2815375.5108

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

REVISIONS

6/2/99

30-DEC-2019 14:46
R:\Design_Area\control\Control Sheets\E-Sheets\b4648_ls_RW03E-1.dgn
$tbody - $AT $S-$HORS