PROJECT REFERENCE NO.	SHEET NO.
17BP.1.R.92	EC-06/CONST.04
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NAD 83/2011



CONTRACTOR SHALL INSTALL AN ONSITE CONCRETE WASHOUT STRUCTURE PER THE NCDOT DETAIL AND SPECIAL PROVISIONS. ACTUAL LOCATION OF THE STRUCTURE SHALL BE DETERMINED IN THE FIELD. CONCRETE WASHOUT STRUCTURE SHALL BE MAINTAINED BY THE CONTRACTOR. ALL CONCRETE TRUCKS SHALL USE THE CONCRETE WASHOUT STRUCTURE. NO WASHOUT OF CONCRETE TRUCKS SHALL BE ALLOWED EXCEPT IN THE CONCRETE WASHOUT STRUCTURE.

NOTE:
ADD TEMPORARY ROCK SILT CHECKS TYPE – A AT DRAINAGE OUTLETS.

NOTE:
PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.

NOTE:
MATTING WITH NYLON MESH CANNOT BE USED WITHIN 25 FT. OF THE TOP OF STREAM BANK.

FINAL EROSION CONTROL
FOR CONSTRUCTION SHEET 06

REVISIONS

8/17/99

08-AUG-2019 13:10
R:\Hydraulics\CADD\PSH\EC\17BP.1.R.92_rdy_PSH_06.dgn
$$$$USERNAME$$$$