DocuSign Envelope ID: FFE32C35-E751-410C-A70E-AB9D76EACB06

6/2/99

PROJECT REFERENCE NO.	SHEET NO.
17BP.1.R.92	2A-1
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 022610 ENGINEER BRUCE RAYNE JR.

DocuSigned by: Bruce Rayne Jr. 7/9/2021 B2BA45C2B6C4E8...

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 160 RALEIGH, NORTH CAROLINA 27609 (919) 876-6888 NCBEES #F-0326

PAVEMENT SCHEDULE

C1	PROP. APPROX. 3″ ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1″ DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 1″ OR GREATER THAN 1½″ IN DEPTH.
E1	PROP. APPROX. 5.5″ ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 627 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1″ DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 4″ OR GREATER THAN 5½″ IN DEPTH.
J1	PROP. 6″ AGGREGATE BASE COURSE
T	EARTH MATERIAL

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.



TYPICAL SECTION NO. 1
–L– STA 10+55.00 TO –L– STA 12+40.00
–L– STA 16+05.00 TO –L– STA 16+50.00

* 8′ SHOULDER WHERE GUARDRAIL REQUIRED



TYPICAL SECTION NO. 2
–L– STA 12+40.00 TO –L– STA 13+38.75 (BEGIN BRIDGE)
–L– STA 15+06.25 (END BRIDGE) TO –L– STA 16+05.00

* 8′ SHOULDER WHERE GUARDRAIL REQUIRED



TYPICAL SECTION NO. 3
–L– STA 13+38.75 TO –L– STA 15+06.25

13-JUN-2019 15:56
R:\Roadway\Proj\17BP.1.R.92_rdy_typ.dgn
$$$$USERNAME$$$$