

2023CPT.01.14.10941.1

Jun 21, 2023

DA00572

TIP NO

7.240 MILES

FED AID NO STATE FUNDED

MILLING, RESURFACING, RUMBLE STRIPS, & PAVE. MARKINGS

VARIOUS SECTIONS OF US 64

FSC II LLC DBA FRED SMITH  
COMPANY  
RALEIGH, NC

BARNHILL CONTRACTING CO  
ROCKY MOUNT, NC

**ROADWAY ITEMS**

Item ID	Code	Quantity	Description	Unit	Rate	Amount	Rate	Amount
0001	0000100000-N	800	MOBILIZATION	Lump Sum		119,500.00		125,400.00
0004	1297000000-E	607	MILL ASP PVMT ***** DTH (1-1/2")	SY	0.75	100,002.75	1.50	200,005.50
0005	1330000000-E	607	INCIDENTAL MILLING	SY	2.95	22,717.95	5.00	38,505.00
0006	1523000000-E	610	ASP CONC SURF CRS S9.5C	TON	58.00	751,854.00	61.00	790,743.00
0007	1575000000-E	620	ASP FOR PLANT MIX	TON	625.00	488,125.00	671.00	524,051.00
0008	1577000000-E	620	POLYM MOD ASP BNDR FOR PLT MIX	TON	925.00	212,750.00	792.00	182,160.00
0009	1662000000-E	650	OG ASP FRICT FC-1 MOD	TON	100.00	377,800.00	115.00	434,470.00
0010	1705000000-E	SP	PATCHING EXIST PAVEMENT (FULL DEPTH)	TON	300.00	22,200.00	310.00	22,940.00
0011	1840000000-E	665	MILLED RUMBLE STRIPS	LF	0.36	25,850.88	0.21	15,079.68
0012	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	SF	5.00	2,420.00	7.75	3,751.00
0013	4423000000-N	SP	WZ DIGITAL SPD LMT SIGNS	EA	2,750.00	13,750.00	1,000.00	5,000.00
0014	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		112,020.34		11,000.00
0015	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	LF	0.84	72,619.68	0.84	72,619.68
0016	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	LF	5.00	185.00	5.00	185.00
0017	4700000000-E	1205	12"WIDE THERMO 90 MILS	LF	5.00	5,000.00	5.00	5,000.00
0018	4709000000-E	1205	24"WIDE THERMO 90 MILS	LF	18.00	810.00	18.00	810.00
0019	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	EA	120.00	360.00	120.00	360.00
0020	4810000000-E	1205	PAINT PVMT MARKINGS 4"	LF	0.45	38,903.40	0.45	38,903.40
0021	4820000000-E	1205	PAINT PVMT MARKINGS 8"	LF	3.00	111.00	3.00	111.00
0022	4825000000-E	1205	PAINT PVMT MARKINGS 12"	LF	4.00	4,000.00	4.00	4,000.00
0023	4835000000-E	1205	PAINT PVT MKG LINES 24"	LF	10.00	450.00	10.00	450.00
0024	4845000000-N	1205	PAINT PVT MKG SYMBOL	EA	60.00	180.00	60.00	180.00
0025	4900000000-N	1251	PERM RAISED PVMT MARKERS	EA	25.00	350.00	20.00	280.00
0026	4905100000-N	SP	NON-CAST IRON SNOWPLB PVMT MRKER	EA	55.00	23,540.00	49.50	21,186.00
0027	1220000000-E	545	INCIDENTAL STONE BASE	TON	150.00	3,000.00	100.00	2,000.00

CONTRACT TOTAL	TOTAL	2,398,500.00	TOTAL	2,499,190.26
ROADWAY ITEMS	SUB-TOTAL	2,398,500.00	SUB-TOTAL	2,499,190.26

**BIDDERS IN ORDER**

**CONTRACT TOTAL**

FSC II LLC DBA FRED SMITH COMPANY	1	2,398,500.00
BARNHILL CONTRACTING CO	2	2,499,190.26