



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

June 13, 2019

Addendum No. 2

Contract No.: DA00465

WBS Element: 2019CPT.01.19.20462.1

Full Depth Reclamation On Various Secondary Routes In Hertford County

To Whom It May Concern:


Reference is made to the proposal and plans previously furnished for this project.

The following revision has been made to the proposal and plans:

Plan Sheet 3, "Summary of Quantities" has been revised to remove the requirement for "Final Surface Testing". Please replace the previous Plan Sheet 3, "Summary of Quantities" with the attached revised Plan Sheet 3, "Summary of Quantities".

The amended EBS File (DA00465.002x) has been uploaded. We apologize for any inconvenience.

Sincerely,

DocuSigned by:

CDAEAC77A6394FB...

C. E. Slachta
Division Proposals Engineer

Cc: J. D. Jennings, PE
C. W. Bridgers Jr., PE
G. A. Byrum, PE
R. W. Midgett, PE
M. R. Hill, PE

| | |
|-----------------------|-----------|
| PROJECT NO. | SHEET NO. |
| 2019CPT.01.19.20462.1 | 3 |

REVISED 6/13/2019

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | MOBILIZATION | BORROW EXCAVATION | SOIL CEMENT BASE | PORTLAND CEMENT FOR SOIL CEMENT BASE | INCIDENTAL STONE BASE | SHOULDER RECONSTRUCTION | INCIDENTAL MILLING | SURFACE COURSE, S9.5C | ASPHALT BINDER FOR PLANT MIX | TEMPORARY SILT FENCE | COIR FIBER MAT | COIR FIBER WATTLE | SEEDING & MULCHING | RESPONSE FOR EROSION CONTROL | WORK ZONE ADV/GEN WARNING SIGNING | TEMPORARY TRAFFIC CONTROL | GENERIC PAVEMENT MARKING ITEM (HOT SPRAYED THERMO PVMT MARKING LINES, 4" 50 MILS) | 4" WHITE PAINT | 4" YELLOW PAINT |
|---|----------|--------|--------------------------|---------------------|--------|-------|-----------|--------------------------------|---------------------------|--------------|-------|--------------|-------------------|------------------|--------------------------------------|-----------------------|-------------------------|--------------------|-----------------------|------------------------------|----------------------|----------------|-------------------|--------------------|------------------------------|-----------------------------------|---------------------------|---|----------------|-----------------|
| | | | | | | | | | | MI | FT | LS | CY | SY | TON | TONS | SMI | SY | TONS | TONS | LF | SY | LF | ACR | EA | SF | LS | LF | LF | |
| 2019CPT.01.19.20462.1 | Hertford | 1 | SR 1121 RAWLS RD | SR 1116 TO SR 1114 | 1 | 2 | 2WU | NO | NO | 1.28 | 22 | 1 | 211 | 18,022 | 540 | 26 | 2.56 | | 3,088 | 185 | 96 | | 96 | 1.3 | 3 | 60 | 1 | 44,442 | 27,546 | 16,896 |
| 2019CPT.01.19.20462.1 | Hertford | 2 | SR 1153 WILL SLADE RD | SR 1152 TO DEAD END | 1 | 2 | 2WU | NO | NO | 0.4 | 20 | * | 66 | 5,162 | 156 | 8 | 0.80 | | 878 | 53 | 30 | | 30 | 0.4 | 3 | 40 | * | 13,888 | 8,608 | 5,280 |
| 2019CPT.01.19.20462.1 | Hertford | 3 | SR 1430 ARCHER TOWN RD | SR 1432 TO SR 1431 | 1 | 2 | 2WU | NO | NO | 1.34 | 20 | * | 221 | 17,294 | 565 | 27 | 2.68 | | 2,942 | 177 | 101 | | 101 | 1.3 | 3 | 72.5 | * | 46,525 | 28,837 | 17,688 |
| 2019CPT.01.19.20462.1 | Hertford | 4 | SR 1419 NEWSOME GROVE RD | SR 1409 TO NC 561 | 1 | 2 | 2WU | NO | NO | 2.1 | 20 | * | 347 | 27,103 | 886 | 42 | 4.20 | | 4,610 | 277 | 158 | | 158 | 2.1 | 3 | 80 | * | 72,912 | 45,192 | 27,720 |
| 2019CPT.01.19.20462.1 | Hertford | 5 | SR 1425 VANN RD | SR 1403 TO DEAD END | 1 | 2 | 2WU | NO | NO | 2.31 | 20 | * | 381 | 29,813 | 1,074 | 46 | 4.62 | | 5,103 | 306 | 173 | | 173 | 2.3 | 5 | 40 | * | 80,203 | 49,711 | 30,492 |
| 2019CPT.01.19.20462.1 | Hertford | 6 | SR 1152 JIM HARDY RD | SR 1154 TO NC 561 | 1 | 2 | 2WU | NO | NO | 1.52 | 20 | * | 251 | 19,617 | 593 | 30 | 2.31 | | 3,337 | 200 | 114 | | 114 | 2.3 | 3 | 96 | * | 52,774 | 32,710 | 20,064 |
| 2019CPT.01.19.20461.1 | Hertford | 7 | SR 1121 RAWLS RD | SR 1116 TO SR 1118 | 2 | 2 | 2WU | NO | NO | 1 | 22 | * | 100 | | | 30 | 2.00 | 100 | 1,232 | 74 | 75 | 100 | 75 | 1.0 | 2 | 76 | * | 34,720 | 21,520 | 13,200 |
| 2019CPT.01.19.20461.1 | Hertford | 8 | SR 1430 ARCHER TOWN RD | SR 1431 TO DEAD END | 2 | 2 | 2WU | NO | NO | 0.39 | 20 | * | 12 | | | 3 | 0.24 | 250 | 425 | 26 | 29 | 39 | 29 | 0.1 | 1 | 36 | * | 13,541 | 8,393 | 5,148 |
| 2019CPT.01.19.20461.1 | Hertford | 9 | SR 1431 ARCHER RD | SR 1430 TO DEAD END | 2 | 2 | 2WU | NO | NO | 0.12 | 20 | * | 39 | | | 10 | 0.78 | 100 | 132 | 8 | 9 | 12 | 9 | 0.4 | 0 | 40 | * | 4,166 | 2,582 | 1,584 |
| TOTAL FOR PROJ NO. 2019CPT.01.19.20462.1, ETC. | | | | | | | | | | 10.46 | | 1 | 1,628 | 117,011 | 3,814 | 222 | 20.19 | 450 | 21,747 | 1,306 | 785 | 151 | 785 | 11.20 | 23 | 540.5 | 1 | 363,171 | 225,099 | 138,072 |