



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

July 9, 2013

Addendum No. 1

Contract No.: DA00159

TIP No.: N/A

WBS No.: 1C.008094

Flexible Pavement Reclamation and Paving on Bal Gra Road (SR 1501) In Bertie County

To Whom It May Concern:

Reference is made to the proposal previously furnished for this project.

The following revisions have been made to the proposal:

Plan Sheet No.2 has been revised to illustrate the requirements for widening. Please void the existing Plan Sheet No.2 in the proposal and staple revised Plan Sheet No.2 thereto and acknowledge addendum on the Bid Form.

Sincerely,

A handwritten signature in blue ink, appearing to read "W. B. Hobbs".

W. B. Hobbs, PE
Division Project Manager

WBH/ces
Attachment

cc: S. D. Baker, PE
S. L. Emory, PE

NOTES:

- 1. EDGES, PAVEMENT WIDENING, INTERSECTIONS, AND BRIDGE FLARES ARE INCLUDED IN THE TABLE OF QUANTITIES
- 2. PAVEMENT EDGE SLOPES SHOULD MEET SHOULDER WEDGE SPECIAL PROVISION
- 3. SHOULDERS ARE TO BE CONSTRUCTED BY OTHERS

PROJECT REFERENCE NO.	SHEET NO.
DA00159	2 OF 4

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.25" ASPHALT CONCRETE SURFACE COURSE TYPE SF9.5A, AT AN AVERAGE RATE OF 138 LBS. PER SQ.YD.
C2	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ.YD.
J	FOR ALL WIDENING, REMOVE 10" DEPTH MATERIAL AND REPLACE WITH ASPHALT MILLINGS, AGGREGATE BASE COURSE OR A COMBINATION OF THESE. PROP. 10" FULL DEPTH RECLAMATION, USING A CEMENT RATE OF 57 LBS. PER SQ. YD.
K	PROP. 10" FULL DEPTH RECLAMATION, USING A CEMENT RATE OF 57 LBS. PER SQ. YD.

