DocuSign Envelope ID: E5CDA255-FE9F-47F9-A30E-473982E4376D

12/06/07

COMPUTED BY: bam DATE: 12/2/14
CHECKED BY: _____ DATE: _____

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
17BP.1.R.65	3-A

SUMMARY OF EARTHWORK

STATION	STATION	UNCL. EXCAV.	EMBANK. +%	BORROW	WASTE
–L– STA. 10+70.00	–L– STA. 13+49.77	8	105	97	
SUBTOTALS:		8	105	97	
–L– STA. 14+42.23	–L– STA. 16+95.00	9	47	38	
SUBTOTALS:		9	47	38	
PROJECT SUBTOTALS:		17	152	135	
LOSS DUE TO CLEARING & GRUBBING					
PROJECT TOTALS:		17	152	135	
5% TO REPLACE TOPSOIL ON BORROW PIT				7	
GRAND TOTALS:		17		142	
SAY:		50		200	

CONTINGENCY ITEMS
UNDERCUT EXCAVATION – 50 CY
GEOTEXTILE FOR SOIL STABILIZATION – 175 SY
SELECT GRANULAR MATERIAL – 50 CY
SUBDRAIN EXCAVATION – 23 CY
SUBDRAIN FINE AGGREGATE – 17 CY
6" PERFORATED SUBDRAIN PIPE – 100 LF
6" OUTLET PIPE – 6 LF
SUBDRAIN PIPE OUTLET – 1 EACH

PAVEMENT REMOVAL SUMMARY

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD²
–L–	13+30.00	13+61.37	CL	69.53
–L–	14+31.06	14+60.00	CL	67.24
			TOTAL:	136.77
			SAY:	150.00

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	PERM. DRAIN. EASE.	TEMP. DRAIN. EASE.
1	MARYLAND C. BOYCE, III & WADE H. BOYCE		717.91 SF					
2	BARBARA J. SYMONS		1,082.54 SF					
3	CECIL H. PERRY, ET UX		3,334.85 SF					

SHOULDER BERM GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LENGTH
–L– LT.	13+22.50	13+35.69	13.19'
–L– LT.	14+50.15	14+62.50	12.35'
–L– RT.	13+29.50	13+41.85	12.35'
–L– RT.	14+56.31	14+69.50	13.19'
		TOTAL:	51.08'
		SAY:	60.00'

SUB–REGIONAL & REGIONAL LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

NOTE: INVERT ELEVATIONS INDICATED ARE FOR BID PURPOSES ONLY AND SHALL NOT BE USED FOR PROJECT CONSTRUCTION STAKEOUT. SEE "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES, SECTION 300–5".

| STATION | LOCATION (LT,RT, OR CL) | STRUCTURE NO. FROM | STRUCTURE NO. TO | TOP ELEVATION | INVERT ELEVATION | INVERT ELEVATION | SLOPE CRITICAL | DRAINAGE PIPE (RCP, CSP, CAAP, HDPE, or PVC) SIZE / THICKNESS OR GAUGE | | | | | | | | | | | | C.S. PIPE SIZE / THICKNESS OR GAUGE | | | | | | | R.C. PIPE (CLASS III) SIZE | | | | | | | R.C. PIPE (CLASS IV) SIZE | | | | | | | *** R. C. PIPE (CLASS V) | *** R. C. PIPE CULVERTS, CONTRACTOR DESIGN PIPE | *** R. C. PIPE CULVERTS, CONTRACTOR DESIGN PIPE | 15" SIDE DRAIN PIPE | 18" SIDE DRAIN PIPE | ENDWALLS STD. 838.01, STD. 838.11 OR STD. 838.80 (UNLESS NOTED OTHERWISE) CU. YDS. | | QUANTITIES FOR DRAINAGE STRUCTURES * TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. "A" + (1.3 X COL. B') LIN. *FT. | | | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES AND HOOD STANDARD 840.03 TYPE OF GRATE | | | | CONCRETE TRANSITIONAL SECTION | | C.B. STD. 840.18 OR 840.27 | G.D.I. TYPE "B" STD. 840.18 OR 840.24 | G.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24 | T.B.D.I. STD. 840.35 | G.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.29 | M.H. FRAME & COVER STD. 840.54 | J.B. STD. 840.31 OR 840.32 | CORR. STEEL ELBOWS NO. & SIZE | CONC. COLLARS CL. "B" C.Y. STD. 840.72 | CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71 | PIPE REMOVAL LIN.FT. | REMARKS |
|---|---|---|---|---|---|---|---|---