RAL-WS024 12/3/2014 P:\2013\13134.01 Pasquotank #29\Roadway\Xsc\XSC Earthwork Volumes.xls
DocuSign Envelope ID: E5CDA255-FE9F-47F9-A30E-473982E4376D

PROJ. REFERENCE NO.	SHEET NO.
17BP.1.R.65	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+70.00	0	0
11+00.00	2	1
11+20.00	1	2
11+50.00	2	4
12+00.00	2	10
12+50.00	1	13
13+00.00	0	22
13+49.77	0	29

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+42.23	0	0
15+00.00	1	20
15+50.00	1	11
16+00.00	2	4
16+45.00	2	1
16+95.00	3	0

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".