DocuSign Envelope ID: 17EC9C75-4531-428F-8D3D-411DA04FD1FF



PLAN @ END BENT NO. 1

PLAN @ END BENT NO. 2

ESTIMATED QUANTITIES		
BRIDGE @ STA. 17+05.00 -L-	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
END BENT 1	53	58
END BENT 2	46	51
TOTAL	99	109

NORTH CAROLINA PROFESSIONAL SEAL ENGINEER THOMAS PAUL GARRETT 018030
5/19/2018 9:59:56 AM PDT

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

V&M
Vaughn & Melton
Consulting Engineers
Asheville, North Carolina
828-253-2796
Raleigh, NC 919-977-9455
Boone, NC 828-355-9933
Tri-Cities, TN 423-467-8401
Knoxville, TN 865-546-5800
Spartanburg, SC 864-574-4715
Charleston, SC 843-974-5650
Middlesboro, KY 606-248-6600
Charlotte, NC 704-357-0488
Atlanta, GA 770-627-3509
Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved



SECTION H-H



℄ SECTION
BERM RIP RAPPED



SECTION C-C

PROJECT NO. 17BP.1.R.77
GATES COUNTY
STATION: 17+05.00 -L-

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
RIP RAP DETAILS

ASSEMBLED BY : WDC	DATE : 1-2018
CHECKED BY : TPG	DATE : 3-2018
DRAWN BY : REK 1/84	REV. 5/1/06R TLA/GM
CHECKED BY : RDU 1/84	REV. 10/1/11 MAA/GM
	REV. 12/21/11 MAA/GM

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-12
1			3			TOTAL SHEETS
2			4			13

STD. NO. RR1