

September 28, 2016

Addendum No. 1

Contract No.: DA00308

WBS Element: 33791.3.1, ETC.

Sidewalk and Drainage Structure Repairs on US17 in Pasquotank County

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.

The following revision has been made to the proposal:

Page No. 27 "Department Furnished Materials" has been revised to remove the 30" RCP form the list of items furnished by the Department. Please void existing Page No. 27 and replace with revised Page No. 27.

If you choose the "Electronic Bid Preparation with Manual Delivery Method" or "Traditional Paper Bid Method," please acknowledge receipt of Addendum #1 in the space provided on the Addendum Acknowledgement Form.

If you choose the "Electronic Bid Preparation with Manual Delivery Method," place DA00308.001 in the same folder with DA00308.EBS, so that Expedite Bid will properly apply the addendum.

Sincerely,

-DocuSigned by:

-99A5A272ED6A447...

W. B. Be

W. B. Hobbs, PE Division Project Manager

WBH/ces Attachment

cc: A. W. Roper, PE

C. S. Mebane, PE R. W. Midgett, PE

ROADWAY SPECIAL PROVISIONS

DEPARTMENT FURNISHED MATERIALS

The Department will furnish the following surplus materials to be utilized in completing the work associated with this project;

Precast Box (1Ea) 56"x36"x41"

Precast Box (1Ea) 61"x48"x47"

RCP (2 Joints) 30"dia x 16'

These materials are located within the project limits at 1111 North Road Street, US 17. The Contractor will be responsible for moving the materials to the installed location. In the event these materials are unusable, the Contractor will supply necessary materials for this project. The Department will remove and dispose of non-utilized materials from the above list. The Contractor is advised to inspect these materials for applicability prior to bid.

No direct payment or credit will be made for the Department furnishing the above referenced materials. The Contractor shall adjust the Unit Price Bid for Line Items where these materials are utilized.

EROSION AND SEDIMENT CONTROL/STORMWATER CERTIFICATION:

(1-16-07) (Rev 9-18-12)

105-16, 225-2, 16

SP1 G180

General

Schedule and conduct construction activities in a manner that will minimize soil erosion and the resulting sedimentation and turbidity of surface waters. Comply with the requirements herein regardless of whether or not a National Pollution discharge Elimination System (NPDES) permit for the work is required.

Establish a chain of responsibility for operations and subcontractors' operations to ensure that the *Erosion and Sediment Control/Stormwater Pollution Prevention Plan* is implemented and maintained over the life of the contract.

- (A) Certified Supervisor Provide a certified Erosion and Sediment Control/Stormwater Supervisor to manage the Contractor and subcontractor operations, insure compliance with Federal, State and Local ordinances and regulations, and manage the Quality Control Program.
- (B) *Certified Foreman* Provide a certified, trained foreman for each construction operation that increases the potential for soil erosion or the possible sedimentation and turbidity of surface waters.