RAL-WS065 8/7/2017 R:\Roadway\CorridorModeling\Earthwork XSC Volume Summary.xls
DocuSign Envelope ID: AFA88402-C017-432F-8802-B9A29E6F43C9

PROJ. REFERENCE NO.	SHEET NO.
17BP.1.R.82	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+47.29	0	0
10+50.00	0	0
11+00.00	3	4
11+50.00	2	5
12+00.00	1	23
12+50.00	0	47

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	0	19
15+00.00	1	8
15+50.00	1	6
16+00.00	0	14
16+50.00	1	14
17+00.00	2	6
17+26.93	1	1

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+63.97	0	0
13+00.00	15	8
13+50.00	15	16
14+00.00	8	24
14+50.00	5	34
15+00.00	2	32
15+50.00	0	33
15+53.06	0	3