Docusign Envelope ID: 969A271C-E358-81D9-811B-35DE57623FC2

COMPUTED BY: Thein Tun Zan DATE: 11-06-2025
CHECKED BY: Jinyoung Park DATE: 11-06-2025

(9-17-24)

PROJECT NO.	SHEET NO.
BP1-R014	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	200
				TOTAL LF:	200

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF ROCK PLATING

LINE	Beginning Slope (H:V)	Approx. Station	Ending Slope (H:V)	Approx. Station	Location LT/RT	Rock Plating Detail No. 1/2/3/4	Riprap Class* 1/2/B	Rock Plating SY
-L-	1.5:1	14+75	2.5:1	15+90	LT	1	*	120
							TOTAL SY:	120

*Use Class 1, 2 or B riprap if riprap class is not shown for rock plating location.