PROJ. REFERENCE NO.	SHEET NO.
BP1-R014	X-1

Approximate quantities only. Unclassified excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+40.00	0	0
10+50.00	1	0
10+75.00	1	1
11+00.00	3	1
11+25.00	7	1
11+50.00	7	1
11+75.00	3	1
12+00.00	1	2
12+25.00	0	4
12+50.00	0	12
12+75.00	0	23
13+00.00	0	35
13+25.00	0	53
13+50.00	0	71
13+75.00	0	69
13+96.88	0	55

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+69.13	0	0
14+75.00	0	15
15+00.00	0	78
15+25.00	0	110
15+50.00	0	122
15+75.00	0	116
16+00.00	0	101
16+25.00	0	74
16+50.00	0	48
16+75.00	0	27
17+00.00	0	11
17+25.00	0	6
17+50.00	1	3
17+75.00	1	2
18+00.00	1	2
18+25.00	1	2
18+50.00	1	1
18+65.00	1	1