

2026CPT.01.05.10461, 2026CPT.01.05.20461, 2026CPT.01.05.20462

TIP NO

10.452 MILES

FED AID NO STATE FUNDED

MLLING, RESRFCING, SHLDR RCNST, RUMBLE STRIPS, PVMNT MRK

3 SECTIONS OF PRIMARY & 4 SECTIONS OF SECONDARY ROADS

			C D ROSE CONSTRUCTION LLC KITTY HAWK, NC	FSC II LLC DBA FRED SMITH COMPANY RALEIGH, NC	BARNHILL CONTRACTING CO ROCKY MOUNT, NC		
ROADWAY ITEMS							
0001	0000100000-N	800	MOBILIZATION	Lump Sum	101,893.00	84,700.00	120,000.00
0002	0106000000-E	230	BORROW EXCAVATION	360 CY	22.00 7,920.00	20.00 7,200.00	45.00 16,200.00
0003	1220000000-E	545	INCIDENTAL STONE BASE	230 TON	69.00 15,870.00	70.00 16,100.00	75.00 17,250.00
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	4 SMI	2,100.00 8,400.00	2,850.00 11,400.00	2,500.00 10,000.00
0005	1260000000-E	SP	AGGREGATE SHOULDER BORROW	14 TON	69.00 966.00	70.00 980.00	100.00 1,400.00
0006	1297000000-E	607	MILL ASP PVMT ***** DTH (1-1/2")	129,813 SY	0.74 96,061.62	0.75 97,359.75	2.25 292,079.25
0007	1330000000-E	607	INCIDENTAL MILLING	9,592 SY	2.09 20,047.28	7.25 69,542.00	8.50 81,532.00
0008	1519000000-E	610	ASP CONC SURF CRS S9.5B	2,227 TON	58.00 129,166.00	60.00 133,620.00	71.50 159,230.50
0009	1523000000-E	610	ASP CONC SURF CRS S9.5C	12,737 TON	56.00 713,272.00	63.00 802,431.00	71.50 910,695.50
0010	1575000000-E	620	ASP FOR PLANT MIX	906 TON	560.00 507,360.00	600.00 543,600.00	606.00 549,036.00
0011	1705000000-E	SP	PATCHING EXIST PAVEMENT (FULL DEPTH)	208 TON	210.00 43,680.00	215.00 44,720.00	300.00 62,400.00
0012	1881000000-E	SP	GENERIC PAVING ITEM (LF) SINUSOIDAL MILLED RUMBLE STRIPS, (18")	10,032 LF	1.54 15,449.28	0.68 6,821.76	0.46 4,614.72
0013	1881000000-E	SP	GENERIC PAVING ITEM (LF) SINUSOIDAL MILLED RUMBLE STRIPS, (8")	20,064 LF	0.76 15,248.64	0.68 13,643.52	0.46 9,229.44
0014	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	182 SF	10.00 1,820.00	8.50 1,547.00	8.05 1,465.10
0015	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum	32,404.96	13,737.37	20,000.00
0016	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	138,515 LF	0.59 81,723.85	0.56 77,568.40	0.56 77,568.40
0017	4709000000-E	1205	24"WIDE THERMO 90 MILS	260 LF	7.29 1,895.40	14.40 3,744.00	14.40 3,744.00
0018	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	16 EA	96.58 1,545.28	150.00 2,400.00	150.00 2,400.00
0019	4810000000-E	1205	PAINT PVMT MARKINGS 4"	172,835 LF	0.09 15,555.15	0.12 20,740.20	0.12 20,740.20
0020	4835000000-E	1205	PAINT PVT MKG LINES 24"	260 LF	4.82 1,253.20	8.05 2,093.00	8.05 2,093.00
0021	4845000000-N	1205	PAINT PVT MKG SYMBOL	16 EA	62.70 1,003.20	66.30 1,060.80	66.30 1,060.80
0022	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES, (4", 65 MILS)	34,320 LF	0.34 11,668.80	0.31 10,639.20	0.31 10,639.20
0023	4898000000-N	1251	GENERIC PAVEMENT MARKING ITEM (EA) 1251 POLYCARBONATE H-SHAPED MARKERS	535 EA	52.40 28,034.00	40.00 21,400.00	40.00 21,400.00
0024	6084000000-E	1660	SEEDING AND MULCHING	1.9 ACR	2,750.00 5,225.00	2,750.00 5,225.00	2,750.00 5,225.00
0025	6117000000-N	1675	RESPONSE FOR EROS CONTROL	3 EA	1.00 3.00	500.00 1,500.00	500.00 1,500.00
CONTRACT TOTAL				TOTAL	1,857,465.66	TOTAL 1,993,773.00	TOTAL 2,401,503.11
ROADWAY ITEMS				SUB-TOTAL	1,857,465.66	SUB-TOTAL 1,993,773.00	SUB-TOTAL 2,401,503.11

BIDDERS IN ORDER

C D ROSE CONSTRUCTION LLC
 FSC II LLC DBA FRED SMITH COMPANY
 BARNHILL CONTRACTING CO

1
2
3

CONTRACT TOTAL

1,857,465.66
 1,993,773.00
 2,401,503.11

DocuSigned by:

Mark S. Winslow

37ED002D8DDF4B4...

12/05/2025