

TIP NO

27.193 MILES

FED AID NOSTATE FUNDED

RESUEFACING, THIN-LIFT, SHOULDER RECONSTRUCTION, PAVE MARK

VARIOUS SECONDARY ROUTES

C D ROSE CONSTRUCTION LLC						FSC II LLC DBA FRED SMITH COMPANY		BARNHILL CONTRACTING CO			
KITTY HAWK, NC						RALEIGH, NC		ROCKY MOUNT, NC			
ROADWAY ITEMS											
0001	0000100000-N	800	MOBILIZATION	Lump Sum		182,009.00		192,000.00		194,900.00	
0002	0106000000-E	230	BORROW EXCAVATION	562 CY	36.00	20,232.00	55.00	30,910.00	90.00	50,580.00	
0003	1220000000-E	545	INCIDENTAL STONE BASE	491 TON	72.00	35,352.00	102.00	50,082.00	85.00	41,735.00	
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	40.28 SMI	2,300.00	92,644.00	2,500.00	100,700.00	2,000.00	80,560.00	
0005	1330000000-E	607	INCIDENTAL MILLING	1,740 SY	12.00	20,880.00	10.00	17,400.00	11.00	19,140.00	
0006	1519000000-E	610	ASP CONC SURF CRS S9.5B	27,949 TON	63.00	1,760,787.00	63.00	1,760,787.00	65.00	1,816,685.00	
0007	1520000000-E	SP	ASP CONC SURF CRS S9.5B LEVEL	24 TON	180.00	4,320.00	105.00	2,520.00	200.00	4,800.00	
0008	1575000000-E	620	ASP FOR PLANT MIX	1,835 TON	520.00	954,200.00	500.00	917,500.00	556.00	1,020,260.00	
0009	1705000000-E	SP	PATCHING EXIST PAVEMENT (FULL DEPTH)	320 TON	240.00	76,800.00	300.00	96,000.00	250.00	80,000.00	
0010	1775500000-E	660	AST, MAT COAT, #*** STONE (#67)	80,785 SY	1.49	120,369.65	2.00	161,570.00	1.49	120,369.65	
0011	1838000000-E	660	EMULSION FOR AST	33,122 GAL	2.52	83,467.44	1.25	41,402.50	2.52	83,467.44	
0012	2845000000-N	858	ADJ METER OR VALVE BOXES	2 EA	300.00	600.00	1,200.00	2,400.00	300.00	600.00	
0013	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	1,454 SF	8.00	11,632.00	5.00	7,270.00	6.30	9,160.20	
0014	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		138,849.20		222,980.50		123,000.00	
0015	4709000000-E	1205	24"WIDE THERMO 90 MILS	44 LF	35.00	1,540.00	40.00	1,760.00	35.00	1,540.00	
0016	4720000000-E	1205	THERMO PVT MKG CHARACTER 90	6 EA	200.00	1,200.00	225.00	1,350.00	200.00	1,200.00	
0017	4810000000-E	1205	PAINT PVT MKG MARKINGS 4"	406,840 LF	0.11	44,752.40	0.11	44,752.40	0.11	44,752.40	
0018	4835000000-E	1205	PAINT PVT MKG LINES 24"	44 LF	10.00	440.00	10.00	440.00	10.00	440.00	
0019	4840000000-N	1205	PAINT PVT MKG CHARACTER	6 EA	100.00	600.00	100.00	600.00	100.00	600.00	
0020	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 55 MILS)	406,840 LF	0.34	138,325.60	0.34	138,325.60	0.34	138,325.60	
0021	4900000000-N	1251	PERM RAISED PVT MKG MARKERS	118 EA	26.00	3,068.00	30.00	3,540.00	26.00	3,068.00	
0022	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF	4.00	4,000.00	2.00	2,000.00	3.99	3,990.00	
0023	6071012000-E	1642	COIR FIBER WATTLE	280 LF	13.50	3,780.00	10.00	2,800.00	14.75	4,130.00	
0024	6084000000-E	1660	SEEDING AND MULCHING	19.5 ACR	3,200.00	62,400.00	2,200.00	42,900.00	2,775.00	54,112.50	
0025	6117000000-N	1675	RESPONSE FOR EROS CONTROL	10 EA	100.00	1,000.00	1.00	10.00	1.00	10.00	
CONTRACT TOTAL						TOTAL	3,763,248.29	TOTAL	3,842,000.00	TOTAL	3,897,425.79
ROADWAY ITEMS						SUB-TOTAL	3,763,248.29	SUB-TOTAL	3,842,000.00	SUB-TOTAL	3,897,425.79

BIDDERS IN ORDER


C D ROSE CONSTRUCTION LLC

FSC II LLC DBA FRED SMITH COMPANY

BARNHILL CONTRACTING CO

1	3,763,248.29
2	3,842,000.00
3	3,897,425.79

CONTRACT TOTAL

DocuSigned by:

37ED002D8DDF4B4...

12/10/2024