



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

November 20, 2024

Addendum No. 1

Contract No.: DA00628

WBS Element: 44847.3.3

Roadway Improvements on SR-1333 (Main St. Extension) in Pasquotank County

To Whom It May Concern:

Reference is made to the proposal and plans previously furnished for this project.


The following revisions have been made to the proposal and plans:

Page No. R1 "Lump Sum Grading" has been revised to delete the reference to "Borrow Excavation". Please replace the original Page No. R1 with the attached revised Page No. R1.

Pages No. 159 - 164 "Bid Form" have been revised to include Line Item #85 "Undercut Excavation". Please replace the original Pages No. 159 - 164 "Bid Form" with the attached revised Pages No. 159 - 164 "Bid Form".

https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=1&let_status=Advertised

Sincerely,

DocuSigned by:

37ED002D8DDF4B4...

Mark S. Winslow
Division Contract Engineer

Cc: C. W. Bridgers, Jr., PE B. Tatum
R. K. Sawyer, PE J. Hoadley
R. W. Midgett, PE
M. B. Gill, PE
B. N. Braswell, PE
D. B. Otts, PE
C. A. Spear, PE

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION ONE
113 AIRPORT DRIVE, SUITE 100
EDENTON, NC 27932

Telephone: (252) 482-1850
Fax: (252) 482-8722
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
113 AIRPORT DRIVE, SUITE 100
EDENTON, NC 27932

PROJECT SPECIAL PROVISIONS**ROADWAY****NOTE TO CONTRACTOR:**

The Contractor must cooperate with State forces working within the limits of this project as directed by the Engineer. The Department reserves the right to make, at any time during the progress of the work, such alterations in plans or the details of construction as may be found necessary or desirable by the Engineer to complete the project. The Contractor shall maintain access to driveways for all residents and property owners throughout the life of the project. The Contractor shall be responsible for maintaining the project as directed by Section 104-10 in the *2024 Standard Specifications*.

The Contractor shall be responsible for returning any disturbed areas back to its original condition. This work may include, but will not be limited to, grading, seeding and mulching, etc. All materials and labor necessary to perform the above-mentioned work will be considered incidental to the various contract items and no direct payment will be made for these activities.

The quantities shown in the itemized proposal for the project are considered to be approximate only and are given as the basis for comparison of bids. The Department of Transportation may increase or decrease the quantity of any item or portion of the work as may be deemed necessary or expedient. An increase or decrease in the quantity of any item will not be regarded as sufficient ground for an increase or decrease in the unit prices, nor in the time allowed for the completion of the work, except as provided for the contract.

CLEARING AND GRUBBING - METHOD II:

(9-17-02)(Rev. 3-19-24)

200

SP2 R02A

Perform clearing on this project to the limits established by Method - II shown on Standard Drawing No. 200.02 of the *Roadway Standard Drawings*. Conventional clearing methods may be used except where permit drawings or conditions have been included in the proposal which require certain areas to be cleared by hand methods.

LUMP SUM GRADING:

(8-17-10)(Rev. 1-16-24)

226

SP2 R16

Lump sum grading shall be performed in accordance with Section 226 Comprehensive Grading of the *Standard Specifications* except as follows:

Delete all references to Section 230 Borrow Excavation (Item 0106).

SHOULDER AND FILL SLOPE MATERIAL:

(5-21-02)(Rev. 1-16-24)

235, 560

SP2 R45 A

Description

Perform the required shoulder and slope construction for this project in accordance with the applicable requirements of Section 560 and Section 235 of the *Standard Specifications*.

County: PASQUOTANK

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0106000000-E	230	BORROW EXCAVATION	2,800 CY		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0006	0194000000-E	265	SELECT GRANULAR MATERIAL, CLASS III	2,100 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	400 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	43 TON		
0009	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	202 SY		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	88 LF		
0011	0345000000-E	310	24" SIDE DRAIN PIPE	92 LF		
0012	0995000000-E	340	PIPE REMOVAL	169 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	410 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	370 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	420 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	500 TON		

County: PASQUOTANK

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	75 TON		
0019	1891000000-E	SP	GENERIC PAVING ITEM PAVEMENT TEXTURING	3,056 SY		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0021	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0022	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE	6 LF		
0026	2612000000-E	848	6" CONCRETE DRIVEWAY	170 SY		
0027	3030000000-E	862	STEEL BEAM GUARDRAIL	537.5 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0030	3628000000-E	876	RIP RAP, CLASS I	80 TON		
0031	3649000000-E	876	RIP RAP, CLASS B	30 TON		
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	325 SY		
0033	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	40.5 SF		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	31 LF		

County: PASQUOTANK

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0036	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	349 SF		
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0039	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0040	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0041	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,860 LF		
0042	5325400000-E	1510	4" WATER LINE	181 LF		
0043	5325600000-E	1510	6" WATER LINE	451 LF		
0044	5326600000-E	1510	16" WATER LINE	341 LF		
0045	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	2,880 LB		
0046	5538000000-E	1515	4" VALVE	2 EA		
0047	5562000000-E	1515	*** INSERTION VALVE (16")	2 EA		
0048	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0049	5686500000-E	1515	WATER SERVICE LINE	52 LF		
0050	5810000000-E	1530	ABANDON 16" UTILITY PIPE	330 LF		
0051	5836000000-E	1540	24" ENCASMENT PIPE	95 LF		

County: PASQUOTANK

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	5872500000-E	1550	BORE AND JACK OF *** (24")	95 LF		
0053	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (6")	451 LF		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	1,350 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	465 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	140 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0062	6029000000-E	SP	SAFETY FENCE	320 LF		
0063	6030000000-E	1630	SILT EXCAVATION	590 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,535 SY		
0065	6037000000-E	1629	COIR FIBER MAT	100 SY		
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	5 LF		
0067	6045000000-E	SP	*** TEMPORARY PIPE (24")	155 LF		
0068	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	65 SY		

County: PASQUOTANK

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0070	6071002000-E	1642	FLOCCULANT	150 LB		
0071	6071012000-E	1642	COIR FIBER WATTLE	530 LF		
0072	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0073	6087000000-E	1660	MOWING	3 ACR		
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0078	6111000000-E	SP	IMPERVIOUS DIKE	70 LF		
0079	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0080	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	13 EA		
0081	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0085	0036000000-E	225	UNDERCUT EXCAVATION	1,600 CY		
CULVERT ITEMS						
0082	8130000000-N	414	BOX CULVERT EXCAVATION, STA ***** (21+60)	Lump Sum	L.S.	
0083	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	112 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	8804000000-N	SP	GENERIC CULVERT ITEM ALUMINUM BOX CULVERT 23'-0" x 6'-1"	Lump Sum	L.S.	

1221/Nov20/Q31594.5/D349400714000/E85

Total Amount Of Bid For Entire Project :