DocuSign Envelope ID: 3F210419-10E7-418B-B9DE-EFEABE23958E

# RIGHT OF WAY CONTROL SHEET

| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| 17.BP.1.R.99 | RW03E-1 |

## Location and Surveys

LOCATION & SURVEYS
DIVISION 1
1300 US HWY 64 W
PLYMOUTH, NC 27962

PROJECT SURVEYOR

NORTH CAROLINA PROFESSIONAL SEAL L-5327 LAND SURVEYOR LINWOOD T. DOWNS III

DocuSign by: Linwood T. Downs III
8/25/2021 | 12:24 PM EDT

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

I , Linwood T. Downs III , certify that the right of way and permanent easement monumentation for this project shown herein was completed under my direct and responsible charge from an actual survey made under my supervision; that all horizontal closures had a minimum ratio of precision of 1:10,000 (Class A). Field work was performed on July 15, 2021, and all coordinates are based on NAD83/2011; That this survey was performed to meet the requirements of 21NCAC 56.1600 as applicable.

This 25th day of August, 2021.

DocuSign by: Linwood T. Downs III
Professional Land Surveyor L-5327

NORTH CAROLINA PROFESSIONAL SEAL L-5327 LAND SURVEYOR LINWOOD T. DOWNS III

ROW MARKER IRON PIN AND CAP-E

| | ALIGN | STATION | OFFSET | NORTH | EAST |
|---|---|---|---|---|---|
| | EL | 13+92.00 | 30.00 | 928493.8847 | 2790099.8125 |
| | EL | 13+92.00 | 40.00 | 928486.5677 | 2790092.9963 |
| | EL | 15+05.00 | -30.00 | 928460.7639 | 2790223.3925 |
| | EL | 15+05.00 | -40.00 | 928468.0810 | 2790230.2087 |
| | EL | 17+30.00 | 40.00 | 928256.1799 | 2790340.3128 |
| | EL | 17+30.00 | 45.00 | 928252.5213 | 2790336.9047 |
| | EL | 18+25.00 | 45.00 | 928187.7674 | 2790406.4168 |
| | EL | 18+25.00 | 40.00 | 928191.4259 | 2790409.8249 |
| * | EL | 20+10.00 | 40.00 | 928065.3261 | 2790545.1904 |
| | EL | 20+10.00 | 30.00 | 928072.6431 | 2790552.0066 |
| | EL | 21+15.00 | -40.00 | 928052.2923 | 2790676.5492 |
| | EL | 21+15.00 | -30.00 | 928044.9753 | 2790669.7330 |

ROW MARKER PERMANENT EASEMENT-E

| | ALIGN | STATION | OFFSET | NORTH | EAST |
|---|---|---|---|---|---|
| | EL | 16+25.00 | 40.00 | 928327.7500 | 2790263.4837 |
| | EL | 16+25.00 | 40.00 | 928327.7500 | 2790263.4837 |
| | EL | 16+31.00 | 60.00 | 928309.0247 | 2790254.2402 |
| | EL | 17+02.00 | 60.00 | 928260.6297 | 2790306.1913 |
| * | EL | 17+10.00 | 40.00 | 928269.8123 | 2790325.6787 |

* = NOT SET DUE TO INACCESSIBILITY

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
3. RIGHT OF WAY MONUMENTATION ESTABLISHED ON JULY 15, 2021.

REVISIONS

6/2/99

30-AUG-2021 16:15
R:\Row_Import_Non-NBIS Bridges\690025_Pasquotank (17bp.1.r.99)\Control\Control Sheets\E-Sheets\690025_ls_rw02d-1.dgn
ltdowns AT LS-31565