



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

November 25, 2024

Addendum No. 1

Contract No.: DA00629

WBS Element: BP1.R017.3

Replacement of Bridge #53 on SR-1312 (St. John Church Rd) over Occoneechee Creek in Northampton County

To Whom It May Concern:


Reference is made to the proposal and plans previously furnished for this project.

The following revisions have been made to the proposal:

Pages No. 119 - 123 "Bid Form" have been revised to include Line Item #76 "Shoulder Berm Gutter". Please replace the original Pages No. 119 - 123 "Bid Form" with the attached revised Pages No. 119 - 123 "Bid Form".

https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=1&let_status=Advertised

Sincerely,

DocuSigned by:

37ED002D8DDF4B4...

Mark S. Winslow
Division Contract Engineer

Cc: C. W. Bridgers, Jr., PE
R. K. Sawyer, PE
R. W. Midgett, PE
M. B. Gill, PE
B. N. Braswell, PE
D. B. Otts, PE
M. R. Hill, PE
C. B. Johnson, PE
J. Morris

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0248000000-N	SP	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STATION (14+62.50 -L-)	Lump Sum	L.S.	
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0010	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	30 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	32 LF		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	52 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	10 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	310 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	494 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	224 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	37 TON		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0019	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0020	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0025	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0026	3030000000-E	862	STEEL BEAM GUARDRAIL	200 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	315 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	238 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,820 LF		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	1,270 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	140 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	55 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6029000000-E	SP	SAFETY FENCE	720 LF		
0045	6030000000-E	1630	SILT EXCAVATION	190 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
0047	6037000000-E	1629	COIR FIBER MAT	100 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	95 LF		
0049	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	450 SY		
0050	6071002000-E	1642	FLOCCULANT	30 LB		
0051	6071012000-E	1642	COIR FIBER WATTLE	30 LF		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6071014000-E	1642	COIR FIBER WATTLE BARRIER	100 LF		
0053	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0054	6087000000-E	1660	MOWING	0.5 ACR		
0055	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0058	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0060	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	5 EA		
0061	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0076	2556000000-E	846	SHOULDER BERM GUTTER	193 LF		
STRUCTURE ITEMS						
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+62.50 -L-)	Lump Sum	L.S.	
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+62.50 -L-)	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.6 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+62.50 -L-)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,916 LB		

County: NORTHAMPTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0067	8328400000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** GALVANIZED STEEL PILES (HP 12 X 53)	10 EA		
0068	8365000000-E	450	HP 12 X 53 GALVANIZED STEEL PILES	900 LF		
0069	8393000000-N	450	PILE REDRIVES	5 EA		
0070	8394000000-N	450	DYNAMIC PILE TESTING	1 EA		
0071	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	150 LF		
0072	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	225 TON		
0073	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	250 SY		
0074	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0075	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	750 LF		

1325/Nov25/Q18499.75/D341584328000/E76

Total Amount Of Bid For Entire Project :