

APRIL 27, 2015

TO: PROSPECTIVE BIDDERS  
FROM: GABE DOBBS, PROJECT ENGINEER (KIMLEY-HORN) ON BEHALF OF TOWN OF MATTHEWS  
SUBJECT: ADDENDUM 3 – WBS 39077.3.F3 (MUNICIPAL CONTRACT FOR U-4713B CAMPUS RIDGE RD. REALIGNMENT) – Additional Questions from Bidders

The following responses are from questions by contractors:

Question #1 - While review SP-06 it appears that a number of Contract Line Items are listed in the "Measurement and Payment" section but under the "Pay Item" heading it appears that only two of the items listed will be paid, please explain.

It also appears that items for coir fiber mat and coir fiber baffles need to be added based on the descriptions in SP-06

Answer #1 – Items listed in SP-06 and subsequent instructions are to clarify the intent of the design and materials used for construction of the skimmer basins shown in the plans. Most of these items are measured and paid for according to NCDOT Standard Specifications items, as is specifies in the language of SP-06. The quantities of these items have been accounted for in the standard line item bid quantities.

Coir fiber mat, for clarification, is a matting type typically used for construction of these basins, and is accounted for in Pay Item 53 "Matting for Erosion Control". No additional item needed for coir fiber mat. A pay item and quantity has been added to the attached bid schedule of prices Page 2 – Pay Item 50B "Coir Fiber Baffles".

-END OF ADDENDUM #3

Attachments:

-Updated Bid Schedule of Prices – Page 2

CC: Mr. Ritchie Hearne, P.E.  
Mr. Terry Burleson, P.E.  
Ralph Messera, Public Works Director - Town of Matthews  
Benjamin Taylor, P.E. (Kimley-Horn)

**SCHEDULE OF PRICES – Page 2**

		<b>EROSION CONTROL ITEMS</b>			
43	1660	SEEDING & MULCHING	9	AC	
44	310	18" TEMP PIPE	156	LF	
45	310	24" TEMP PIPE	351	LF	
46	1639	SPECIAL STILLING BASIN	2	EA	
47	SP-5	IMPERVIOUS DKE	100	LF	
48	SP-4	PERMANENT SOIL REINFORCEMENT MAT	20460	SY	
49	SP-6	2" SKIMMER	3	EA	
50	SP-6	2.5" SKIMMER	4	EA	
50B	1640	COIR FIBER BAFFLES	520	LF	
51	1605	TEMPORARY SLT FENCE	4186	LF	
52	1630	SILT EXCAVATION	1650	CY	
53	1631	MATTING FOR EROSION CONTROL	550	SY	
54	1610	SEDIMENT CONTROL STONE	390	TON	
55	1610	STONE FOR EROSION CONTROL, CLASS A	100	TON	
56	1610	STONE FOR EROSION CONTROL, CLASS B	805	TON	
57	876	RIP-RAP, CLASS 1	167	TON	
58	1632	1/4" HARDWARE CLOTH	250	LF	
59	1615	TEMPORARY MULCHING	7	AC	
60	1620	SEED FOR TEMPORARY SEEDING	950	LB	
61	1620	FERTILIZER FOR TEMPORARY SEEDING	3.5	TN	
62	1622	TEMPORARY SLOPE DRAIN	190	LF	
		<b>TRAFFIC CONTROL ITEMS</b>			
63	SP-3	TRAFFIC CONTROL	1	LS	
					SUBTOTAL =
					10% Contingency =
					<b>TOTAL =</b>